

AIM ENGINEERING & SURVEYING, INC.
Lee County MSBTU: Cherry Estates Road Re-surfacing Project
Bid Schedule

March, 2018

Road Resurfacing

No.	ITEM DESCRIPTION	QTY	UNIT	UNIT PRICE	CONTRACT AMOUNT
101-1	Mobilization with pre-construction video	1	LS		\$ -
101-2	Survey (Layout & Record Drawing Survey)	1	LS		\$ -
102	Maintenance of Traffic with provisions for access	1	LS		\$ -
104	Erosion Control Program & NPDES Permit	1	LS		\$ -
110	Removal and Disposal of Ex. Concrete Pavement	2,500	SY		\$ -
160	Stabilized Subgrade (6") LBR 40, 98% Density	2,500	SY		\$ -
285	Limerock Base (6") LBR 100, 98% Density	2,625	SY		\$ -
327	Mill Ex. Asphalt Pavement (Removal & Disposal)	16,100	SY		\$ -
334	Asphaltic Concrete (1" SP 9.5) w/prime	18,600	SY		\$ -
425	Replace Inlet top & grate	4	EA		\$ -
710	Painted, Std., White, Solid 24" Stop Bar	120	LF		\$ -
M-1	Monitoring for vibrations	1	LS		\$ -
R-1	Restoration of work areas, incl. driveways, sod, landscaping, utility pads, etc.	1	LS		\$ -

Total

Alternate

A-1	N. end Binnacle Lane- Remove Conc. Pvm't. and Replace with (6-6-1) asphaltic flexible pavement	65	SY		\$ -
-----	--	----	----	--	------

Total with Alt.

Note:

Testing for Density, Materials and LBR shall be provided separately by others under Lee County contract.