

Cherry Estates Road Re-surfacing Project

SCOPE OF WORK

This project involves the road re-surfacing and road re-construction for the Cherry Estates subdivision on Pine Island, Lee County, Florida. The work will comprise approximately, 18,600 SY of asphalt pavement wearing surface, 2,500 SY of base rock and 2,500 SY of subgrade. The existing asphaltic concrete paved roads being Binnacle Lane, Bounty Lane, Bowsprit Lane, Skipper Lane and Sloop Lane shall be milled **1 inch, regraded**, compacted, primed and re-paved. An alternative bid item is included to remove 65 square yards of concrete pavement at the north end of Binnacle Lane and replace with (6-6-1) subgrade, limerock base and asphaltic flexible pavement. Binnacle Lane and Bounty Lane are inverted crown roadways with four drainage inlets that require the top of inlet collar to be reconstructed with a new inlet grates. Harpoon Lane is currently constructed of rigid concrete pavement that shall be removed and re-constructed of a flexible asphaltic concrete pavement, base and subgrade. Included with the project are pre-construction video, survey, maintenance of traffic with access provisions, stop bars and restoration requirements.