

CONTRACT SUMMARY INFORMATION

SUMMARY: Annual Contract for Directional Bore Services

Purchase is made in accordance with the Terms & Conditions of Lee County Solicitation No. B-140176.

Solicitation No.:	B-140176
Project Title:	Annual Contract for Directional Bore Services
Contracts Analyst:	Mike Nevarez
Start Date:	8/23/14
Expiration Date:	8/22/19
Board Date:	5/6/13
Blue Sheet No.:	20140190
Term:	Two years
Renewal Options:	Three additional one-year periods
Address Book No.:	257967
Awarded Vendor:	Roberts Drilling
Contact Person:	Kevin Yochum
Phone No.:	239-693-6149

Notes: Fee Schedule Below

This Contract will be used in the event of a Disaster or Emergency also.

**ANNUAL CONTRACT FOR DIRECTIONAL
BORE SERVICES**

Bid No: B-140176

Contractor: Roberts Drilling,

ITEM #	ITEM DESCRIPTION	UNIT	QUANTITY	UNIT PRICE
DIRECTIONAL BORE OPERATION				
1	Mobilization (To include Maintenance of Traffic-MOT)	LS	1	\$250.00
2	1 - 2" Conduit	LF	1	\$9.00
3	1 - 3" Conduit	LF	1	\$11.00
4	1 - 4" Conduit	LF	1	\$15.00
5	1 - 6" Conduit	LF	1	\$25.00
6	1 - 8" Conduit	LF	1	\$40.00
7	2 - 2" Conduit	LF	1	\$12.00
8	3 - 2" Conduit	LF	1	\$15.00
9	5 - 2" Conduit	LF	1	\$22.00
10	10 - 2" Conduit	LF	1	\$40.00
11	Coupling two Directional Bore Conduits (SCR 13.5) together with E-lock coupling 2"	Per Coupling	1	\$16.00
12	Coupling two Directional Bore Conduits (SCR 13.5) together with E-lock coupling 1 1/4"	Per Coupling	1	\$14.00
13	Dewatering	LS	1	\$500.00
14	Rock Excavation	LF	1	\$10.00
15	Trench Shoring	EA	1	\$5.00
16	Restoration	EA	1	\$5.00
17	Sod	SY	1	\$5.00
18	4 - 1 1/4" sdr 13.5 Blu, Org, Grn, Yel	LF	1	\$12.50
18a	3 - 1 1/4" sdr 13.5 Blu, Org, Grn.	LF	1	\$11.00
18b	1 - 1 1/4" sdr 13.5 Conduit color optional	LF	1	\$8.50
19	4 - 2" Conduit	LF	1	\$18.00
20	1 - 4" Conduit	LF	1	\$15.00
21	4 - 1 1/4" sdr 13.5 Blu, Org, Grn, Yel & 1 - 2" Grey conduit	LF	1	\$15.50
22	4 - 1 1/4" sdr 13.5 Blu, Org, Grn, Yel & 2 - 2" Grey conduit	LF	1	\$18.50
23	1 - 1 1/4" sdr 11 conduit	LF	1	\$8.50
24	1 - 2" sdr 11 conduit	LF	1	\$9.50
25	1 - 3" sdr 11 conduit	LF	1	\$12.00
26	1 - 4" sdr 11 conduit	LF	1	\$16.00
TRENCHING FURNISH AND INSTALL				
27	4 - 1 1/4" sdr 13.5 Blu, Org, Grn, Yel	LF	1	\$4.50
28	1 - 2" Conduit	LF	1	\$3.50
29	2 - 2" Conduit	LF	1	\$4.75
30	3 - 2" Conduit	LF	1	\$6.00
31	4 - 2" Conduit	LF	1	\$7.00
32	5 - 2" Conduit	LF	1	\$8.50
33	1 - 3" Conduit	LF	1	\$3.75
34	1 - 4" Conduit	LF	1	\$4.00
35	4 - 1 1/4" sdr 13.5 Blu, Org, Grn, Yel & 1 - 2" Grey conduit	LF	1	\$6.00
36	4 - 1 1/4" sdr 13.5 Blu, Org, Grn, Yel & 2 - 2" Grey conduit	LF	1	\$6.50

ITEM #	ITEM DESCRIPTION	UNIT	QUANTITY	UNIT PRICE
TRENCHING INSTALL ONLY (MATERIAL SUPPLIED BY OTHERS)				
37	4 - 1 1/4" sdr 13.5 Blu, Org, Gm, Yet	LF	1	\$3.00
38	Installing 1 - 2" Conduit by Trenching	LF	1	\$3.00
39	Installing 2 - 2" Conduit by Trenching	LF	1	\$3.50
40	Installing 3 - 2" Conduit by Trenching	LF	1	\$4.00
41	Installing 4 - 2" Conduit by Trenching	LF	1	\$4.75
42	Installing 5 - 2" Conduit by Trenching	LF	1	\$5.50
43	Installing 1 - 3" Conduit by Trenching	LF	1	\$3.00
44	Rock Excavation	LF	1	\$10.00
45	Trench Shoring	EA	1	\$1.00
46	3 - 1 1/4" sdr 13.5 Blu, Org, Gm	LF	1	\$3.00
47	1 - 1 1/4" sdr 13.5 Conduit Color Optional	LF	1	\$3.00
48	Restoration	EA	1	\$1.00
49	Sod	SY	1	\$10.00
PULL BOX INSTALLATION (PER LEE COUNTY PLANS & SPECIFICATIONS 3.2)				
50	Small Pull Box: 17" x 30"	EA	1	\$300.00
51	Medium Pull Box: 24" x 36"	EA	1	\$550.00
52	Large Pull Box: 30" x 48"	EA	1	\$800.00
CABINET BASE INSTALLATION (PER LEE COUNTY PLANS & SPECIFICATIONS)				
53	Quartzite Cabinet Base: 40" x 58"	EA	1	\$1,800.00
54	Furnish & Install #10 Locate Wire in Existing Conduit as Directed	LF	1	\$0.40
55	Furnish & Install Pull String in Existing Conduit as Directed	LF	1	\$0.20
56	Install one conduit "any size" into existing pull box or cabinet base	EA	1	\$75.00
57	Install two conduits "any size" into existing pull box or cabinet base	EA	1	\$75.00
58	Install three conduits "any size" into existing pull box or cabinet base	EA	1	\$100.00
59	Install four conduits "any size" into existing pull box or cabinet base	EA	1	\$125.00
60	Install five conduits "any size" into existing pull box or cabinet base	EA	1	\$150.00

CONDUIT NOTES (REFERENCE LEE COUNTY PLANS & SPECIFICATIONS & FDOT STANDARDS)

* All orange 1 1/4" SDR 13.5 conduits shall have a #10 AWG stranded copper THHN wire pulled in conduit.

Three to five feet of wire shall be installed in each pull box, with wires continuous from start to end of total conduit installation. Where wire needs to be spliced a copper split bolt will be used.

* All conduits, other than 1 1/4" orange shall have a pull string installed. Pull string must be secured to side of conduit end.

* All conduits entering a pull box or cabinet base shall have duct seal installed.

* All conduit will be paid by length of run; point to point.