



North Pump Station and Ground Storage

Marina Pump Station

South Pump Station and Ground Storage

Priority 3: Replace 18-inch AC pipes from Times Square to Avenue C with PVC.

Priority 3: Replace both 8-inch and 10-inch AC pipes along Estero Blvd. with a single 12-inch PVC pipeline.

Priority 4: Replace existing 2 and 3-inch pipes with 8-inch pipes.

Priority 1: Add a new 12-inch pipe parallel to the existing 10-inch pipe to improve the area residual pressure for Bay Beach Lane.

Priority 2: Replace the existing 4-inch or smaller pipes with 8-inch pipes to improve fire protection for Buccaneer Lagoon.

Priority 3: Replace 8-inch AC pipe along Estero Blvd., South of Lenell Road, with 8-inch PVC.

**Legend**

- Existing Pipes to Remain
- 2 and 3-inch Pipes Replacement (Priority 4)
- 18-inch AC Pipe Replacement (Priority 3)
- 8 and 10-inch AC Pipes Replacement (Priority 3)
- 8-inch AC Pipe Replacement (Priority 3)
- Buccaneer Lagoon Improvements (Priority 2)
- Bay Beach Lane Improvements (Priority 1)

