



Lee County
Department of Transportation
1500 Monroe Street
Fort Myers, FL 33901
(239) 533-8580 (239) 485-8520 Fax

ROADWATCH UPDATE
June 11, 2026, to June 17, 2026

1. **Road Work/Maintenance/Improvement**

Corkscrew Road Widening Project – Phase 2 Construction Project: The project constructs four, 11-foot-wide travel lanes from Bella Terra Boulevard to just east of Alico Road, and a new traffic signal at the Alico Road intersection. Also included are on-road bike lanes in each direction, a 10-foot-wide shared-use path on the south side of the road, a 6-foot sidewalk on the north side of the road, and street lighting. The 22-foot wide (varies) median includes various hardwood and palm trees as well as shrubs.

Drivers, pedestrians, and bicyclists are urged to use extra caution when traveling through the work zone.

- As of Thursday morning, June 11, 2026, eastbound and westbound traffic has shifted to the new lanes on the south side of Corkscrew Road, from just west of Wayside Lane to east of the Corkscrew Shores main entrance. All traffic is now on the new lanes from just west of Wayside Lane to just east of Alico Road.
- Crews will be installing drainage throughout the project area on Corkscrew Road and Alico Road. Motorists should expect trucks and equipment to be moving materials throughout the project.
- Motorists should drive with caution and expect intermittent daytime flagging as road crews are performing earthwork up to the shoulders of the road on Corkscrew Road and Alico Road, within the project limits. Please be aware that trucks may be entering and leaving the roadway.
- Crews will be installing utility conduits, light pole bases and light poles on the north side of Corkscrew Road from Wayside Lane to Alico Road.
- Sidewalks are closed in areas throughout the project as the contractor performs underground work.

The work activities above are scheduled to occur, however unforeseen underground conditions and weather may affect this schedule.

Please use caution and watch for workers and construction vehicles entering and leaving the roadway. Due to additional work required by Lee County Utilities, as well as delays in utility relocations by FPL and Lumen, the project completion is expected at the end of 2026. Project cost is approximately \$27 M. The contractor is Bergeron Land Development, Inc. For further questions, please visit the project website at <https://corkscrewroadwidening.com> or contact Jennifer Dorning by email at Jennifer.Dorning@atkinsrealis.com or by phone at (239) 338-7723.

Village of Estero Corkscrew Road Shared Use Path Project: This Village of Estero project constructs a 10-foot-wide asphalt pathway on the north side of Corkscrew Road from Ben Hill Griffin Parkway to Palermo Lake Court (eastern entrance of Grandezza), and 6-foot wide concrete sidewalk from east of Palermo Lake Court that connects to the sidewalk that runs to Midnight Blue Court (Wild Blue Vista) built by Lee County's previous widening project. The 10-foot-wide asphalt pathway will also be constructed on the south side of Corkscrew Road from Ben Hill Griffin Parkway to Bella Terra Boulevard. Roadway and pathway lighting similar to those on Estero Parkway will be installed to complement the new facilities, along with a substantial amount of landscaping and irrigation which will add to the beautification of the Corkscrew Road corridor.

The sidewalk and pathway are active work zones and remain closed to pedestrians and bicyclists from Ben Hill Griffin Parkway to Midnight Blue Court/Bella Terra Boulevard.

- Motorists should expect lane closures from 8:00 AM to 3:30 PM for crews to upgrade sod to meet the Village of Estero's Corkscrew Road landscape plan and to complete irrigation throughout the project in preparation for landscape installation.
- Crews have completed light pole installation; however lighting will not be operational until closer to project completion after all electrical is installed.
- *WORK BY UTILITY COMPANIES: Various utilities are relocating utilities throughout the project. This work may require daytime lane closures within the project area.*

The work activities above are scheduled to occur, however unforeseen underground conditions and weather may affect this schedule.

Please use caution and watch for workers and construction vehicles entering and leaving the roadway. Estimated completion is Fall 2026. Project cost is approximately \$23 million, including \$4.6 million for landscaping and irrigation and \$4 million for lighting. For further questions, please contact Jennifer Dorning by email at Jennifer.Dorning@atkinsrealis.com or by phone at (239) 338-7723.

Big Carlos Pass Bridge Project – Construction Project: The project builds a new bridge over Big Carlos Pass, from Estrellita Drive on Fort Myers Beach to the Lovers Key State Park bayside entrance on Lovers Key. The new bridge replaces the existing moveable bridge over Big Carlos Pass with a fixed span bridge that provides a vertical navigation clearance of 60 feet. The new bridge has been constructed on the Gulf side of the existing bridge, and includes one travel lane in each direction, bicycle lanes, a six-foot-wide sidewalk along the north side of Estero Boulevard, and a 10-foot-wide shared use path along the south side of Estero Boulevard. A parking area with access to the Lovers Key State Park will be included on the southeast side of the bridge. The project also includes relocation of existing infrastructure for Lee County Utilities and Bonita Springs Utilities.

Boaters are reminded to avoid the construction equipment and the temporary trestle that is in the water.

Mariners are now using the navigational channel under the new bridge.

A temporary clearance gauge is available.

FISHING IS NOT PERMITTED FROM THE BIG CARLOS PASS BRIDGE

- **On Wednesday, June 17, 2026, between the hours of 8:00 PM and 10:00 PM, motorists should expect a FULL CLOSURE of the Big Carlos Pass Bridge** for crews to perform bridge work. The contractor expects the closure to last approximately one hour. Motorists are urged to plan ahead and expect delays.
- Pedestrians should follow signs to use the sidewalk on the south side of the bridge.
- The contractor is performing concrete work throughout the job including installing curb, pedestrian railing, and sidewalk. Delivery is occurring during times that are favorable for successful pours and within permit requirements.
- Vehicles are now using the newly constructed, fixed-span bridge. LeeTran trolley stops on the east side of the bridge are open for service. Pedestrian and bicyclist access is limited until the completion of span 1 (closest to Fort Myers Beach).
- Motorists should continue to expect intermittent daytime lane closures with flagging for crews to receive materials and perform utility and bridge work.
- The contractor continues dismantling the old bridge from the water.
- Crews will continue performing earthwork, and installing drainage improvements and sod throughout the project.

TRESPASSING INTO THE CONSTRUCTION SITE IS DANGEROUS AND ILLEGAL.

THIS INCLUDES THE BEACH AREA UNDER THE BRIDGE.

Pedestrians and boaters are reminded to please stay out of the work zone.

Drivers, pedestrians, and bicyclists are urged to use extra caution when traveling through the work zone as workers and construction vehicles are entering and leaving the roadway. Motorists should

expect reduced speeds throughout the project area. **Fishing is not permitted from the Big Carlos Pass Bridge.**

Estimated completion is summer 2026. Project cost is approximately \$90.8 M. The contractor is Superior Construction. For further questions, please visit the project website at <https://bigcarlosbridgeproject.com/> or contact Jennifer Dorning by email at Jennifer.Dorning@atkinsrealis.com or by phone at (239) 338-7723. For more information regarding the future parking area on the southeast side of the bridge, visit www.leegov.com/parks and click on the parks project info tool for updates.

Ortiz Avenue Widening from S.R. 884 (Colonial Boulevard) to S.R. 82 (Dr. Martin Luther King, Jr. Boulevard): This project consists of widening of Ortiz Avenue from 2 lanes to 4 lanes and constructs a six-foot sidewalk on the east side of the road and a 10-foot paved trail on the west side of the road. An on-road bike lane on both sides of the road will also be included. New street lighting will be installed, and a grass median will separate traffic. No improvements will be made at the roundabout intersection with Hanson Street. The contractor will reconstruct the roadway with drainage improvements and stormwater management facilities. Work also includes installation of new water main and installation of new reclaimed water and sewer facilities for Lee County and the City of Fort Myers.

Drivers, pedestrians, and bicyclists are urged to use extra caution when traveling through the work zone.

- During nighttime/overnight hours during the week of Sunday, June 14, 2026, **crews will shift northbound traffic to the new roadway on the east side of the corridor from Colonial Center Drive to the roundabout at Hanson Street.** Once northbound traffic has been shifted, southbound traffic will remain on the existing southbound lanes separated from the northbound traffic while crews prepare a temporary crossover. This configuration is expected to be in place through early to mid-July.
 - Flaggers will be positioned at each driveway for the overnight activities to ensure proper traffic flow when southbound traffic and northbound traffic are in a separated configuration.
 - Motorists are advised to choose alternate routes during the overnight traffic shift, when possible. Motorists driving on Ortiz Avenue should use caution and pay close attention to the new stop locations before proceeding to the live lanes.
 - Exits from The Edison Apartments, Fort Myers Seventh-Day Adventist Church and Schofield Street will be switched to Right Turn Only and will have to utilize the Hanson Street roundabout to access the southbound Ortiz Avenue lanes.

- Bruce Herd Lane will be switched to Right Turn Only.
- Motorists are advised that Six Mile Cypress Parkway has been reduced to one northbound lane from just north of Annette Way, continuing through the Colonial Boulevard intersection to Ortiz Avenue. **The lane reduction is expected to be in place through early June** as crews construct the new northbound lanes on Ortiz Avenue. The Colonial Center Drive intersection will remain accessible to motorists during this time.
- Until further notice, the entrance to the Vistas at Eastwood Apartments has been reduced to one lane in and one lane out.
- Crews are working on the new sidewalk on the west side of Ortiz Avenue, north of the roundabout. Pedestrians are advised that this area is an active construction zone and will remain closed until work has been completed.
- The existing pedestrian path between S.R. 82/Dr. Martin Luther King, Jr. Boulevard and the Vistas at Eastwood Apartments will be closed until late June for utility installations. Pedestrians are advised to follow detour signs directing them to the alternative route that utilizes Alessio Drive.
- The existing pedestrian path on the west side of Ortiz Avenue, south of the roundabout, is now closed for reconstruction. Pedestrians will be detoured onto the new sidewalk on the east side of Ortiz Avenue.
- The Contractor will be performing utility work north and south of the roundabout.
- Motorists should expect heavy truck traffic entering and exiting the project area north of the roundabout.
- The contractor is identifying existing utility locations throughout the project.
- The contractor is scheduled to survey the project during daytime hours.
- **LeeTran riders are advised of the following bus stop changes:**
 - The southbound stop just south of the Vistas at Eastwood Apartments entrance has been relocated to the north side of the entrance, next to the new alignment of the southbound traffic.
 - The temporary northbound bus stop near the Lee County Jail entrance remains near the newly constructed driveway, next to the new alignment of northbound traffic.
 - The northbound AND southbound stops just north of the Lee County Jail driveway and the northbound stop near RaceTrac are temporarily out of service.

The work activities above are scheduled to occur, however unforeseen underground conditions and weather may affect this schedule.

Motorists are asked to drive with caution and watch for workers and construction vehicles entering and leaving the work zone. Estimated completion is Late 2026. Project cost is approximately \$31 M. The contractor is OHLA USA. For further questions, please visit www.ortizavewidening.com or contact Jennifer Dorning by email at Jennifer.Dorning@atkinsrealis.com or by phone at (239) 338-7723. contact Jennifer Dorning by email at Jennifer.Dorning@atkinsrealis.com or by phone at (239) 338-7723.

Able Canal Pathway Project: The project constructs a new 12-foot-wide, 6-mile shared use pathway along the north side of Able Canal starting at the Harns Marsh access point next to 35th Street West and the Sailfish Canal and extending east to Joel Boulevard in Lehigh Acres. The purpose of the project is to facilitate accessible, non-motorized travel options for commuters and recreational users in the Able Canal corridor and within the Lehigh Acres community. Work includes an asphalt path with a pedestrian bridge, pavilions, landscaping and other amenities.

TRESPASSING INTO THE CONSTRUCTION SITE IS DANGEROUS AND ILLEGAL.

*Please be aware that the Lee County Sheriff's Office
is authorized to charge trespassers if found in the work zone.*

- Motorists should anticipate periodic lane closures on Connecticut Road, 19th Street W, Richmond Avenue and Connie Avenue while crews install new guardrail. Please use extra caution and follow the directions of flaggers.
- Crews are working on embankment, earthwork and storm drain installation between 35th Street West and Richmond Avenue North.
- Crews are installing erosion control throughout the project. Flagging and staging activity should be expected at Lehigh Acres Park, but there will be no impact to park users during construction.

The work activities above are scheduled to occur, however unforeseen underground conditions and weather may affect this schedule.

Please use caution and watch for workers and construction vehicles entering and leaving the roadway. The project began in August 2025 with estimated completion in Fall 2027. Project cost is approximately \$10.2 M. The contractor is Pavement Maintenance, LLC. For further questions, please visit <https://www.leegov.com/parks> or contact Jennifer Dorning by email at Jennifer.Dorning@atkinsrealis.com or by phone at (239) 338-7723.

I-75 at Daniels Parkway (exit 131) Interchange Improvements: FDOT is reconstructing the I-75 at Daniels Parkway interchange. The interchange improvements include reconstruction of the Daniels Parkway Interchange (Exit 131) converting it to a Diverging Diamond Interchange (DDI) design, reconstruction of the I-75 ramps, construction of pedestrian and bicycle accommodations through the interchange, installation of new signals at the ramps, and resurfacing of Daniels Parkway through the project area.

The following activities are subject to change based on weather conditions and unforeseen underground conditions.

- On Monday, June 15, 2026, starting at 8:00 PM, motorists should expect **brief full closures of eastbound and westbound Daniels Parkway and the I-75 ramps** for crews to work on overhead signals. Off-duty police officers will be onsite to assist motorists. Please use extra caution and expect delays.
- Motorists should anticipate lane closures on I-75 between 9:00 PM and 7:00 AM and on Daniels Parkway between 7:00 PM and 7:00 AM.
- Crews are working on installing temporary lighting, permanent light pole bases, and temporary signals.
- Crews are working on widening at the southbound I-75 off-ramp and Daniels Parkway.
- Crews are working on earthwork and underground drainage throughout the project area.
- Please note that the westbound lanes on Daniels Parkway are shifted slightly to the south, then back to the north. Traffic on the southbound I-75 off-ramp has also shifted to the east. Please pay attention to signs and pavement marking and drive with caution.
- Motorists are advised that the speed limit has been reduced in the project area. Please follow all posted signage.
- Pedestrian access has been shifted to the south side of Daniels Parkway. Please follow signs and proceed with caution in the work zone.
- Motorists should expect trucks and equipment to be moving materials throughout the project

Please use caution and watch for workers and construction vehicles entering and leaving the roadway. The expected completion date is summer 2028. For further questions, please visit <https://www.swflroads.com/project/446296-2> or contact Michaela Zawodny by email at Michaela.Zawodny@dot.state.fl.us or by phone at (239) 410-8174.

Bell Boulevard Sidewalk from Sunrise Boulevard to Joel Boulevard: Lee County is constructing a 6-foot sidewalk on Bell Boulevard in Lehigh Acres from Sunrise Boulevard to Joel Boulevard. This project, when complete, will provide a continuous sidewalk connecting pedestrians from SR 82 to Joel Boulevard via Bell Boulevard. The project also includes a steel pedestrian bridge over Jim Canal, concrete driveway replacements, minor roadway reconstruction, paving, drainage improvements, and pedestrian safety upgrades. Construction is scheduled to begin in late March 2026, with completion anticipated in Fall 2026. Project cost is approximately \$1.5 million. The contractor is V&H Construction.

Drivers, pedestrians, and bicyclists are urged to use extra caution when traveling through the work zone.

- Motorists should expect periodic flagging throughout the project.
- Expect single lane closures intermittently throughout the project area.
- Crews are pouring sidewalks and driveways throughout the project.

- Crews are installing and maintaining erosion control and traffic control devices throughout the project.
- The contractor is identifying existing utility locations throughout the project. Crews may be working close to the roadway. Motorists are asked to drive with caution.

The work activities above are scheduled to occur, however unforeseen underground conditions and weather may affect this schedule.

Please use caution and watch for workers and construction vehicles entering and leaving the roadway. For further questions, please visit www.leegov.com or contact Molly Schweers by email at Molly.Schweers@atkinsrealis.com or by phone at (239) 292-0497.

Estero Boulevard Hurricane Repairs (Estrellita Drive to Crescent Street) – Construction Project: This project includes repairs of damaged asphalt, curb and gutter, sidewalk, pavement, pedestrian handrail, school flashers, pedestrian signals, as well as the removal and replacement of the center drain brick pavers. The contractor will also replace ADA ramps and detectible warning surfaces.

Flamingo Street to Mound Road

- Crews continue to remove and replace the center drain brick pavers on Estero Boulevard. No extended lane closures are expected for this work, however left turns from side streets may be temporarily restricted. Please use caution as crews work close to the travel lanes.

Buccaneer Drive to Lenell Road

- Crews are currently removing damaged concrete, such as sidewalk, curb, and gutter. Extended lane closures are not anticipated for this work; however, motorists, pedestrians, and bicyclists are encouraged to slow down and use caution.

Primo Drive to Miramar Street

- Crews are scheduled to remove and replace the center drain brick pavers on Estero Boulevard. No extended lane closures are expected for this work, however left turns from side streets may be temporarily restricted. Please use caution as crews work close to the travel lanes.

Drivers, pedestrians, and bicyclists are urged to use extra caution when traveling through the work zone as workers and construction vehicles are entering and leaving the roadway. Estimated completion

is fall 2027. Project cost is approximately \$9 M. The contractor is Wright Construction Group. For further questions, please contact Jennifer Dorning by email at Jennifer.Dorning@atkinsrealis.com or by phone at (239) 338-7723. For more information www.leegov.com.

Treeline Avenue Intersection Improvements from Jetport Loop to Heartwood Boulevard: This project consists of converting a northbound left-turn lane from Treeline Avenue onto Daniels Parkway into a thru lane, converting a northbound thru lane into a second northbound right turn lane, ADA improvements at both the Daniels Parkway/Treeline Avenue and the Treeline Avenue/Intercom Lane intersections, and overall signal improvements.

The following activities are subject to change based on weather conditions and unforeseen underground conditions.

- Motorists should expect lane closures during the daytime hours of 9:00 AM to 4:00 PM on southbound Treeline Avenue for crews to work on underground utilities.

Please use caution and watch for workers and construction vehicles entering and leaving the roadway. The project begins in May 2026 with estimated completion in late 2026. Project cost is approximately \$3 million. The contractor is Ajax Paving. For further questions, please visit <https://www.leegov.com/> or contact Jennifer Dorning by email at Jennifer.Dorning@atkinsrealis.com or by phone at (239) 338-7723.

Three Oaks Parkway Extension Project Phase 2 from Indian Paint Lane to Daniels Parkway: This project consists of extending Three Oaks Parkway north in the vicinity of Indian Paint Lane to Daniels Parkway and constructs 4 lanes with a 5-foot-wide bicycle lane. Phase 2 includes 6-foot-wide sidewalks on both sides of the roadway.

- Cody Lee Road, the northern entrance to Publix Shopping Center, will close June 15, 2026, for one month, while the contractor constructs the southbound lanes of the Three Oaks Parkway Extension. The Publix Shopping Center can be accessed via the new traffic signal at Daniels Parkway and Powers Court/Apalooosa Lane or travel south on Three Oaks Parkway and follow the roundabout to the Old Fiddlesticks Boulevard access to the shopping center.
- Fiddlesticks Boulevard traffic is shifted to the new roundabout in order to access Three Oaks Parkway Extension and Daniels Parkway.

- Motorists are using the new northbound lanes of Three Oaks Parkway configured to one lane in each direction. The contractor will then build the southbound lanes for Three Oaks Parkway and the new driveway to the Publix Shopping Center.
- Motorists can use the roundabout to Old Fiddlesticks Boulevard to access the Publix Shopping Center from the south.
- Palomino Lane will reopen to traffic in conjunction with this traffic shift on Friday.
- Daniels Parkway is open to three lanes of traffic in each direction. The outside east and westbound lanes will remain closed for additional construction activities. However, the outside right-turn lanes will be open for use.

Drivers, pedestrians, and bicyclists are urged to use extra caution when traveling through the project.

All work is subject to weather conditions.

Motorists are asked to drive with caution and watch for workers and construction vehicles entering and leaving the work zone. Estimated completion is mid-2028. Project cost is approximately \$39.7 M. The contractor is EHC Construction. For further questions, please visit www.ThreeOaksExtension.com or contact Kris Cella by email at Kcella@cella.cc or by phone at (239) 337-1071.

Quinn Dean Neighborhood Stormwater Improvements Project – Construction Project: The City of Bonita Springs is working on a stormwater improvements project that will enhance drainage in the area. The project includes upgrading the existing stormwater pipes and constructing two stormwater retention ponds. As part of this project, the Bonita Springs Utilities Department will also relocate water and sewer lines. All roadways will be restored once the utilities are complete. Drivers, pedestrians, and bicyclists are urged to use extra caution when traveling through the work zone.

- Motorists should expect intermittent lane closures, road closures with possible local traffic only permitted and flagging operations during daytime hours on the following streets:
 - Dean Street
 - Tangerine Drive
 - Quinn Street
- Trucks and construction equipment will be entering and leaving the roadway; expect minor delays.

The work activities above are scheduled to occur during the duration of the project; however, unforeseen underground conditions and weather may affect this schedule.

Please use caution and watch for workers and construction vehicles entering and leaving the roadway.

Project completion is expected in fall of 2027. For further questions, please contact CMA Outreach, Inc. by email at kcella@cella.cc or by phone at (239) 337-1071.

Orange River Boulevard Sidewalk and Utility Improvements Project: The project includes water main replacement, installation of new stormwater drainage systems, addition of a new 6-foot sidewalk and curbs and upgrading lighting and pedestrian signalization in the surrounding area of Orange River Boulevard from Palm Beach Boulevard (SR 80) to east of Lorraine Drive. These improvements will enhance water reliability and improve pedestrian and traffic safety.

*Drivers, pedestrians, and bicyclists are urged to use extra caution
when traveling through the work zone.*

- The Contractor will be installing an eastbound single-lane closure on Palm Beach Boulevard for roadway restoration on the southwest corner of Palm Beach Boulevard and Orange River Boulevard. Motorists and pedestrians are advised to proceed with caution and follow the direction of signage and/or flaggers. Depending on weather conditions, overnight activities are expected to be completed on or before Thursday night, June 18, 2026.
- The Contractor will be installing curb and gutter on the southwest corner of Palm Beach Boulevard and Orange River Boulevard. Motorists and pedestrians are advised to proceed with caution and follow the direction of signage and/or flaggers.
- A pedestrian detour has been installed between Underwood Drive and Orange River Boulevard. Pedestrians using the sidewalk on the south side of Palm Beach Boulevard are advised to proceed with caution and follow the direction of signage.
- Crews will be pouring sidewalk in the Right of Way (ROW).
- Crews will be restoring roadway and placing asphalt throughout the project area.
- Crews will be working on utilities in the Right of Way (ROW) along the north and south side of Orange River boulevard. They will start at Lakeside Club Drive and work eastward. Intermittent flagging operations may be necessary.

*The work activities above are scheduled to occur; however,
unforeseen underground conditions and weather may affect this schedule.*

Please use caution and watch for workers and construction vehicles entering and leaving the roadway. Estimated completion is Fall 2026. Project cost is approximately \$3M. The contractor is Thompkins Contracting Inc. Work is expected to occur Monday through Friday from 7:00 AM to 7:00 PM; however, some night and weekend work may be necessary. For further questions, please contact Carolyn Usher by email info@OrangeRiverBlvdImprovementsProject.com or by phone at (239) 337-1071. *Please note changes to the road watch are shown above in Orange.*

Tice Street Sidewalk and Watermain Replacement Project – Construction Project: This project includes replacement of existing water mains, installation of new potable water infrastructure, and construction of new ADA-compliant sidewalks along Tice Street and surrounding areas. Additional work includes driveway restoration, minor drainage improvements, and roadway restoration within the project limits. These improvements will enhance water system reliability and improve pedestrian safety and connectivity in the area. Drivers, pedestrians, and bicyclists are urged to use extra caution when traveling through the work zone.

- Beginning June 15, 2026, possible night work may occur on Tice Street from Nuna Avenue to Ortiz Avenue.
- Motorists should expect intermittent lane closures and flagging operations during daytime and possibly nighttime hours.
- Expect one lane of traffic along Tice Street closed in periodic locations from Lynnedda Avenue to Ortiz Avenue over the next two weeks. Signs will indicate local traffic only and residents will be able to access their driveways.
- Lynnedda Avenue has been converted to a one-way-street through the duration of the project. Motorists should use caution and follow detour signs while roadway configuration is in place.
- Crews will be installing new water main along Tice Street, including valves, fittings, hydrants, and service connections.
- Crews will be performing excavation, trenching, and backfilling operations from Ortiz Avenue heading west to New York Drive.
- Crews will be constructing new concrete sidewalks, curb ramps, and ADA improvements from Ortiz Avenue heading west to New York Drive.
- Trucks and construction equipment will be entering and leaving the roadway; expect minor delays.
- Sidewalks may be closed in active work areas; pedestrians should follow posted detours from Ortiz Avenue heading west to New York Drive.

The work activities above are scheduled to occur during the duration of the project; however, unforeseen underground conditions and weather may affect this schedule.

Please use caution and watch for workers and construction vehicles entering and leaving the roadway. Project completion is expected in spring of 2027. Project cost is approximately \$3.9 M. For further questions, please contact CMA Outreach, Inc. by email at kcella@cella.cc or by phone at (239) 337-1071.

Striping Maintenance: Lee County DOT Traffic will be performing a moving operation with traffic delays on **June 11, 2026 to June 17, 2026 between the hours of 9:00 AM to 4:00 PM** (weather permitting) on the following roadways:

Crystal Drive	Park Meadows Drive
Matthew Drive	Crystal Court
Sago Avenue	Brantley Road
Palm Drive	Presidential Court
Fourth Avenue	Corporate Court
Cypress Drive	Whiskey Creek Drive
Tenth Avenue	Tanglewood Parkway
Eighth Avenue	Manchester Boulevard
Crystal Drive	McGregor Boulevard

Intersection Markings Maintenance: Intermittent Lane closures and delays are possible **June 11, 2026 to June 17, 2026 between the hours of 9:00 AM to 4:00 PM** (weather permitting) on the following roadways:

Milwaukee Boulevard	Bell Boulevard
Moore Avenue	Richmond Avenue (<i>excludes Bear Street – Greenbriar Boulevard</i>)
Gunnery Road	Homestead Road

Night work scheduled for Thursday June 11, 2026: LCDOT Traffic will be refreshing the pavement markings along Captiva Drive between the hours of **8:00 PM to 4:00 AM** (weather permitting). Motorists are advised to use caution while traveling through the area as there will be lane closures with flaggers present controlling traffic along with additional workers and equipment on the roadway.

Night work scheduled for Thursday June 18, 2026: LCDOT Traffic will be changing the existing northbound right turn lane on Del Prado Boulevard @ Hancock Bridge Parkway into a shared thru/right lane. Work includes altering existing pavement markings and swapping the existing signal head. Work will take place between the hours of **8:00 PM to 4:00 AM** (weather permitting). Motorists are advised to use caution while traveling through the area as there will be lane closures along with workers and equipment will be present on the roadway and in the intersection. After completion, crews will be refreshing pavement markings at various locations along Del Prado Blvd.

For additional information, please contact Randy Hart at DOTMarkings@leegov.com.

5019 Lee Boulevard – Lehigh (RES2025-02426 & DRV2025-01926): ONX Lehigh Acres LLC will be performing roadway and sidewalk improvements beginning **Friday, June 5, 2026, and continuing**

through November 6, 2026. Asphalt pavement, concrete sidewalk, concrete curbing, and drainage improvements will be performed. The outside (right) lane of eastbound traffic on Lee Boulevard just after Main Street will be subject to lane closures, as will one of two left turn lanes from the westbound portion of Main Street turning south onto Lee Boulevard. Periodic lane closures for eastbound and westbound lanes will occur between the hours of **7:00 PM and 6:00 AM** on weekdays. For further information, please contact Justin Howell at JHowell@ellitepermits.com. Traffic Control Products of Florida will provide maintenance of traffic services (239) 334-8888.

15220 Treeline Avenue S. – Fort Myers (ROW2025-01627): Pavement Maintenance, LLC. will be performing roadway and turn lane **improvements beginning November 24, 2025, and continuing through July 2, 2026.** Improvements include baserock, asphalt pavement, drainage improvements, concrete sidewalk and concrete curb. Installation of a new northbound and south bound turn lane to access 152200 Treeline Avenue S. Only one turn lane will be worked at a time. Only one lane will be close at a time as needed. Based on the calendar days, this work will be performed at night from **7:00 PM to 6:00 AM**, when we have to close the lanes. For additional information, please contact Juan Gomez at jgomez@pmioffl.com or (239) 464-9767.

Treeline Avenue, south of Daniels Parkway (ROW2025-02269): PMI will be performing road and sidewalk improvements **beginning December 3, 2025, and continuing through July 30, 2026.** They will be installing a north and southbound turn lane at 14181 & 14051 Treeline Avenue S. Work will also include asphalt pavement, concrete sidewalk, and concrete curb and drainage improvements. The daytime work hours will be from 7:00 AM to 4:00 PM for shoulder work and will not require lane closures (MOT index 102-602). The nighttime hours will be from **7:00 PM to 6:00 AM and will include lane closures.** For more information, please contact the Project Manager, Juan Gomez, at 239-464-9767 or by email at jgomez@pmioffl.com.

SR 80 and River Hall Parkway to SR 80 and Joel Boulevard (ALVA): Lee County DOT and its contractor, Intelligent Infrastructure Solutions LLC, will begin the installation of Fiber Optic Cable for approximately 7 miles between Joel Boulevard and River Hall Parkway on SR 80. There will be no lane closures at this time. These improvements include ATMS Communications for signalized intersections (Broadway, Styles, Joel, and Alva Bridge). The work activities above are scheduled to occur, however unforeseen conditions and weather may affect this schedule. The project will begin **Monday, February 16, 2026, and estimated completion is June 2026.** Motorists and pedestrians are urged to use extra caution when traveling through the work zones. For further information, please contact Kyle Blanc at

LCDOTProjects@leegov.com.

Sanibel Toll Facility: Starting **Monday, March 30, 2026, and ending on August 27, 2026**, there will be intermittent nightly lane closures. Lee County DOT will be performing lane maintenance through the toll plaza. Intermittent lane closures can be expected from **8:00 PM to 6:00 AM**. Please contact Rob Radford at (239) 229-5980, if you should have any questions.

Midpoint Toll Facility: Starting **Monday, March 2, 2026, and ending on September 8, 2026**, there will be intermittent nightly lane closures. Lee County DOT will be performing lane maintenance through the toll plaza. Intermittent lane closures can be expected starting at **8:00 PM to 6:00 AM**. Please contact Rob Radford at (239) 229-5980, if you should have any questions.

Cape Toll Facility: Starting **Monday, March 16, 2026, and ending on September 29, 2026**, there will be intermittent nightly lane closures. Lee County DOT will be performing lane maintenance through the toll plaza. Intermittent lane closures can be expected starting at **8:00 PM to 6:00 AM**. Please contact Rob Radford at (239) 229-5980, if you should have any questions.

12th Street from Gerald Ave to North Ave – Lehigh Acres: Team SCOTT will be performing a pipe replacement project beginning **Monday, March 23, 2026, and continuing through June 21, 2026**. Drainage pipe removal and replacement, roadway restoration, and associated improvements will be performed. 12th Street between Joel Blvd and North Street will be subject to periodic road closures with detours in place. Access will be maintained for local traffic; however, motorists should expect delays and are encouraged to seek alternate routes when possible. Periodic closures will occur between the hours of **9:00 AM and 3:30 PM, Monday through Friday**. For further information regarding this project, please contact Garry Ireland at (239) 340-8695 or via email at info@team-scott.com.

LCDOT along with their contractor Coastal Concrete, will be installing new sidewalks, street lighting and pedestrian crosswalks along **Alico Road westbound between Quaker Lane and Michael G. Ripp Parkway**. ACME barricades will be setting up M.O.T starting **March 9, 2026, with work following on March 10, 2026**. **Project is to last up to 6 months, weather permitting**. Expect single lane closures heading

westbound at times. Please use caution when driving. For more information, please contact Coastal Concrete Alejandro A. Navarro at 239-248-3039.

Daniels Parkway- Lee County (ROW2025-02543): Thompkins Contracting, Inc., will be performing roadway improvements beginning **Monday, March 23, 2026, and continuing through June 30, 2026.** Asphalt pavement, concrete sidewalk, concrete curbing, and drainage improvements will be performed. The inside (right) lane of eastbound traffic and the outside (left) lane on Daniels Parkway heading west will be subject to lane closures, as will one of two lanes from the westbound and eastbound portion of Daniels Parkway. **All work will be completed between the periods of 7:00 PM and 6:00 AM.** For further information, please contact Ricky Acevedo (239) 494-2174 or Robert Langford (239) 896-7480. Scott Safety LLC will provide maintenance of traffic services (833) 723-3499.

Bonita Beach Road and Miller Road - Bonita Springs, FL - Benco Construction LLC will be performing roadway and sidewalk improvements starting on **March 16, 2026, and continuing through June 2026, during the hours of 7:00 PM to 5:00 AM.** Asphalt pavement, concrete sidewalk, concrete curbing, and drainage improvements will be performed. There will be closures at the entrance of Miller Road, off Bonita Beach Road, periodically to allow for the new utility pipe to be installed. There will be flaggers working for the duration of this project. For additional information, please contact Robert Hearn at (239) 994-4561 or rhearn@bencoconstructionllc.com.

Alico Road from Quaker Lane to Michael G Rippe Parkway – Fort Myers: Coastal Site Development will be performing sidewalk improvements beginning **Tuesday, April 7, 2026, and continuing through Friday, June 26, 2026.** Underground directional drilling, concrete sidewalk, concrete curbing, and drainage improvements will be performed. The outside (right) lane of westbound traffic on Alico Road just before Quaker Lane will be subject to lane closures, as will one of two right turn lanes onto Micheal G Rippe Parkway. Periodic lane closures for westbound lanes will occur between the hours of **9:00 AM and 4:30 PM** on weekdays to allow concrete trucks. For further information, please contact Alejandro Navarro at (239) 248-3039.

Burnt Store Road Full Depth Reclamation from NW Fourth Terrace to Gator Slough Canal: A full depth reclamation project on Burnt Store Road in the southbound lanes from NW Fourth Terrace to Gator Slough Canal is nearing completion. Full depth reclamation, paving, and temporary striping operations have been

completed. Once the pavement is properly cured, then final thermoplastic striping will be applied. This work addressed storm-related deterioration and restored the roadway's structural integrity. Final striping operations will be scheduled once cure time requirements are met. For further questions, please contact Katelyn Carmona by email at Katelyn.Carmona@exp.com or by phone at (239) 744-9192.

Pine Island Road Resurfacing from West of Matlacha Drawbridge to East of Little Pine Island Bridge: This project included standard milling and paving operations from west of the Matlacha Drawbridge to east of Little Pine Island Bridge. Once the pavement is properly cured, then final thermoplastic striping will be applied. For further questions, please contact Katelyn Carmona by email at Katelyn.Carmona@exp.com or by phone at (239) 744-9192.

West Lee Boulevard Sidewalk Repair Project (B260031CFC) – Lehigh Acres: Team SCOTT will be performing sidewalk repair work beginning **Monday, April 20, 2026, and continuing through October 10, 2026**. Concrete sidewalk removal and replacement, along with associated restoration, will be performed. West Lee Blvd will be subject to intermittent lane closures, shoulder closures, sidewalk closures, and bicycle lane closures throughout the project limits. Access will be maintained; however, motorists, cyclists, and pedestrians should expect delays and use caution when traveling through the work zone. Intermittent closures will occur between the hours of **9:00 AM and 3:30 PM, Monday through Friday**. For further information regarding this project, please contact **Garry Ireland at (239) 340-8695 or via email at info@team-scott.com**.

Summerlin Road – Fort Myers (ROW2026-00119): QOE will be performing underground boring of fiber optic conduit **beginning Tuesday, June 16, 2026, and continuing through Wednesday, June 17, 2026**. Drilling will be performed at the intersection of Summerlin Rd and Pine Ridge Rd; traffic on Summerlin Road will be subject to lane closures temporarily. Work hours will be from **9:00 AM to 3:30 PM**. For further information, please contact **Rome Lima at (813) 998-6644 or rom.dornelas@qusllc.com**. First Response MOT will provide maintenance of traffic services (239) 628-0638.

Ashlar Avenue near Homestead Road – Lehigh (ROW2026-00075): Bluewater of South Florida, Inc. will be performing roadway and utility improvements **beginning Monday May 18, 2026, and continuing through June 30, 2026**. Ashlar Avenue (across from S loop Boulevard) traffic will be detoured to Taylor Lane. This shutdown will occur between **9:00 AM and 3:30 PM** daily as needed to facilitate utility install

and roadway work. For further information, please contact Chad McKimm at 239-877-0500 or chadm@bluewaterunderground.com. Bob's Barricades will provide maintenance of traffic services.

Meadows Road, west of Ray Avenue – Fort Myers (ROW2026-01159): Strategic Commercial Construction, LLC will be performing roadway and sidewalk improvements beginning **May 26, 2026, and continuing through August 28, 2026**. Asphalt pavement, concrete sidewalk, concrete curbing and drainage improvements will be performed. The east and west bound lanes will be subject to partial lane closures. This periodic closure will occur between **9:00 AM and 3:30 PM** on weekdays. For further information, please contact Strategic Commercial Construction at 727-216-3378.

Turn Lane at Bonita Grande and Snell Lane - Fort Myers (ROW2025-02426): DeAngelis Diamond Construction, LLC Permit Contractor. EHC will be performing roadway improvements **beginning Wednesday, May 27, 2026, and continue through July 3, 2026**. Asphalt pavement, concrete curbing, and drainage improvements will be performed. The outside (right) lane of northbound traffic on Bonita Grande just after Bonita Beach Rd. will be subject to shoulder and sidewalk closures will occur between the hours of 9:00 AM and 3:30 PM on weekdays. For further information, please contact Ronnie Skinner at (239) 253-1272 or krskinner@ehcconstruction.com. ACME will provide maintenance of traffic services.

Midtown Bonita at 27800 Bonita Grande Drive (ROW2025-00619): Haskins, Inc. will perform turn lane improvements:

- Starting at the intersection of Bonita Beach Road SE and Bonita Grande Drive the left lane heading south until Trade Way Drive will be subject to lane closures with flagging operation from **9:00 AM – 3:30 PM on June 1, 2026, through June 30, 2026**.
- Starting at the intersection of Bonita Grande Drive and Trade Way Drive, the left lane heading north towards Bonita Beach Road SE will be subject to lane closures with flagging operation from **9:00 AM – 3:30 PM on June 1, 2026, through June 30, 2026**.
- Starting at the intersection of Bonita Grande Drive and Snell Lane, the left turn lane heading south towards Bonita Beach Road SE will be subject to lane closures with flagging operation from **9:00 AM – 3:30 PM on June 1, 2026, through June 30, 2026**.

For further information, please contact Greg Collier at (239) 300-8818 or Dustin Cash at (239) 478-1688.

Estero Boulevard at Eucalyptus Court – Town of Fort Meyers Beach (ROW2026-01121 and ROW2026-01067): i2i Networks, LLC will be removing damaged underground cables from manholes along Estero Boulevard beginning Monday, June 8, 2026, and continue through Friday, July 3, 2026. The Northbound lane on Estero Boulevard between Lenell Road and Crescent Street, as well as the southbound lane on Crescent Street near 5th Street and 1st Street will be subject to periodic night-time lane closures. Closures will only be at active manhole worksites and will not affect the entire route all at once. Periodic lane closures will occur between the hours of **7:00 PM and 6:00 AM** For further information, please contact Vernon Evans at (360) 599-0022, or at vernon.evans@i2inetworks.net. Southeastern Traffic Supply will provide maintenance of traffic services (404) 989-2441.

250' Flagpole Project – Bernie Braden Park (2051 Cape Coral Parkway East – North side of road): This project consists of erecting a 250' tall flagpole in Bernie Braden Park (north half of park). In addition to the flagpole, and its foundation, work also includes installing localized electrical service lines to provide power for the winch inside the flagpole, the 360-degree aviation light at the top, and uplighting to illuminate the flag at night.

Although a permanent maintenance of traffic is not anticipated for this project, drivers and bicyclists are urged to use extra caution when traveling through this area, so as not to be distracted by the construction work being performed.

1. Motorists should expect heavy truck traffic entering and exiting the project area (between the Welcome Center and the base of the Cape Coral Bridge) on the north side of Cape Coral Parkway starting **Monday, June 1, 2026**, (and continuing throughout the project) with some equipment mobilization potentially taking place late in the preceding week.
2. Some equipment/material deliveries may involve some random slowdowns and stoppages in westbound and/or eastbound traffic, which should be limited to times of the day between the weekday AM and PM bridge traffic rush hours (e.g. 9:00 AM to 3:00 PM), or in some cases after the PM rush hour (e.g. 7:00 PM), or before the AM rush hour (6:00 AM).
3. Any exact days and times of select construction related activities, that may impact traffic flow significantly on Cape Coral Parkway, will be provided/forwarded to Roadwatch when known.

The work activities above are scheduled to occur, however unforeseen construction conditions, material/equipment deliveries, and weather may affect this schedule.

Motorists are asked to drive with caution and watch for workers and construction vehicles entering and leaving the construction area. **Estimated completion is Friday, July 3, 2026.** Project cost is approximately \$420,000. The contractor is Dynamic South. For further questions, please contact Chris Camp by email at ccamp@capecoral.gov or by phone at (239) 574-0468, or the City of Cape Coral's Communications Division

by email at communications@capecoral.gov or by phone at (239) 242-3484.

Russ Berner Construction will be milling and paving for LCDOT in **Lehigh Acres at various intersections listed below**. Work is expected to begin on June 1, 2026 (Monday) and be completed by **June 12, 2026 (Friday)**. **Work hours will be from 8:00 AM to 4:00 PM**. This operation will require a flagging operation. Flagging will be provided by Sunstate Civil Services. Motorists should extra caution and expect delays if work is active at the referenced intersections. Intersections to be milled and paved:

- **Meadow Rd. / Owen Ave.**
- **30th St. SW / Owen Ave.**
- **29th St. SW / Owen Ave.**
- **Todd Ave. / 26th St. SW**
- **Cedartree Ave. / Billings St.**
- **Cecelia Ave. / Belrose St.**
- **Cedartree Ave. / Centennial Blvd.**
- **Chauncey Ave. / Centennial Blvd.**
- **Beecher St. / Cedartree Ave.**
- **28th St. W / Tena Ave. N.**

Please contact Doug Padgett (Russ Berner Construction) at (239) 222-8964 with any questions or concerns.

Stringfellow Road and Iona Sidewalk Repairs. This project involves the removal and replacement of sidewalk panels along Stringfellow Road and within the Iona area where cracking and concrete deterioration has occurred.

- Crews will begin repairs along **Thornton Road**.
- Crews will continue repairs along **Iona Road**.

For the duration of this project, work will take place Monday through Saturday between the hours of **7:00 AM and 7:00 PM** pending weather or unforeseen circumstances. There will be intermittent lane closures and sidewalk detours as a part of this project. Motorists and pedestrians are asked to use caution and follow posted signage while traveling through the work zone. **Construction is anticipated to be completed by February 2027**, weather permitting. For further questions, please contact Katelyn Carmona by email at Katelyn.Carmona@exp.com or by phone at (239) 744-9192.

Alden Pine Country Club Area in the Pineland Area of Pine Island; Scheduled to begin June 8, 2026, and continue through June 22, 2026. As part of the ongoing Countywide Resurfacing for 2026, OHLA (contractor), will be milling & resurfacing in the area. There will be intermittent daily flagging operations with changes to the traffic pattern. Please pay attention to all signage and flaggers. Please note the work hours will be from **8:00 AM to 4:00 PM**. Motorists are asked to exercise caution and reduce their speed while driving through the work zone. Stay alert! For additional information, please contact Robert Peterson at Robert.PetersonJr@ohla-usa.com.

6 Mile Cypress Parkway between Heritage Palms Boulevard to Daniels Park Way - Fort Myers (ROW2025-01114): Blue Streak LLC will be performing handhole placement, fiber pulling, rodding and proofing, aerial pole attachments, and splicing fiber from **June 2, 2026, through June 16, 2026**. The outside (right) lane of southbound traffic and any right turning lanes on 6 Mile Cypress will be subjected to lane closures starting at Heritage Palms Blvd to Daniels Pkwy in a periodic moving MOT. Sidewalk closures will be required with the lane closure in the moving MOT, such closures will be submitted appropriately through our vendor Southeastern Traffic Supply. Working hours will be from **9:00 AM to 3:30 PM** on weekdays. For further information, please contact Nicholas Novo at (305) 915-9127 or nnovo@bluestreakllc.com.

Broadhurst Loop at Cypress Lake Drive - Fort Myers (ROW2026-00924): Diamond Solutions Inc., will perform asphalt pavement improvements beginning **Monday, June 8, 2026, and continuing through Monday, June 15, 2026**. The outside (right) lane of westbound traffic on Cypress Lake Drive just before Broadhurst Loop will be subject to lane closures on **Monday, June 15, 2026, between the hours of 9:00 AM and 4:00 PM**. Broadhurst loop will have alternating north and southbound lanes closed on Monday, June 15, 2026, as improvements take place in the main drive lane. One lane will remain open to traffic at all times. AWP Safety of Florida will provide maintenance of traffic services: (407)-319-7893. For additional information, please contact Katie Rutkowski at katie.rutkowski@thediamondsolutions.com.

Summerlin Road – Fort Myers (RW 2026-H-192-00007): QOE will be performing underground boring of fiber optic conduit **beginning Thursday, June 18, 2026, and continuing through June 19, 2026**. Drilling will be performed at the intersection of Summerlin Road and San Carlos Bboulevard; traffic on Summerlin Road will be subject to lane closures temporarily. Work hours will be from **9:00 AM to 3:30 PM**. For further information, please contact **Rome Lima** at (813) 998-6644 or rom.dornelas@qusllc.com. First Response MOT will provide maintenance of traffic services (239) 628-0638.

Burnt Store Road Safety Improvements: This project consists of safety improvements along Burnt Store Road from Delilah Drive to Vincent Avenue including maintenance of traffic, erosion control, earthwork, construction of 4-foot-wide paved shoulders throughout the project limits, new right and left turn lanes at Caloosa Parkway, milling and resurfacing at the new turn lane location, installation of rumble strips along the edge lines and centerline stripes, new guardrail, roadway signing, pavement markings, and sodding. The contractor is Ajax Paving Industries of Florida, LLC.

Drivers are urged to use extra caution when traveling through the work zone and to use courtesy and patience throughout the construction area.

The following activities are subject to change based on weather conditions and unforeseen field conditions:

- Crews will maintain work zone signage and traffic control devices throughout the project limits.
- Crews will continue installing erosion control measures, including silt fence installation throughout the project corridor.
- Daytime crews will be stockpiling base material in designated laydown areas.
- Motorists should expect intermittent nighttime flagging operations as crews perform clearing, grubbing, and roadway grading operations adjacent to the roadway shoulders.

The posted speed limit within the work zone remains reduced to **50 mph**.

MOTORISTS ARE REMINDED TO OBEY THE POSTED SPEED LIMIT.

Please use caution and watch for workers, equipment, and construction vehicles entering and leaving the roadway. For additional information, please contact Alesia Hatsitski at ahatsitski@aimengr.com.

Summerlin Road and San Carlos Boulevard (SR 865)-Fort Myers (ROW2026-01447): TECO Peoples Gas will be performing a roadway closure beginning **June 18, 2026, from 10:00 AM to 2:00 PM**. The outside (Right) lane on the west bound side of Summerlin Rd. just after the San Carlos intersection will be subject to rd. closure, as will the one of the two left turn lanes from North bound portion of San Carlos Blvd turning west onto Summerlin rd. Lane closures will occur between the hours of **10:00 AM to 2:00 PM on June 18, 2026**. For Further information, please contact Eddie Walsh at (813)482-8900 ejwalsh@tecoenergy.com. Southeastern Traffic Supply will provide maintenance of traffic services (727) 434-4174.

Gunnery Road-Storm System Inspection: Lee County and its contractor, Sewer Viewer, will be conducting storm system inspections along Gunnery Road in Lehigh Acres from **Lee Boulevard south to Leonard Boulevard/23rd Street SW, beginning Tuesday June 16, 2026 – Friday, June 19, 2026.** Schedule is weather dependent. Motorists should expect intermittent lane closures throughout the duration of the work. Drivers are urged to use caution in the area, follow posted signage, watch for workers and equipment, and allow extra travel time. Please use alternate routes when possible. We appreciate the public’s patience during this maintenance operation. For additional information, please contact Rhett Tillman at rtillman@leegov.com or (239) 533-9400.

The intersection of Samville Road and Bayshore Road– North Fort Myers (ROW2026-00339): Capling Leveling, Inc. will be performing roadway and sidewalk improvements beginning **Friday, June 12, 2026, and continue through August 30, 2026.** Asphalt pavement, concrete sidewalk, concrete curbing, and road improvements will be performed. The Eastbound lane of Samville Road will be subject to alternating lane closures, as will the Westbound lane of Samville Road. Periodic lane closures for Eastbound and Westbound lanes will occur between the hours of **9:00 AM and 3:30 PM** on weekdays. For further information, please contact Chris Welch at (239) 747-5771 or Cwelch@caplingleveling.com. Acme Barricades will provide maintenance of traffic services (305) 796-3587.

College Parkway at South Pointe Boulevard - Fort Myers (ROW2025-01920): AIM Engineering & Surveying, Inc. will be performing utility cores beginning **Monday, June 15, 2026, and continuing through Wednesday, June 17, 2026.** Utility cores will be performed in the roadway to verify the horizontal and vertical location of existing utilities. Eastbound and westbound travel lanes, as well as the westbound turn lanes of College Parkway, are subject to lane closure. Only one lane will be closed at a time. Lane closures will take place between **8:00 PM and 5:00 AM.** For further information, please contact Jesse Warner at (239) 910-1657 or jwarner@aimengr.com. STS will provide maintenance of traffic (MOT) services. Please contact Missy Thompson for MOT information at (727) 434-4174.

Pennsylvania Street and Alico Road – Fort Myers (ROW2026-00205): Stevens Construction, Inc. will be performing roadway and sidewalk improvements beginning **Monday, June 15, 2026, and continue through July 17, 2026.** Asphalt pavement, concrete sidewalk, concrete curbing, and drainage improvements will be performed. The outside (right) lane of westbound traffic on Alico Road just after Gator Road will be subject to lane closures, as will the sidewalk be closed traveling westbound on Alico Road. Periodic lane closures for westbound lanes will occur between the hours of 9:00 a.m. and 3:30 p.m. on weekdays. For further information, please contact Tom Porter or Todd Denney at 239-270-4695 or

tomp@stevensbuilds.com. A&SW Consultants, Inc., will provide maintenance of traffic services 239-898-0931.

Homestead Road N at Ashlar Avenue (Chick-Fil-A Lehigh - ROW2026-00075): Southern Striping Solutions, LLC. (dba Collier Paving and Concrete) will be performing roadway improvements (new turn lane construction) approximately **beginning Monday, June 22, 2026, and continue through approximately July 24, 2026.** Sub-grade excavation, concrete curbing, lime rock placement, asphalt paving, and pavement markings will be performed. The outside (right) lane of westbound traffic on Homestead Road N at Ashlar Avenue will be subject to lane closures between the hours of **9:00 AM and 4:00 PM** on weekdays. For further information, please contact Jon Ackley at (239)-292-3406 or jackley@collierpave.com or Jason DeMarco at (239)-910-3410 or jason@collierpave.com. Acme Barricades will provide maintenance of traffic services (239)-479-5266

Three Oaks Parkway at Williams Road – Estero (ROW2026-01458): Advanced Remediation Solutions will be performing a remediation beginning **June 25, 2026 and continuing through June 25, 2026.** Work will include limited excavation and restoration activities within the County-maintained Right of Way to remove petroleum impacted soil resulting from a Waste Pro vehicle incident. The outside right lane of southbound traffic on Three Oaks Parkway just after Milan Villas Lane will be subject to a lane closure. Additionally, the right turn lane on the eastbound side of Williams Road turning onto Three Oaks Parkway southbound will have a shoulder closure. A closure for the southbound lane will occur between the hours of **9:00 AM and 3:00 PM on Thursday, June 25, 2026.** For further information, please contact **Austin Allen** at (352-536-4516) or (Austin@imsfl.us). Atlantic Traffic Solutions, LLC will provide maintenance of traffic services (386-748-9056).

2. Bridge Maintenances

Matlacha Drawbridge: Work on the Matlacha Mechanical and Electrical Repair project commenced on **August 25, 2025,** and will be ongoing until **late June 2026.** Workers will be intermittently present on the site but may not be seen for extended periods of time as work is required inside the tender house. While on site, motorists can expect to encounter construction workers and vehicles on the roadway, as well as deliveries and the removal of old equipment from the bridge. Please be aware that this is an active work zone, and drivers are asked to exercise caution when driving through the site. For further information, please contact Avelino Cancel at (239) 533-9400 or email: acancel@leegov.com.

Bridge #124060 - Lee County DOT Operations will perform bridge deck repairs on Del Prado, north of Cape Coral Parkway. The job is scheduled to start **on May 25, 2026, to June 11, 2026**, weather permitting. Lane closures from **9:00 AM to 4:00 PM**. For further information, please contact Carlos Hernandez at (239) 533-9400 or email: chernandez@leegov.com.

Bridge #120170 - Lee County DOT Operations will perform bridge deck repairs on Lee Blvd, East bound lan, West of Sunshine Blvd. The job is scheduled to start on **June 4, 2026, to June 12, 2026**, weather permitting. Lane closures from **8:00 PM to 5:00 AM**. For further information, please contact Carlos Hernandez at (239) 533-9400 or email: chernandez@leegov.com.

Bridge #120065 - Lee County DOT Operations will perform bridge deck repairs on Joel Blvd. The job is scheduled to start on **June 1, 2026, to June 18, 2026**, weather permitting. Lane closures from **9:00 AM to 4:00 PM**. For further information, please contact Carlos Hernandez at (239) 533-9400 or email: chernandez@leegov.com.

Bridge #124115 - Lee County DOT Operations will perform bridge deck repairs on Sanibel Island bridge, span B on the E bound lane. The job is scheduled to start **on June 22, 2026, to June 25, 2026**, weather permitting. Lane shifts from 9:00 AM to 4:00 PM. For further information, please contact Carlos Hernandez at (239) 533-9400 or email: chernandez@leegov.com.

Bridge #10042 - Lee County DOT will make bridge repairs on the Alva bridge. Weather permitting, repairs are scheduled for **June 2, 2026, to June 11, 2026**; flag men control single-lane closures **from 9:00 AM to 4:00 PM**. For further information, please contact Carlos Hernandez at (239) 533-9400 or email: chernandez@leegov.com.

Bridge #125004 - Lee County DOT Operations will perform bridge deck repairs on March Avenue. The job is scheduled to start **on June 15, 2026 to June 18, 2026**, weather permitting. Flagmen control single-lane closures from **9:00 AM to 4:00 PM**. For further information, please contact Carlos Hernandez at (239) 533-9400 or email: chernandez@leegov.com.

Bridge #124025 - Lee County DOT Operations will perform bridge deck repairs on Buckingham Rd . The job is scheduled to start on **June 22, 2026 to June 25, 2026**, weather permitting. Flagmen control single-lane closures from **9:00 AM to 4:00 PM**. For further information, please contact Carlos Hernandez at (239) 533-9400 or email: chernandez@leegov.com.

Bridge #124056 - Lee County DOT Operations will perform bridge deck repairs on Summerlin Rd. The job is scheduled to start on **June 29, 2026 to July 9, 2026**, weather permitting. Lane closures from **9:00 AM to 4:00 PM**. For further information, please contact Carlos Hernandez at (239) 533-9400 or email: chernandez@leegov.com.

3. Street Lighting Maintenance

Midpoint Bridge/Veterans Parkway/Colonial Boulevard from Country Club Boulevard to Summerlin Rd: Lee County DOT Traffic will be performing street lighting maintenance on Midpoint Bridge/Veterans Parkway/ Colonial Boulevard from Country Club Boulevard to Summerlin Road.

- On **Wednesday, June 10, 2026**, there will Eastbound Lane closure on Veterans Parkway/Midpoint Bridge from Country Club Boulevard to East of the Toll Plaza from **9:00 AM to 4:00 PM**.
- On **Thursday, June 11, 2026**, there will Eastbound Lane closure on Midpoint Bridge/Colonial Blvd from the Toll Plaza to Summerlin Road from **9:00 AM to 4:00 PM**.

The work activities above are scheduled to occur, however unforeseen conditions and weather may affect this schedule. For further information, please contact Ryan Kirsch at (239) 896-8074.

4. Landscaping – Tree Trimming

Del Prado Boulevard: Lee County DOT will be performing various landscape tasks on Del Prado Boulevard between Cape Coral Parkway and Hancock Bridge Parkway. Lane closures may occur between **9:00 AM and 4:00 PM**. Motorists should use caution as flagmen, workers, and equipment will be present. Work is scheduled to **begin April 6, 2026, and will be ongoing as resources and weather allow**. For further information, please call Bob DeBrock at (239) 533-9425.

Banyan Street: Lee County DOT will be trimming/removing trees on Banyan Street in Boca Grande. Road closure may occur between **9:00 AM and 4:00 PM**. Motorists should use caution as flagmen, workers, and

equipment will be present. Work is scheduled to **begin April 13, 2026, and should be completed by June 18, 2026**. For further information, please call Bob DeBrock at (239) 533-9425.

5. Traffic Signal Maintenance

Old San Carlos Boulevard & Estero Boulevard (Fort Myers Beach): Lee County DOT - Traffic and its contractor DPI Experts has begun the permanent repairs of the traffic signal at Old San Carlos Boulevard & Estero Boulevard. The project includes the replacement of damaged pedestrian signal and street light foundations, including ADA Ramps and Detectable Warning Surfaces, pedestrian signals, streetlights, wiring, Traffic Signals, Traffic Signal Cabinet, and refreshment of Pavement Markings. **Construction hours will be 7:00 PM - 5:30 AM.**

- At this time crews are working on removing concrete and ADA Ramps and replacing foundations and pouring the new sidewalk and ADA Ramps. Pedestrians can expect pedestrian detours and drivers can expect intermittent lane closures when crews are removing and installing concrete. Each corner will be done separately.

The work activities above are scheduled to occur, however unforeseen conditions and weather may affect this schedule.

Construction started on May 04, 2026, and the Estimated completion is Fall 2026. Motorists and Pedestrians are urged to use extra caution when traveling through the work zones. For further information, please contact Ryan Kirsch at LCDOTProjects@leegov.com.