



**Posted Date:** July 15, 2019

**Solicitation No.:** B190367BAG

**Solicitation Name:** Alva Boat Ramp Renovation

**Subject:** Addendum Number 2

The following represents clarification, additions, deletions, and/or modifications to the above referenced bid. This addendum shall hereafter be regarded as part of the solicitation. Items not referenced herein remain unchanged, including the response date. Words, phrases or sentences with a strikethrough represent deletions to the original solicitation. Underlined words and bolded, phrases or sentences represent additions to the original solicitation.

**1) CLARIFICATIONS**

**SECTION CS-17.0 LIMESTONE RIPRAP**

**Delete the third paragraph that reads** *"The average stone diameter required for construction will vary between 8 inches and 12 inches. No more than 25% of the rock shall be pieces weighing less than 50 pounds each. At least 50% of the rock shall be pieces weighing 100 pounds or more each."*

**Replace with the following:** *"The average stone diameter required for construction will vary between 18 inches and 24 inches. No more than 25% of the rock shall be pieces weighing less than 300 pounds each. At least 50% of the rock shall be pieces weighing 450 pounds or more each. The toe stone shall be approximately 30" diameter."*

**Delete the fifth paragraph that reads:** *"Stone of the quality and gradations specified shall be placed in such a manner so as to minimize the void spaces between the stones. The finished surface shall be relatively uniform and shall contain the maximum amount of large stone as can be obtained by performing the WORK as specified. The structures shall be constructed to the lines and grades shown on the CONTRACT Plans. Stones shall be placed in a manner that will prevent rolling or sliding of stone down the slopes. The equipment used in placing in the stone will be subject to the approval of the COUNTY and ENGINEER. Both during construction and upon completion, the structures will be thoroughly examined for adherence to the CONTRACT Plans."*

**Replace with the following:** *"Riprap shall be individually placed in a manner that will prevent rolling or sliding of stone down the slope. Riprap should be oriented with the longest dimension perpendicular to the structure's alignment, where possible. Placing the*


*stone by dropping by crane, dumping into chutes or by similar methods will not be permitted. Riprap shall be individually placed so as to be in contact with adjacent stones and should interlock to form a compact stable mass. The quality of the chinking stone shall be the same as the riprap. Chinking stone shall be placed to fill voids within the riprap layers using the largest chinking stone possible to fill each void."*

**2) QUESTIONS/ANSWERS**

1.	Coastal Engineering gave us a Square Foot so we can fill in the tonnage. The contractors should receive a tonnage to use in order to keep quotes competitive. I have already spoken to the rip rap suppliers and the request for quantities are all over the place. Also specs and drawings call out for different dimensions or rip rap.
Answer	<b>The park property is 200 feet wide. Average width of the riprap to be placed is less than 20 feet. Total area of the river bank to be regraded/ripraped is 2,800 SF. The County does not wish to provide a specific quantity of stone for this relatively small area. The contractor can elect to reuse existing stone to supplement work meet the grades depicted in the construction plans. This will minimize tracking of quantities. Rip rap is to remain Lump Sum (LS) unit of measure as indicated on Bid Schedule.</b>

**BIDDER/PROPOSER IS ADVISED, YOU ARE REQUIRED TO ACKNOWLEDGE RECEIPT OF THIS ADDENDUM WHEN SUBMITTING A BID/PROPOSAL. FAILURE TO COMPLY WITH THIS REQUIREMENT MAY RESULT IN THE BIDDER/PROPOSER BEING CONSIDERED NON-RESPONSIVE.**

**ALL OTHER TERMS AND CONDITIONS OF THE SOLICITATION DOCUMENTS ARE AND SHALL REMAIN THE SAME.**

  
 \_\_\_\_\_  
 Brooke Green  
 Lee County Procurement Management