



Procurement Management Department
2115 Second Street, 1st Floor
Fort Myers, FL 33901
Main Line: (239) 533-8881
Fax Line: (239) 485-8383
www.leegov.com/procurement

Posted Date: August 1, 2023

Solicitation No.: B230008BAG

Solicitation Name: Hurricane Ian Permanent Signal Repair

Subject: Addendum Number 2

The following represents clarification, additions, deletions, and/or modifications to the above referenced bid. This addendum shall hereafter be regarded as part of the solicitation. Items not referenced herein remain unchanged, including the response date. Words, phrases or sentences with a strikethrough represent deletions to the original solicitation. Underlined words and bolded, phrases or sentences represent additions to the original solicitation.

1. ATTACHMENTS

a. Hurricane Ian Individual Traffic Signal Repair List

2. QUESTIONS/ANSWERS

1.	Is there a list of intersections and the quantities at each location available?
Answer	<i>Intersection List can be found on Sheet No. T-7 - T-9 of the plans.</i> <i>Attached herein is a pdf spreadsheet with individualized quantities per each intersection sorted by Inspection ID.</i>

BIDDER/PROPOSER IS ADVISED, YOU ARE REQUIRED TO ACKNOWLEDGE RECEIPT OF THIS ADDENDUM WHEN SUBMITTING A BID/PROPOSAL. FAILURE TO COMPLY WITH THIS REQUIREMENT MAY RESULT IN THE BIDDER/PROPOSER BEING CONSIDERED NON-RESPONSIVE.

ALL OTHER TERMS AND CONDITIONS OF THE SOLICITATION DOCUMENTS ARE AND SHALL REMAIN THE SAME.

Brooke Green, CPPB
Grants Procurement Analyst
Direct Line: 239-533-8848
Lee County Procurement Management

Attachment 1A

Hurricane Ian Individual Traffic Signal Repair List

INSPECTION ID	PAY ITEM NO.	DESCRIPTION	UNIT	QUANTITY
IAN-002	650-1-80	VEHICULAR TRAFFIC SIGNAL, ADJUST/MODIFY EXISTING SIGNAL	AS	1.000
	650-2-105	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, TUNNEL VISOR	EA	1.000
	653-1-12	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 2 WAY	AS	1.000
	LC-FLAT BAR	FLAT BAR, REPLACE - FURNISH & INSTALL	EA	2.000
	700-3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	2.000
	715-5-31	LUMINAIRE & BRACKET ARM- ALUMINUM, FURNISH & INSTALL NEW LUMINAIRE AND ARM ON NEW/EXISTING POLE	EA	1.000
IAN-003	715-5-51	LUMINAIRE & BRACKET ARM, REMOVE LUMINAIRE AND ARM; POLE REMAINS	EA	1.000
	650-1-14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	1.000
	LC-FLAT BAR	FLAT BAR, REPLACE - FURNISH & INSTALL	EA	3.000
	700-3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	2.000
	700-3-501	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	2.000
	715-5-31	LUMINAIRE & BRACKET ARM- ALUMINUM, FURNISH & INSTALL NEW LUMINAIRE AND ARM ON NEW/EXISTING POLE	EA	1.000
IAN-008	715-5-51	LUMINAIRE & BRACKET ARM, REMOVE LUMINAIRE AND ARM; POLE REMAINS	EA	1.000
	653-1-40	PEDESTRIAN SIGNAL RELOCATE	AS	2.000
	LC-FLAT BAR	FLAT BAR, REPLACE - FURNISH & INSTALL	EA	5.000
	700-5-21	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	2.000
IAN-012	700-5-50	INTERNALLY ILLUMINATED SIGN, RELOCATE	EA	4.000
	700-5-60	INTERNALLY ILLUMINATED SIGN, REMOVE	EA	2.000
	650-1-14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	1.000
	650-1-80	VEHICULAR TRAFFIC SIGNAL, ADJUST/MODIFY EXISTING SIGNAL	AS	3.000
IAN-013	650-2-105	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETRO- FURNISH & INSTALL, TUNNEL VISOR	EA	1.000
	659-1-102	MOUNTING ASSEMBLY, REPAIR/REPLACE/RETRO- FURNISH & INSTALL, SPAN WIRE MOUNTING ASSEMBLY	EA	1.000
	LC-FLAT BAR	FLAT BAR, REPLACE - FURNISH & INSTALL	EA	3.000
	700-3-501	SIGN PANEL RELOCATE, UP TO 12SF	EA	2.000
	632-7-4	SIGNAL CABLE, ADJUST	PI	1.000
	634-4-400	SPAN WIRE ASSEMBLY, ADJUST	PI	1.000
IAN-014	650-1-14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	3.000
	650-1-60	VEHICULAR TRAFFIC SIGNAL, REMOVE - POLES TO REMAIN	AS	2.000
	650-1-80	VEHICULAR TRAFFIC SIGNAL, ADJUST/MODIFY EXISTING SIGNAL	AS	1.000
	650-2-102	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, BACKPLATE- BLACK WITH REFLECT BORDER	EA	3.000
	650-2-105	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, TUNNEL VISOR	EA	1.000
	LC-FLAT BAR	FLAT BAR, REPLACE - FURNISH & INSTALL	EA	1.000
IAN-019	660-4-12	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL ABOVE GROUND EQUIPMENT	EA	2.000
	700-5-50	INTERNALLY ILLUMINATED SIGN, RELOCATE	EA	2.000
	715-5-21	LUMINAIRE & BRACKET ARM, F&I, REPLACE ON EXISTING	EA	2.000
	650-2-105	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, TUNNEL VISOR	EA	15.000
	660-4-12	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL ABOVE GROUND EQUIPMENT	EA	1.000
	660-4-60	VEHICLE DETECTION SYSTEM- VIDEO, REMOVE	EA	1.000
IAN-026	700-5-21	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	1.000
	700-3-101	SIGN PANEL, F&I GROUND MOUNT, UO TO 12SF	EA	1.000
	700-5-21	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	2.000
	700-5-60	INTERNALLY ILLUMINATED SIGN, REMOVE	EA	2.000
	632-7-4	SIGNAL CABLE, ADJUST	PI	1.000
	634-4-400	SPAN WIRE ASSEMBLY, ADJUST	PI	1.000
IAN-030	634-5-1	FIBERGLASS INSULATOR, FURNISH & INSTALL	LF	50.000
	653-1-40	PEDESTRIAN SIGNAL, RELOCATE	AS	2.000
	LC-FLAT BAR	FLAT BAR, REPLACE - FURNISH & INSTALL	EA	2.000
	660-4-12	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL ABOVE GROUND EQUIPMENT	EA	2.000
	660-4-60	VEHICLE DETECTION SYSTEM- VIDEO, REMOVE	EA	2.000
	700-5-21	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	1.000
IAN-051	700-5-50	INTERNALLY ILLUMINATED SIGN, RELOCATE (ADJUST)	EA	1.000
	700-5-60	INTERNALLY ILLUMINATED SIGN, REMOVE	EA	1.000
	632-7-2	SIGNAL CABLE - REPAIR/REPLACE/OTHER, F&I	LF	150.000
	632-7-4	SIGNAL CABLE, ADJUST	PI	1.000
	634-4-400	SPAN WIRE ASSEMBLY, ADJUST	PI	1.000
	650-1-14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	2.000
IAN-067	LC-FLAT BAR	FLAT BAR, REPLACE - FURNISH & INSTALL	EA	2.000
	700-5-21	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	1.000
	700-5-60	INTERNALLY ILLUMINATED SIGN, REMOVE	EA	1.000
	639-1-0	ELECTRICAL POWER SERVICE DIAGNOSTIC AND MISCELLANEOUS REPAIR	EA	1.000
	639-1-112	ELECTRICAL POWER SERVICE, F&I, OVERHEAD, METER FURNISHED BY CONTRACTOR FROM POWER COMPANY	AS	1.000
	639-1-610	ELECTRICAL POWER SERVICE, REMOVE OVERHEAD	AS	1.000
IAN-070	639-2-1	ELECTRICAL SERVICE WIRE, F&I	LF	250.000
	646-1-11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	2.000
	646-1-60	ALUMINUM SIGNALS POLE, REMOVE	EA	2.000
	650-1-19	VEHICULAR TRAFFIC SIGNAL, F&I ALUMINUM, 5 SECTION CLUSTER, 1 WAY	AS	1.000
	650-2-102	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, BACKPLATE- BLACK WITH REFLECT BORDER	EA	3.000
	653-1-11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	4.000
IAN-071	653-1-12	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 2 WAYS	AS	2.000
	LC-FLAT BAR	FLAT BAR, REPLACE - FURNISH & INSTALL	EA	8.000
	660-4-11	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL CABINET EQUIPMENT	EA	1.000
	660-4-12	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL ABOVE GROUND EQUIPMENT	EA	4.000
	665-1-11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	8.000
	665-1-60	PEDESTRIAN DETECTOR REMOVE - POLE/PEDESTAL TO REMAIN	EA	4.000
IAN-077	670-5-110	TRAFFIC CONTROLLER ASSEMBLY, F&I, NEMA	AS	1.000
	670-5-600	TRAFFIC CONTROLLER ASSEMBLY, REMOVE CONTROLLER WITH CABINET	AS	1.000
	684-1-1	MANAGED FIELD ETHERNET SWITCH, F&I	EA	1.000
	685-1-13	UNINTERRUPTIBLE POWER SUPPLY, FURNISH & INSTALL, LINE INTERACTIVE WITH CABINET	EA	1.000
	700-3-501	SIGN PANEL, RELOCATE, UP TO 12 SF	EA	1.000
	715-5-21	LUMINAIRE & BRACKET ARM, F&I, REPLACE ON EXISTING	EA	4.000
IAN-077	632-7-2	SIGNAL CABLE- REPAIR/REPLACE/OTHER, FURNISH & INSTALL	LF	80.000
	650-1-14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	1.000
	700-3-202	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 12-20 SF	EA	2.000
	700-3-502	SIGN PANEL, RELOCATE, 12-20 SF	EA	2.000
	700-3-602	SIGN PANEL, REMOVE, UP TO 12-20 SF	EA	1.000
	659-1-102	MOUNTING ASSEMBLY, REPAIR/REPLACE/RETRO-FURNISH & INSTALL, SPAN WIRE MOUNTING ASSEMBLY	EA	1.000
IAN-077	660-4-12	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL ABOVE GROUND EQUIPMENT	EA	1.000
	700-3-202	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 12-20 SF	EA	1.000
	700-3-502	SIGN PANEL, RELOCATE, UP TO 12-20 SF	EA	2.000
	715-5-21	LUMINAIRE & BRACKET ARM, REPLACE LUMINAIRE AND ARM ON EXISTING POLE	EA	2.000
	LC-FLAT BAR	FLAT BAR, REPLACE - FURNISH & INSTALL	EA	3.000
	659-1-102	MOUNTING ASSEMBLY, REPAIR/REPLACE/RETRO-FURNISH & INSTALL, SPAN WIRE MOUNTING ASSEMBLY	EA	3.000
IAN-077	700-3-202	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 12-20 SF	EA	2.000
	700-3-502	SIGN PANEL, RELOCATE, UP TO 12-20 SF	EA	2.000
	LC-FLAT BAR	FLAT BAR, REPLACE - FURNISH & INSTALL	EA	3.000
	632-7-1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	1.000
	634-4-153	SPAN WIRE ASSEMBLY, F&I, TWO POINT, BOX OR DROP BOX (EAST SIDE)	PI	1.000
	650-1-14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	3.000

Attachment 1A

Hurricane Ian Individual Traffic Signal Repair List

IAN-072	650-1-19	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 5 SECTION CLUSTER, 1 WAY	AS	1,000
	650-1-60	VEHICULAR TRAFFIC SIGNAL, REMOVE- POLES TO REMAIN	AS	1,000
	650-2-102	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, BACKPLATE- BLACK WITH REFLECT BORDER	EA	1,000
	659-1-102	MOUNTING ASSEMBLY, REPAIR/REPLACE/RETRO- FURNISH & INSTALL, SPAN WIRE MOUNTING ASSEMBLY	EA	1,000
	700-3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	1,000
	700-3-202	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 12-20 SF	EA	2,000
	700-3-501	SIGN PANEL, RELOCATE, UP TO 12 SF	EA	1,000
	700-3-502	SIGN PANEL, RELOCATE, 12-20 SF	EA	2,000
IAN-073	LC-FLAT BAR	FLAT BAR, REPLACE - FURNISH & INSTALL	EA	2,000
	650-5-109	VEHICULAR TRAFFIC SIGNAL, REMOVE- POLES TO REMAIN	AS	2,000
	659-1-102	MOUNTING ASSEMBLY, REPAIR/REPLACE/RETRO-FURNISH & INSTALL, SPAN WIRE MOUNTING ASSEMBLY	EA	2,000
	700-3-202	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 12-20 SF	EA	1,000
	700-3-502	SIGN PANEL, RELOCATE, 12-20 SF	EA	2,000
	LC-FLAT BAR	FLAT BAR, REPLACE - FURNISH & INSTALL	EA	2,000
	632-7-2	SIGNAL CABLE-REPAIR/REPLACE/OTHER, FURNISH & INSTALL	LF	150,000
	632-7-4	SIGNAL CABLE, ADJUST	PI	1,000
IAN-075	650-1-14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	1,000
	650-2-102	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, BACKPLATE- BLACK WITH REFLECT BORDER	EA	2,000
	659-1-102	MOUNTING ASSEMBLY, REPAIR/REPLACE/RETRO-FURNISH & INSTALL, SPAN WIRE MOUNTING ASSEMBLY	EA	2,000
	659-1-104	MOUNTING ASSEMBLY, REPAIR/REPLACE/RETRO- FURNISH & INSTALL, DISCONNECT HANGER	EA	1,000
	685-5-80	UNINTERRUPTIBLE POWER SUPPLY, STANDALONE CABINET, BATTERY DIAGNOSTICS	EA	1,000
	685-5-81	UNINTERRUPTIBLE POWER SUPPLY, STANDALONE CABINET, BATTERY REPLACEMENT	EA	1,000
	700-3-101	SIGN PANEL, FURNISH AND INSTALL GROUND MOUNT, UP TO 12 SF	EA	1,000
	700-3-202	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 12-20 SF	EA	2,000
	LC-FLAT BAR	FLAT BAR, REPLACE - FURNISH & INSTALL	EA	12,000
	650-1-14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	1,000
IAN-078	650-1-19	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 5 SECTION CLUSTER, 1 WAY	AS	1,000
	650-1-60	VEHICULAR TRAFFIC SIGNAL, REMOVE- POLES TO REMAIN	AS	1,000
	700-5-22	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL, OVERHEAD MOUNT, 12-18 SF	EA	1,000
	700-5-50	INTERNALLY ILLUMINATED SIGN, RELOCATE	EA	2,000
IAN-081	659-1-104	MOUNTING ASSEMBLY, REPAIR/REPLACE/RETRO- FURNISH & INSTALL, DISCONNECT HANGER	EA	2,000
	700-5-21	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	3,000
	700-5-60	INTERNALLY ILLUMINATED SIGN, REMOVE	EA	1,000
	LC-FLAT BAR	FLAT BAR, REPLACE - FURNISH & INSTALL	EA	3,000
IAN-082	632-7-1	SIGNAL CABLE-NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	1,000
	632-7-6	SIGNAL CABLE, REMOVE - INTERSECTION	PI	1,000
	650-1-14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	5,000
	660-4-11	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL CABINET EQUIPMENT	EA	1,000
	660-4-12	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL ABOVE GROUND EQUIPMENT	EA	4,000
	660-4-60	VEHICLE DETECTION SYSTEM- VIDEO, REMOVE	EA	4,000
	715-1-12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 – 6 (AERIAL)	LF	300,000
IAN-085	632-7-2	SIGNAL CABLE-REPAIR/REPLACE/OTHER, FURNISH & INSTALL	LF	50,000
	632-7-4	SIGNAL CABLE, ADJUST	PI	1,000
	650-1-14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	1,000
	650-1-60	VEHICULAR TRAFFIC SIGNAL, REMOVE- POLES TO REMAIN	AS	1,000
	659-1-102	MOUNTING ASSEMBLY, REPAIR/REPLACE/RETRO-FURNISH & INSTALL, SPAN WIRE MOUNTING ASSEMBLY	EA	6,000
	700-3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	4,000
	700-3-501	SIGN PANEL, RELOCATE, UP TO 12 SF	EA	3,000
	715-5-21	LUMINAIRE & BRACKET ARM, REPLACE LUMINAIRE AND ARM ON EXISTING POLE	EA	2,000
IAN-090	632-7-1	SIGNAL CABLE-NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	1,000
	650-1-16	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 4 SECTION, 1 WAY	AS	1,000
	650-1-60	VEHICULAR TRAFFIC SIGNAL, REMOVE- POLES TO REMAIN	AS	1,000
	650-2-102	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, BACKPLATE- BLACK WITH REFLECT BORDER	EA	6,000
	650-2-105	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, TUNNEL VISOR	EA	13,000
	659-1-102	MOUNTING ASSEMBLY, REPAIR/REPLACE/RETRO-FURNISH & INSTALL, SPAN WIRE MOUNTING ASSEMBLY	EA	2,000
	660-4-11	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL CABINET EQUIPMENT	EA	1,000
	660-4-90	VEHICLE DETECTION SYSTEM- VIDEO, DIANGOSIS AND MISCELLANEOUS REPAIR	EA	1,000
	663-1-121	SIGNAL PRIORITY AND PREEMPTION SYSTEM, FURNISH AND INSTALL, GPS, REPLACE CABINET ELECTRONICS	EA	1,000
	684-1-1	MANAGED FIELD ETHERNET SWITCH, FURNISH & INSTALL	EA	1,000
	685-5-80	UNINTERRUPTIBLE POWER SUPPLY, STANDALONE CABINET, BATTERY DIAGNOSTICS	EA	1,000
	685-5-81	UNINTERRUPTIBLE POER SUPPLY, STANDALONE CABINET, BATTERY REPLACEMENT	EA	1,000
	700-3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	1,000
	700-5-50	INTERNALLY ILLUMINATED SIGN, RELOCATE	EA	3,000
	LC-FLAT BAR	FLAT BAR, REPLACE - FURNISH & INSTALL	EA	6,000
IAN-091	632-7-1	SIGNAL CABLE-NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	1,000
	632-7-6	SIGNAL CABLE, REMOVE- INTERSECTION	PI	1,000
	634-4-152	SPAN WIRE ASSEMBLY, F&I, TWO POINT, DIAGONAL	PI	1,000
	634-4-600	SPAN WIRE ASSEMBLY, REMOVE-POLES REMAIN	PI	1,000
	650-1-14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	EA	4,000
	650-1-15	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3SECTION, 2-4 WAYS	AS	5,000
	650-1-60	VEHICULAR TRAFFIC SIGNAL, REMOVE- POLES TO REMAIN	AS	7,000
	663-1-121	SIGNAL PRIORITY AND PREEMPTION SYSTEM, FURNISH AND INSTALL, GPS, REPLACE CABINET ELECTRONICS	EA	1,000
	685-5-80	UNINTERRUPTIBLE POWER SUPPLY, STANDALONE CABINET, BATTERY DIAGNOSTICS	EA	1,000
	685-5-81	UNINTERRUPTIBLE POWER SUPPLY, STANDALONE CABINET BATTERY REPLACEMENT	EA	1,000
	700-5-50	INTERNALLY ILLUMINATED SIGN, RELOCATE	EA	3,000
IAN-092	650-2-102	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, BACKPLATE- BLACK WITH REFLECT BORDER	EA	3,000
	659-1-102	MOUNTING ASSEMBLY, REPAIR/REPLACE/RETRO-FURNISH & INSTALL, SPAN WIRE MOUNTING ASSEMBLY	EA	1,000
	660-4-11	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL CABINET EQUIPMENT	EA	1,000
	660-4-12	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL ABOVE GROUND EQUIPMENT	EA	1,000
	663-1-121	SIGNAL PRIORITY AND PREEMPTION SYSTEM, FURNISH AND INSTALL, GPS, REPLACE CABINET ELECTRONICS	EA	1,000
	684-1-1	MANAGED FIELD ETHERNET SWITCH, FURNISH & INSTALL	EA	1,000
	700-3-102	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, 12-20 SF	EA	3,000
	715-5-31	LUMINAIRE & BRACKET ARM- ALUMINUM, FURNISH & INSTALL NEW LUMINAIRE AND ARM ON NEW/EXISTING POLE	EA	1,000
	715-5-51	LUMINAIRE & BRACKET ARM, REMOVE LUMINAIRE AND ARM; POLE REMAINS	EA	1,000
	LC-FLAT BAR	FLAT BAR, REPLACE - FURNISH & INSTALL	EA	4,000
IAN-093	630-2-11	CONDUIT, FURNISH AND INSTALL, OPEN TRENCH (CABINET CONDUIT REPAIR)	LF	30,000
	646-1-11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	1,000
	650-1-14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	2,000
	650-1-19	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 5 SECTION CLUSTER, 1 WAY	AS	1,000
	650-2-102	VEHICULAR SIGNAL AUXILIAREIS, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, BACKPLATE-BLACK WITH REFLECT BORDER	EA	4,000
	653-1-40	PEDESTRIAN SIGNAL POLE, RELOCATE	AS	1,000
	660-4-11	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL CABINET EQUIPMENT	EA	1,000
	660-4-12	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL ABOVE GROUND EQUIPMENT	EA	1,000
	663-1-121	SIGNAL PRIORITY AND PREEMPTION SYSTEM, FURNISH AND INSTALL, GPS, REPLACE CABINET ELECTRONICS	EA	1,000
	663-1-122	SIGNAL PRIORITY AND PREEMPTION SYSTEM, FURNISH AND INSTALL, GPS, DETECTOR	EA	1,000
	670-5-110	TRAFFIC CONTROLLER ASSEMBLY, F&I, NEMA	AS	1,000
	670-5-600	TRAFFIC CONTROLLER ASSEMBLY, REMOVE CONTROLLER WITH CABINET	AS	1,000
	684-1-1	MANAGED FIELD ETHERNET SWITCH, FURNISH & INSTALL	EA	1,000
	685-1-13	UNINTERRUPTIBLE POWER SUPPLY, FURNISH AND INSTALL, LINE INTERACTIVE WITH CABINET	EA	1,000
	685-5-81	UNINTERRUPTIBLE POWER SUPPLY, STANDALONE CABINET, BATTERY REPLACEMENT	EA	1,000
	700-3-202	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 12-20 SF	EA	2,000

Attachment 1A
Hurricane Ian Individual Traffic Signal Repair List

	700-3-502	SIGN PANEL, RELOCATE, 12-20 SF	EA	1,000
	715-5-31	LUMINAIRE & BRACKET ARM- ALUMINUM, FURNISH & INSTALL NEW LUMINAIRE AND ARM ON NEW/EXISTING POLE	EA	1,000
	LC-FLAT BAR	FLAT BAR, REPLACE - FURNISH & INSTALL	EA	2,000
IAN-094	700-5-21	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	2,000
	700-5-60	INTERNALLY ILLUMINATED SIGN, REMOVE	EA	2,000
IAN-095	632-7-1	SIGNAL CABLE-NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	1,000
	632-7-6	SIGNAL CABLE, REMOVE- INTERSECTION	PI	1,000
	634-6-1	MESSENGER WIRE, FURNISH & INTALL- REPLACE EXISTING	LF	130,000
	650-1-14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	1,000
	650-2-102	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, BACKPLATE- BLACK WITH REFLECT BORDER	EA	2,000
	659-1-104	MOUNTING ASSEMBLY, REPAIR/REPLACE/RETRO- FURNISH INSTALL, DISCONNECT HANGER	EA	9,000
	700-3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	3,000
	700-3-501	SIGN PANEL, RELOCATE, UP TO 12 SF	EA	1,000
	700-3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	1,000
	715-1-12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 – 6 (AERIAL)	LF	130,000
IAN-100	632-7-4	SIGNAL CABLE, ADJUST	PI	1,000
	634-4-400	SPAN WIRE ASSEMBLY, ADJUST	PI	1,000
	650-2-102	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, BACKPLATE- BLACK WITH REFLECT BORDER	EA	2,000
	700-3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	2,000
	700-3-501	SIGN PANEL, RELOCATE, UP TO 12 SF	EA	1,000
	715-5-21	LUMINAIRE & BRACKET ARM, REPLACE LUMINAIRE AND ARM ON EXISTING POLE	EA	1,000
	LC-FLAT BAR	FLAT BAR, REPLACE - FURNISH & INSTALL	EA	4,000
IAN-103	650-2-102	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, BACKPLATE- BLACK WITH REFLECT BORDER	EA	2,000
	650-2-105	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, TUNNEL VISOR	EA	1,000
	685-5-80	UNINTERRUPTIBLE POWER SUPPLY, STANDALONE CABINET, BATTERY DIAGNOSTICS	EA	1,000
	685-5-81	UNINTERRUPTIBLE POWER SUPPLY, STANDALONE CABINET, BATTERY REPLACEMENT	EA	1,000
	700-3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	2,000
	LC-FLAT BAR	FLAT BAR, REPLACE - FURNISH & INSTALL	EA	2,000
IAN-104	632-7-1	SIGNAL CABLE-NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	1,000
	634-4-152	SPAN WIRE ASSEMBLY, F&I, TWO POINT, DIAGONAL	PI	1,000
	634-5-1	FIBERGLASS INSULATOR, FURNISH & INSTALL	LF	25,000
	650-1-14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	7,000
	650-1-15	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 2-4 WAYS	AS	1,000
	650-1-19	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 5 SECTION CLUSTER	AS	2,000
	650-1-60	VEHICULAR TRAFFIC SIGNAL, REMOVE- POLES TO REMAIN	AS	9,000
	685-5-80	UNINTERRUPTIBLE POWER SUPPLY, STANDALONE CABINET, BATTERY DIAGNOSTICS	EA	1,000
	685-5-81	UNINTERRUPTIBLE POWER SUPPLY, STANDALONE CABINET, BATTERY REPLACEMENT	EA	1,000
	700-5-50	INTERNALLY ILLUMINATED SIGN, RELOCATE	EA	2,000
IAN-106	632-7-4	SIGNAL CABLE, ADJUST	PI	1,000
	634-4-400	SPAN WIRE ASSEMBLY, ADJUST	PI	1,000
	650-2-105	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, TUNNEL VISOR	EA	2,000
	650-5-109	VEHICULAR SIGNAL AUXILIATEIS, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, BACKPLATE- FLEXIBLE REQUIRED	EA	4,000
	LC-FLAT BAR	FLAT BAR, REPLACE - FURNISH & INSTALL	EA	6,000
IAN-107	632-7-2	SIGNAL CABLE-REPAIR/REPLACE/OTHER, FURNISH & INSTALL	LF	50,000
	632-7-4	SIGNAL CABLE, ADJUST	PI	1,000
	634-4-400	SPAN WIRE ASSEMBLY, ADJUST	PI	1,000
	650-1-14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	1,000
	650-2-102	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT-FURNISH & INSTALL, BACKPLATE- BLACK WITH REFLECT BORDER	EA	1,000
	659-1-102	MOUNTING ASSEMBLY, REPAIR/REPLACE/RETRO-FURNISH & INSTALL, SPAN WIRE MOUNTING ASSEMBLY	EA	1,000
	700-3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	2,000
	700-3-501	SIGN PANEL, RELOCATE, UP TO 12 SF	EA	1,000
	700-3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	2,000
	LC-FLAT BAR	FLAT BAR, REPLACE - FURNISH & INSTALL	EA	3,000
IAN-108	632-7-2	SIGNAL CABLE-REPAIR/REPLACE/OTHER, FURNISH & INSTALL	LF	50,000
	632-7-4	SIGNAL CABLE, ADJUST	PI	1,000
	634-4-400	SPAN WIRE ASSEMBLY, ADJUST	PI	1,000
	650-1-14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	1,000
	650-2-102	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, BACKPLATE- BLACK WITH REFLECT BORDER	EA	1,000
	660-4-12	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL ABOVE GROUND EQUIPMENT	EA	4,000
	660-4-60	VEHICLE DETECTION SYSTEM- VIDEO, REMOVE	EA	4,000
	700-3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	1,000
	700-3-501	SIGN PANEL, RELOCATE, UP TO 12 SF	EA	3,000
	LC-FLAT BAR	FLAT BAR, REPLACE - FURNISH & INSTALL	EA	7,000
IAN-110	632-7-1	SIGNAL CABLE-NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	1,000
	650-1-15	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 2-4 WAYS	AS	3,000
	650-1-60	VEHICULAR TRAFFIC SIGNAL, REMOVE- POLES TO REMAIN	AS	2,000
	659-1-102	MOUNTING ASSEMBLY, REPAIR/REPLACE/RETRO- FURNISH & INSTALL, SPAN WIRE MOUNTING ASSEMBLY	AS	1,000
	700-3-501	SIGN PANEL, RELOCATE, UP TO 12 SF	EA	1,000
	LC-FLAT BAR	FLAT BAR, REPLACE - FURNISH & INSTALL	EA	3,000
IAN-111	632-7-2	SIGNAL CABLE-REPAIR/REPLACE/OTHER, FURNISH & INSTALL	LF	50,000
	632-7-4	SIGNAL CABLE, ADJUST	PI	1,000
	634-4-400	SPAN WIRE ASSEMBLY, ADJUST	PI	1,000
	650-1-14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	1,000
	650-2-102	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, BACKPLATE- BLACK WITH REFLECT BORDER	EA	2,000
	650-2-105	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, TUNNEL VISOR	EA	1,000
	660-4-90	VEHICLE DETECTION SYSTEM- VIDEO, DIAGNOSIS AND MISCELLANEOUS REPAIR	EA	1,000
	663-1-121	SIGNAL PRIORITY AND PREEMPTION SYSTEM, FURNISH AND INSTALL, GPS, REPLACE CABINET ELECTRONICS	EA	1,000
	700-5-21	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	3,000
	700-5-50	INTERNALLY ILLUMINATED SIGN, RELOCATE	EA	3,000
	700-5-60	INTERNALLY ILLUMINATED SIGN, REMOVE	EA	3,000
	LC-FLAT BAR	FLAT BAR, REPLACE - FURNISH & INSTALL	EA	4,000
IAN-112	632-7-1	SIGNAL CABLE-NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	1,000
	632-7-6	SIGNAL CABLE, REMOVE- INTERSECTION	PI	1,000
	634-4-153	SPAN WIRE ASSEMBLY, F&I, TWO POINT, BOX OR DROP BOX	PI	1,000
	634-4-600	SPAN WIRE ASSEMBLY, REMOVE-POLES REMAIN	PI	1,000
	650-1-14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	3,000
	650-2-102	VEHICULAR SIGNAL AUXILIATEIS, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, BACKPLATE- BLACK WITH REFLECT BORDER	EA	2,000
	650-2-105	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, TUNNEL VISOR	EA	1,000
	653-1-11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	1,000
	700-5-50	INTERNALLY ILLUMINATED SIGN, RELOCATE	EA	4,000
	LC-FLAT BAR	FLAT BAR, REPLACE - FURNISH & INSTALL	EA	4,000
IAN-113	632-7-4	SIGNAL CABLE, ADJUST	PI	1,000
	634-4-400	SPAN WIRE ASSEMBLY, ADJUST	PI	1,000
	650-2-102	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, BACKPLATE- BLACK WITH REFLECT BORDER	EA	4,000
	663-1-121	SIGNAL PRIORITY AND PREEMPTION SYSTEM, FURNISH AND INSTALL, GPS, REPLACE CABINET ELECTRONICS	EA	1,000
	700-3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	2,000
	715-5-21	LUMINAIRE & BRACKET ARM, REPLACE LUMINAIRE AND ARM ON EXISTING POLE	EA	1,000
	LC-FLAT BAR	FLAT BAR, REPLACE - FURNISH & INSTALL	EA	2,000
	632-7-4	SIGNAL CABLE, ADJUST	PI	1,000
	650-1-14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	1,000

Attachment 1A

Hurricane Ian Individual Traffic Signal Repair List

IAN-115	650-2-102	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, BACKPLATE- BLACK WITH REFLECT BORDER	EA	3.000
	659-1-102	MOUNTING ASSEMBLY, REPAIR/REPLACE/RETRO-FURNISH & INSTALL, SPAN WIRE MOUNTING ASSEMBLY	EA	2.000
	700-3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	1.000
	700-3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	1.000
	700-5-21	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	1.000
	700-5-50	INTERNALLY ILLUMINATED SIGN, RELOCATE	EA	3.000
IAN-117	LC-FLAT BAR	FLAT BAR, REPLACE - FURNISH & INSTALL	EA	1.000
	634-4-400	SPAN WIRE ASSEMBLY, ADJUST	PI	1.000
	650-1-80	VEHICULAR TRAFFIC SIGNAL, ADJUST/MODIFY EXISTING SIGNAL	AS	2.000
	650-2-102	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, BACKPLATE- BLACK WITH REFLECT BORDER	EA	2.000
	660-4-12	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL ABOVE GROUND EQUIPMENT	EA	1.000
	660-4-60	VEHICLE DETECTION SYSTEM- VIDEO, REMOVE	EA	1.000
IAN-118	700-5-21	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	1.000
	700-5-60	INTERNALLY ILLUMINATED SIGN, REMOVE	EA	1.000
	LC-FLAT BAR	FLAT BAR, REPLACE - FURNISH & INSTALL	EA	5.000
	632-7-1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	1.000
	632-7-6	SIGNAL CABLE, REMOVE- INTERSECTION	PI	1.000
	634-4-153	SPAN WIRE ASSEMBLY, F&I, TWO POINT, BOX OR DROP BOX (WEST SIDE)	PI	1.000
IAN-120	634-4-600	SPAN WIRE ASSEMBLY, REMOVE- POLES REMAIN (WEST SIDE)	PI	1.000
	650-1-14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	1.000
	650-1-19	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 5 SECTION CLUSTER, 1 WAY	AS	1.000
	650-5-109	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, BACKPLATE- FLEXIBLE REQUIRED	EA	1.000
	653-1-40	PEDESTRIAN SIGNAL, RELOCATE	AS	1.000
	700-3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	2.000
IAN-121	700-3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	1.000
	700-5-21	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	1.000
	700-5-60	INTERNALLY ILLUMINATED SIGN, RELOCATE	EA	2.000
	700-5-60	INTERNALLY ILLUMINATED SIGN, REMOVE	EA	1.000
	LC-FLAT BAR	FLAT BAR, REPLACE - FURNISH & INSTALL	EA	1.000
	120-6	EMBANKMENT	CY	3.000
IAN-122	632-7-4	SIGNAL CABLE, ADJUST	PI	1.000
	650-2-102	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, BACKPLATE- BLACK WITH REFLECT BORDER	EA	3.000
	650-2-105	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, TUNNEL VISOR	EA	6.000
	659-1-102	MOUNTING ASSEMBLY, REPAIR/REPLACE/RETRO-FURNISH & INSTALL, SPAN WIRE MOUNTING ASSEMBLY	EA	1.000
	663-1-121	SIGNAL PRIORITY AND PREEMPTION SYSTEM, F&I, GPS, REPLACE CABINET ELECTRONICS	EA	1.000
	663-1-122	SIGNAL PRIORITY AND PREEMPTION SYSTEM, F&I, GPS, DETECTOR	EA	1.000
IAN-123	670-5-111	TRAFFIC CONTROLLER ASSEMBLY, F&I, NEMA, 1 PREEMPTION	AS	1.000
	670-5-600	TRAFFIC CONTROLLER ASSEMBLY, REMOVE CONTROLLER WITH CABINET	AS	1.000
	684-1-1	MANAGED FIELD ETHERNET SWITCH, F&I	EA	1.000
	700-3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	1.000
	700-3-501	SIGN PANEL, RELOCATE, UP TO 12 SF	EA	1.000
	715-5-21	LUMINAIRE & BRACKET ARM, REPLACE LUMINAIRE AND ARM ON EXISTING POLE	EA	1.000
IAN-125	715-11-500	LUMINAIRE, REMOVE	EA	1.000
	LC-FLAT BAR	FLAT BAR, REPLACE - FURNISH & INSTALL	EA	1.000
	120-6	EMBANKMENT	CY	1.000
	650-1-80	VEHICULAR TRAFFIC SIGNAL, ADJUST/MODIFY EXISTING SIGNAL	AS	3.000
	684-1-1	MANAGED FIELD ETHERNET SWITCH, F&I	EA	1.000
	685-5-80	UNINTERRUPTIBLE POWER SUPPLY, STANDALONE CABINET, BATTERY DIAGNOSTICS	EA	1.000
IAN-126	685-5-81	UNINTERRUPTIBLE POWER SUPPLY, STANDALONE CABINET, BATTERY REPLACEMENT	EA	1.000
	632-7-2	SIGNAL CABLE-REPAIR/REPLACE/OTHER, FURNISH & INSTALL	LF	150.000
	632-7-4	SIGNAL CABLE, ADJUST	PI	1.000
	650-1-14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	1.000
	650-2-102	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, BACKPLATE- BLACK WITH REFLECT BORDER	EA	1.000
	650-2-105	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, TUNNEL VISOR	EA	2.000
IAN-127	659-1-102	MOUNTING ASSEMBLY, REPAIR/REPLACE/RETRO-FURNISH & INSTALL, SPAN WIRE MOUNTING ASSEMBLY	EA	2.000
	659-1-104	MOUNTING ASSEMBLY, REPAIR/REPLACE/RETRO- FURNISH & INSTALL, DISCONNECT HANGER	EA	1.000
	660-4-12	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL ABOVE GROUND EQUIPMENT	EA	1.000
	660-4-60	VEHICLE DETECTION SYSTEM- VIDEO, REMOVE	EA	1.000
	700-3-501	SIGN PANEL, RELOCATE, UP TO 12 SF	EA	1.000
	LC-FLAT BAR	FLAT BAR, REPLACE - FURNISH & INSTALL	EA	4.000
IAN-128	632-7-2	SIGNAL CABLE-REPAIR/REPLACE/OTHER, FURNISH & INSTALL	LF	150.000
	632-7-4	SIGNAL CABLE, ADJUST	PI	1.000
	650-1-14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	4.000
	659-1-102	MOUNTING ASSEMBLY, REPAIR/REPLACE/RETRO-FURNISH & INSTALL, SPAN WIRE MOUNTING ASSEMBLY	EA	2.000
	659-1-104	MOUNTING ASSEMBLY, REPAIR/REPLACE/RETRO- FURNISH & INSTALL, DISCONNECT HANGER	EA	1.000
	700-3-501	SIGN PANEL, RELOCATE, UP TO 12 SF	EA	3.000
IAN-129	LC-FLAT BAR	FLAT BAR, REPLACE - FURNISH & INSTALL	EA	4.000
	632-7-4	SIGNAL CABLE, ADJUST	PI	1.000
	634-4-400	SPAN WIRE ASSEMBLY, ADJUST	PI	1.000
	650-2-102	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, BACKPLATE- BLACK WITH REFLECT BORDER	EA	4.000
	700-3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	2.000
	LC-FLAT BAR	FLAT BAR, REPLACE - FURNISH & INSTALL	EA	2.000
IAN-130	632-7-2	SIGNAL CABLE-REPAIR/REPLACE/OTHER, FURNISH & INSTALL	LF	50.000
	632-7-4	SIGNAL CABLE, ADJUST	PI	1.000
	634-4-400	SPAN WIRE ASSEMBLY, ADJUST	PI	1.000
	650-1-19	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 5 SECTION CLUSTER, 1 WAY	AS	2.000
	650-1-60	VEHICULAR TRAFFIC SIGNAL, REMOVE- POLES TO REMAIN	AS	2.000
	700-3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	2.000
IAN-131	700-3-501	SIGN PANEL, RELOCATE, UP TO 12 SF	EA	2.000
	LC-FLAT BAR	FLAT BAR, REPLACE - FURNISH & INSTALL	EA	2.000
	632-7-1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	1.000
	632-7-6	SIGNAL CABLE, REMOVE- INTERSECTION	PI	1.000
	634-4-153	SPAN WIRE ASSEMBLY, F&I, TWO POINT, BOX OR DROP BOX	PI	1.000
	634-4-600	SPAN WIRE ASSEMBLY, REMOVE- POLES REMAIN	PI	1.000
IAN-132	634-5-1	FIBERGLASS INSULATOR, FURNISH & INSTALL	LF	60.000
	700-3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	1.000
	700-3-501	SIGN PANEL, RELOCATE, UP TO 12 SF	EA	1.000
	LC-FLAT BAR	FLAT BAR, REPLACE - FURNISH & INSTALL	EA	1.000
	632-7-4	SIGNAL CABLE, ADJUST	PI	1.000
	650-2-102	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, BACKPLATE- BLACK WITH REFLECT BORDER	EA	1.000
IAN-133	659-1-102	MOUNTING ASSEMBLY, REPAIR/REPLACE/RETRO-FURNISH & INSTALL, SPAN WIRE MOUNTING ASSEMBLY	EA	2.000
	LC-FLAT BAR	FLAT BAR, REPLACE - FURNISH & INSTALL	EA	1.000
	660-4-51	VEHICLE DETECTION SYSTEM- VIDEO, ADJUST/MODIFY CABINET EQUIPMENT	EA	1.000
	660-4-52	VEHICLE DETECTION SYSTEM- VIDEO, ADJUST/MODIFY ABOVE GROUND EQUIPMENT	EA	1.000
	700-3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	1.000
	700-3-501	SIGN PANEL, RELOCATE, UP TO 12 SF	EA	2.000
IAN-134	715-11-211	LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, COBRA HEAD	EA	1.000
	632-7-1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	1.000
	634-4-400	SPAN WIRE ASSEMBLY, ADJUST	PI	1.000
	646-1-11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	2.000
	650-1-14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	1.000

Attachment 1A
Hurricane Ian Individual Traffic Signal Repair List

IAN-130	650-1-15	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 2-4 WAYS	AS	1,000	
	650-1-70	VEHICULAR TRAFFIC SIGNAL, RELOCATE- INCLUDES REMOVAL AND REINSTALLATION	AS	1,000	
	653-1-11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	2,000	
	659-1-102	MOUNTING ASSEMBLY, REPAIR/REPLACE/RETRO- FURNISH & INSTALL, SPAN WIRE MOUNTING ASSEMBLY	EA	1,000	
	663-1-121	SIGNAL PRIORITY AND PREEMPTION SYSTEM, FURNISH & INSTALL, GPS, REPLACE CABINET ELECTRONICS	EA	1,000	
	665-1-11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	2,000	
	684-1-1	MANAGED FIELD ETHERNET SWITCH, FURNISH & INSTALL	EA	1,000	
	685-5-80	UNINTERRUPTIBLE POWER SUPPLY, STANDALONE CABINET, BATTERY DIAGNOSTICS	EA	1,000	
	685-5-81	UNINTERRUPTIBLE POWER SUPPLY, STANDALONE CABINET, BATTERY REPLACEMENT	EA	1,000	
	700-3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	2,000	
700-3-501	SIGN PANEL, RELOCATE, UP TO 12 SF	EA	4,000		
	LC-FLAT BAR	FLAT BAR, REPLACE - FURNISH & INSTALL	EA	1,000	
IAN-131	632-7-2	SIGNAL CABLE- REPAIR/REPLACE/OTHER, FURNISH & INSTALL	LF	150,000	
	632-7-4	SIGNAL CABLE, ADJUST	PI	1,000	
	650-1-19	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 5 SECTION CLUSTER, 1 WAY	AS	2,000	
	650-2-105	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, TUNNEL VISOR	EA	6,000	
	659-1-102	MOUNTING ASSEMBLY, REPAIR/REPLACE/RETRO- FURNISH & INSTALL, SPAN WIRE MOUNTING ASSEMBLY	EA	2,000	
	663-1-121	SIGNAL PRIORITY AND PREEMPTION SYSTEM, FURNISH AND INSTALL, GPS, REPLACE CABINET ELECTRONICS	EA	1,000	
	660-4-11	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL CABINET EQUIPMENT	EA	1,000	
	684-1-1	MANAGED FIELD ETHERNET SWITCH, FURNISH & INSTALL	EA	1,000	
	700-3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	2,000	
	700-3-501	SIGN PANEL, RELOCATE, UP TO 12 SF	EA	2,000	
IAN-132	632-7-2	SIGNAL CABLE-REPAIR/REPLACE/OTHER, FURNISH & INSTALL	LF	200,000	
	646-1-40	ALUMINUM SIGNALS POLE, RELOCATE (ADJUST PEDESTAL)	EA	1,000	
	650-1-14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	1,000	
	650-2-102	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, BACKPLATE- BLACK WITH REFLECT BORDER	EA	2,000	
	650-2-105	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, TUNNEL VISOR	EA	4,000	
	700-5-21	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	1,000	
	700-5-60	INTERNALLY ILLUMINATED SIGN, REMOVE	EA	1,000	
	650-1-80	VEHICULAR TRAFFIC SIGNAL, ADJUST/MODIFY EXISTING SIGNAL	AS	2,000	
	650-2-105	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, TUNNEL VISOR	EA	4,000	
	660-4-51	VEHICLE DETECTION SYSTEM- VIDEO, ADJUST/MODIFY CABINET EQUIPMENT	EA	1,000	
IAN-135	660-4-52	VEHICLE DETECTION SYSTEM- VIDEO, ADJUST/MODIFY ABOVE GROUND EQUIPMENT	EA	2,000	
	700-3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	1,000	
	700-5-21	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	2,000	
	650-1-80	VEHICULAR TRAFFIC SIGNAL, ADJUST/MODIFY EXISTING SIGNAL	EA	3,000	
	650-2-105	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, TUNNEL VISOR	AS	23,000	
	653-1-40	PEDESTRIAN SIGNAL, RELOCATE (ADJUST)	AS	1,000	
	700-5-21	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	1,000	
	649-40-7	STEEL MAST ARM ASSEMBLY- TIGHTEN ARM BASE PLATE BOLTS ON EXISTING POLE	EA	1,000	
	650-1-80	VEHICULAR TRAFFIC SIGNAL, ADJUST/MODIFY EXISTING SIGNAL	AS	2,000	
	650-2-102	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, BACKPLATE- BLACK WITH REFLECT BORDER	EA	1,000	
IAN-144	650-2-105	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, TUNNEL VISOR	EA	14,000	
	659-1-101	MOUNTING ASSEMBLY, REPAIR/REPLACE/RETRO- FURNISH & INSTALL, MAST ARM MOUNTING ASSEMBLY	EA	1,000	
	650-1-80	VEHICULAR TRAFFIC SIGNAL, ADJUST/MODIFY EXISTING SIGNAL	AS	2,000	
	650-2-105	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, TUNNEL VISOR	EA	6,000	
	653-1-40	PEDESTRIAN SIGNAL, RELOCATE	EA	1,000	
	660-4-12	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL ABOVE GROUND EQUIPMENT	EA	1,000	
	660-4-60	VEHICLE DETECTION SYSTEM - VIDEO, REMOVE	EA	1,000	
	700-3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	1,000	
	632-7-2	SIGNAL CABLE-REPAIR/REPLACE/OTHER, FURNISH & INSTALL	LF	60,000	
	639-2-1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	60,000	
IAN-155	650-1-14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	1,000	
	650-1-80	VEHICULAR TRAFFIC SIGNAL, ADJUST/MODIFY EXISTING SIGNAL	AS	4,000	
	650-2-102	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, BACKPLATE- BLACK WITH REFLECT BORDER	EA	1,000	
	650-2-105	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, TUNNEL VISOR	EA	6,000	
	659-1-101	MOUNTING ASSEMBLY, REPAIR/REPLACE/RETRO- FURNISH & INSTALL, MAST ARM MOUNTING ASSEMBLY	EA	1,000	
	632-7-1	SIGNAL CABLE-REPAIR/REPLACE/OTHER, FURNISH & INSTALL	PI	1,000	
	650-1-14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	2,000	
	650-1-15	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 2-4 WAYS	AS	1,000	
	700-3-202	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 12-20 SF	EA	2,000	
	700-3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	1,000	
715-5-31	LUMINAIRE & BRACKET ARM- ALUMINUM, FURNISH & INSTALL NEW LUMINAIRE AND ARM ON NEW/EXISTING POLE	EA	1,000		
IAN-157	632-7-2	SIGNAL CABLE-NEW OR RECONSTRUCTIONED INTERSECTION, FURNISH & INSTALL	LF	180,000	
	650-2-102	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, BACKPLATE- BLACK WITH REFLECT BORDER	EA	8,000	
	650-2-105	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, TUNNEL VISOR	EA	12,000	
	659-1-102	MOUNTING ASSEMBLY, REPAIR/REPLACE/RETRO- FURNISH & INSTALL, SPAN WIRE MOUNTING ASSEMBLY	EA	2,000	
	700-3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	4,000	
	700-3-501	SIGN PANEL, RELOCATE, UP TO 12 SF (ADJUST CANTILEVER ARMS)	EA	4,000	
	715-11-211	LUMINAIRE, F&I-REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, COBRA HEAD	EA	2,000	
		LC-FLAT BAR	FLAT BAR, REPLACE - FURNISH & INSTALL	EA	14,000
	IAN-159	650-1-14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	1,000
		650-2-102	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, BACKPLATE- BLACK WITH REFLECT BORDER	EA	3,000
650-2-105		VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, TUNNEL VISOR	EA	4,000	
685-5-80		UNINTERRUPTIBLE POWER SUPPLY, STANDALONE CABINET, BATTERY DIAGNOSTICS	EA	1,000	
685-5-81		UNINTERRUPTIBLE POWER SUPPLY, STANDALONE CABINET, BATTERY REPLACEMENT	EA	1,000	
700-3-201		SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	4,000	
700-3-501		SIGN PANEL, RELOCATE, UP TO 12 SF (ADJUST CANTILEVER ARMS)	EA	4,000	
715-11-211		LUMINAIRE, F&I-REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, COBRA HEAD	EA	2,000	
632-7-1		SIGNAL CABLE-NEW OR RECONSTRUCTIONED INTERSECTION, FURNISH & INSTALL	PI	1,000	
632-7-6		SIGNAL CABLE, REMOVE- INTERSECTION	PI	1,000	
IAN-161	634-4-153	SPAN WIRE ASSEMBLY, F&I, TWO POINT, BOX OR DROP BOX	PI	1,000	
	634-4-600	SPAN WIRE ASSEMBLY, REMOVE-POLES REMAIN	PI	1,000	
	650-1-14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	5,000	
	650-1-19	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 5 SECTION CLUSTER, 1 WAY	AS	4,000	
	650-1-60	VEHICULAR TRAFFIC SIGNAL, REMOVE- POLES TO REMAIN	AS	12,000	
	660-4-12	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL ABOVE GROUND EQUIPMENT	EA	1,000	
	660-4-60	VEHICLE DETECTION SYSTEM- VIDEO, REMOVE	EA	1,000	
	685-5-80	UNINTERRUPTIBLE POWER SUPPLY, STANDALONE CABINET, BATTERY DIAGNOSTICS	EA	1,000	
	685-5-81	UNINTERRUPTIBLE POWER SUPPLY, STANDALONE CABINET, BATTERY REPLACEMENT	EA	1,000	
	700-3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	4,000	
700-5-50	INTERNALLY ILLUMINATED SIGN, RELOCATE	EA	4,000		
715-11-211	LUMINAIRE, F&I-REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, COBRA HEAD	EA	2,000		
IAN-162	650-2-105	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, TUNNEL VISOR	EA	6,000	
	660-4-12	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL ABOVE GROUND EQUIPMENT	EA	1,000	
	660-4-90	VEHICLE DETECTION SYSTEM- VIDEO, DIAGNOSIS AND MISCELLANEOUS REPAIR	EA	1,000	
	685-5-80	UNINTERRUPTIBLE POWER SUPPLY, STANDALONE CABINET, BATTERY DIAGNOSTICS	EA	1,000	
	685-5-81	UNINTERRUPTIBLE POWER SUPPLY, STANDALONE CABINET, BATTERY REPLACEMENT	EA	1,000	
	700-3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	2,000	
	700-3-501	SIGN PANEL, RELOCATE, UP TO 12 SF	EA	1,000	

Attachment 1A

Hurricane Ian Individual Traffic Signal Repair List

IAN-163	650-1-80	VEHICULAR TRAFFIC SIGNAL, ADJUST/MODIFY EXISTING SIGNAL	AS	2.000
	650-2-105	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, TUNNEL VISOR	EA	11.000
	660-4-52	VEHICLE DETECTION SYSTEM- VIDEO, ADJUST/MODIFY ABOVE GROUND EQUIPMENT	EA	1.000
	685-5-80	UNINTERRUPTIBLE POWER SUPPLY, STANDALONE CABINET, BATTERY DIAGNOSTICS	EA	1.000
	685-5-81	UNINTERRUPTIBLE POWER SUPPLY, STANDALONE CABINET, BATTERY REPLACEMENT	EA	1.000
	700-3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	4.000
IAN-164	700-3-501	SIGN PANEL, RELOCATE, UP TO 12 SF	EA	1.000
	650-1-80	VEHICULAR TRAFFIC SIGNAL, ADJUST/MODIFY EXISTING SIGNAL	AS	3.000
	650-2-102	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, BACKPLATE- BLACK WITH REFLECT BORDER	AS	2.000
	660-4-11	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL CABINET EQUIPMENT	EA	1.000
	660-4-12	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL ABOVE GROUND EQUIPMENT	EA	1.000
	660-4-60	VEHICLE DETECTION SYSTEM- VIDEO, REMOVE	EA	1.000
IAN-166	685-5-80	UNINTERRUPTIBLE POWER SUPPLY, STANDALONE CABINET, BATTERY DIAGNOSTICS	EA	1.000
	685-5-81	UNINTERRUPTIBLE POWER SUPPLY, STANDALONE CABINET, BATTERY REPLACEMENT	EA	1.000
	650-1-80	VEHICULAR TRAFFIC SIGNAL, ADJUST/MODIFY EXISTING SIGNAL	AS	4.000
	650-2-102	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, BACKPLATE- BLACK WITH REFLECT BORDER	EA	4.000
	650-2-105	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, TUNNEL VISOR	EA	1.000
	660-4-11	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL CABINET EQUIPMENT	EA	1.000
IAN-167	700-3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	4.000
	650-1-80	VEHICULAR TRAFFIC SIGNAL, ADJUST/MODIFY EXISTING SIGNAL	AS	1.000
	650-2-102	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, BACKPLATE- BLACK WITH REFLECT BORDER	EA	7.000
	650-2-105	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, TUNNEL VISOR	EA	4.000
	659-1-101	MOUNTING ASSEMBLY, REPAIR/REPLACE/RETRO- FURNISH & INSTALL, MAST ARM MOUNTING ASSEMBLY	EA	1.000
	700-5-50	INTERNALLY ILLUMINATED SIGN, RELOCATE	EA	1.000
IAN-168	650-1-80	VEHICULAR TRAFFIC SIGNAL ADJUST/MODIFY EXISTING SIGNAL	AS	7.000
	650-2-102	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, BACKPLATE- BLACK WITH REFLECT BORDER	EA	6.000
	650-2-105	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, TUNNEL VISOR	EA	28.000
	660-4-12	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL ABOVE GROUND EQUIPMENT	EA	1.000
	685-5-80	UNINTERRUPTIBLE POWER SUPPLY, STANDALONE CABINET, BATTERY DIAGNOSTICS	EA	1.000
	685-5-81	UNINTERRUPTIBLE POWER SUPPLY, STANDALONE CABINET, BATTERY REPLACEMENT	EA	1.000
IAN-169	700-3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	2.000
	700-3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	1.000
	650-1-14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	1.000
	650-1-60	VEHICULAR TRAFFIC SIGNAL, REMOVE- POLES TO REMAIN	AS	1.000
	650-1-80	VEHICULAR TRAFFIC SIGNAL, ADJUST/MODIFY EXISTING SIGNAL	AS	8.000
	650-2-102	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, BACKPLATE- BLACK WITH REFLECT BORDER	EA	3.000
IAN-171	650-2-105	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, TUNNEL VISOR	AS	28.000
	660-4-12	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL ABOVE GROUND EQUIPMENT	EA	1.000
	700-3-501	SIGN PANEL, RELOCATE, UP TO 12 SF	EA	2.000
	650-1-80	VEHICULAR TRAFFIC SIGNAL, ADJUST/MODIFY EXISTING SIGNAL	AS	8.000
	650-2-102	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, BACKPLATE- BLACK WITH REFLECT BORDER	EA	4.000
	650-2-105	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, TUNNEL VISOR	EA	34.000
IAN-173	660-4-11	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL CABINET EQUIPMENT	EA	1.000
	685-5-80	UNINTERRUPTIBLE POWER SUPPLY, STANDALONE CABINET, BATTERY DIAGNOSTICS	EA	1.000
	685-5-81	UNINTERRUPTIBLE POWER SUPPLY, STANDALONE CABINET, BATTERY REPLACEMENT	EA	1.000
	700-3-501	SIGN PANEL, RELOCATE, UP TO 12 SF	EA	2.000
	649-40-7	STEEL MAST ARM ASSEMBLY- TIGHTEN ARM BASE PLATE BOLTS ON EXISTING POLE	EA	1.000
	650-1-80	VEHICULAR TRAFFIC SIGNAL, ADJUST/MODIFY EXISTING SIGNAL	AS	4.000
IAN-176	650-2-102	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, BACKPLATE- BLACK WITH REFLECT BORDER	EA	2.000
	650-2-105	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, TUNNEL VISOR	EA	1.000
	700-3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	1.000
	700-3-202	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 12-20 SF	EA	1.000
	650-2-105	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, TUNNEL VISOR	EA	5.000
	659-1-101	MOUNTING ASSEMBLY, REPAIR/REPLACE/RETRO- FURNISH & INSTALL, MAST ARM MOUNTING ASSEMBLY	EA	1.000
IAN-182	660-4-12	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL ABOVE GROUND EQUIPMENT	EA	1.000
	660-4-60	VEHICLE DETECTION SYSTEM- VIDEO, REMOVE	EA	1.000
	700-3-501	SIGN PANEL, RELOCATE, UP TO 12 SF	EA	1.000
	632-7-1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	1.000
	632-7-6	SIGNAL CABLE, REMOVE- INTERSECTION	PI	1.000
	634-4-152	SPAN WIRE ASSEMBLY, F&I, TWO POINT, DIAGONAL	PI	1.000
IAN-183	634-4-600	SPAN WIRE ASSEMBLY, REMOVE- POLES REMAIN	PI	1.000
	650-1-14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	8.000
	650-1-16	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 4 SECTION, 1 WAY	AS	2.000
	650-1-60	VEHICULAR TRAFFIC SIGNAL, REMOVE- POLES TO REMAIN	AS	8.000
	700-3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	4.000
	700-3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	5.000
IAN-185	650-1-80	VEHICULAR TRAFFIC SIGNAL, ADJUST/MODIFY EXISTING SIGNAL	AS	6.000
	650-2-105	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, TUNNEL VISOR	EA	6.000
	660-4-12	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL ABOVE GROUND EQUIPMENT	EA	2.000
	660-4-60	VEHICLE DETECTION SYSTEM- VIDEO, REMOVE	EA	2.000
	649-40-7	STEEL MAST ARM ASSEMBLY- TIGHTEN ARM BASE PLATE BOLTS ON EXISTING POLE	EA	2.000
	650-1-80	VEHICULAR TRAFFIC SIGNAL, ADJUST/MODIFY EXISTING SIGNAL	AS	2.000
IAN-186	650-2-102	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, BACKPLATE- BLACK WITH REFLECT BORDER	EA	1.000
	650-2-105	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, TUNNEL VISOR	EA	6.000
	659-1-101	MOUNTING ASSEMBLY, REPAIR/REPLACE/RETRO- FURNISH & INSTALL, MAST ARM MOUNTING ASSEMBLY	EA	1.000
	700-3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	AS	1.000
	700-3-501	SIGN PANEL, RELOCATE, UP TO 12 SF	EA	1.000
	650-1-80	VEHICULAR TRAFFIC SIGNAL, ADJUST/MODIFY EXISTING SIGNAL	AS	2.000
IAN-187	650-2-102	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, BACKPLATE- BLACK WITH REFLECT BORDER	EA	5.000
	650-2-105	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, TUNNEL VISOR	EA	8.000
	700-3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	1.000
	700-3-501	SIGN PANEL, RELOCATE, UP TO 12 SF	EA	2.000
	632-7-2	SIGNAL CABLE- REPAIR/REPLACE/OTHER, FURNISH & INSTALL	LF	90.000
	646-1-11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	1.000
IAN-188	650-1-14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	2.000
	650-1-80	VEHICULAR TRAFFIC SIGNAL, ADJUST/MODIFY EXISTING SIGNAL	AS	4.000
	650-2-102	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, BACKPLATE- BLACK WITH REFLECT BORDER	EA	1.000
	650-2-105	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, TUNNEL VISOR	EA	14.000
	653-1-12	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 2 WAYS	AS	1.000
	700-3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	3.000
IAN-189	700-3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	1.000
	650-1-80	VEHICULAR TRAFFIC SIGNAL, ADJUST/MODIFY EXISTING SIGNAL	AS	10.000
	650-2-102	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, BACKPLATE- BLACK WITH REFLECT BORDER	EA	3.000
	650-2-105	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, TUNNEL VISOR	EA	21.000
	660-4-12	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL ABOVE GROUND EQUIPMENT	EA	2.000
	660-4-60	VEHICLE DETECTION SYSTEM- VIDEO, REMOVE	EA	2.000
IAN-190	684-1-1	MANAGED FIELD ETHERNET SWITCH, FURNISH & INSTALL	EA	1.000
	700-3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	2.000
	632-7-2	SIGNAL CABLE- REPAIR/REPLACE/OTHER, FURNISH & INSTALL	LF	40.000
	650-1-80	VEHICULAR TRAFFIC SIGNAL, ADJUST/MODIFY EXISTING SIGNAL	AS	5.000

Attachment 1A

Hurricane Ian Individual Traffic Signal Repair List

IAN-189	650-2-102	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, BACKPLATE- BLACK WITH REFLECT BORDER	EA	3.000
	650-2-105	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, TUNNEL VISOR	EA	15.000
	653-1-40	PEDESTRIAN SIGNAL, RELOCATE	AS	2.000
	660-4-12	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL ABOVE GROUND EQUIPMENT	EA	1.000
	700-3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	1.000
	700-5-21	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	1.000
IAN-191	700-5-50	INTERNALLY ILLUMINATED SIGN, RELOCATE	EA	1.000
	632-7-1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	1.000
	632-7-6	SIGNAL CABLE, REMOVE- INTERSECTION	PI	1.000
	634-4-153	SPAN WIRE ASSEMBLY, F&I, TWO POINT, BOX OR DROP BOX	PI	1.000
	634-4-600	SPAN WIRE ASSEMBLY, REMOVE- POLES REMAIN	PI	1.000
	650-1-14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	6.000
	650-1-19	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 5 SECTION CLUSTER, 1 WAY	AS	4.000
	650-1-60	VEHICULAR TRAFFIC SIGNAL, REMOVE- POLES TO REMAIN	AS	5.000
	653-1-40	PEDESTRIAN SIGNAL, RELOCATE	AS	8.000
	660-4-12	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL ABOVE GROUND EQUIPMENT	EA	2.000
	660-4-51	VEHICLE DETECTION SYSTEM- VIDEO, ADJUST/MODIFY CABINET EQUIPMENT	EA	1.000
	660-4-52	VEHICLE DETECTION SYSTEM- VIDEO, ADJUST/MODIFY ABOVE GROUND EQUIPMENT	EA	1.000
	660-4-60	VEHICLE DETECTION SYSTEM- VIDEO, REMOVE	EA	3.000
	700-3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	4.000
	700-5-21	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	3.000
	700-5-60	INTERNALLY ILLUMINATED SIGN, REMOVE	EA	3.000
	715-5-21	LUMINAIRE & BRACKET ARM, REPLACE LUMINAIRE AND ARM ON EXISTING POLE	EA	1.000
IAN-192	630-2-14	CONDUIT, FURNISH & INSTALL, ABOVEGROUND	LF	25.000
	632-7-1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PL	1.000
	632-7-6	SIGNAL CABLE, REMOVE- INTERSECTION	PI	1.000
	634-6-1	MESSENGER WIRE, FURNISH & INSTALL- REPLACE EXISTING	LF	400.000
	650-1-14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	6.000
	650-1-16	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 4 SECTION, 1 WAY	AS	1.000
	650-1-19	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 5 SECTION CLUSTER, 1 WAY	AS	1.000
	650-1-60	VEHICULAR TRAFFIC SIGNAL, REMOVE- POLES TO REMAIN	AS	5.000
	653-1-11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	1.000
	660-4-12	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL ABOVE GROUND EQUIPMENT	EA	3.000
	685-5-80	UNINTERRUPTIBLE POWER SUPPLY, STANDALONE CABINET, BATTERY DIAGNOSTICS	EA	1.000
	685-5-81	UNINTERRUPTIBLE POWER SUPPLY, STANDALONE CABINET, BATTERY REPLACEMENT	EA	1.000
	700-3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	1.000
	700-5-21	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	1.000
	700-5-50	INTERNALLY ILLUMINATED SIGN, RELOCATE	EA	1.000
IAN-193	700-5-60	INTERNALLY ILLUMINATED SIGN, REMOVE	EA	1.000
	715-5-21	LUMINAIRE & BRACKET ARM, REPLACE LUMINAIRE AND ARM ON EXISTING POLE	EA	3.000
	650-1-80	VEHICULAR TRAFFIC SIGNAL, ADJUST/MODIFY EXISTING SIGNAL	AS	3.000
	650-2-102	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, BACKPLATE- BLACK WITH REFLECT BORDER	EA	1.000
	653-1-40	PEDESTRIAN SIGNAL, RELOCATE	EA	1.000
	660-4-11	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL CABINET EQUIPMENT	EA	1.000
	660-4-12	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL ABOVE GROUND EQUIPMENT	EA	3.000
	660-4-60	VEHICLE DETECTION SYSTEM- VIDEO, REMOVE	EA	3.000
	682-1-500	ITS CCTV CAMERA, ADJUST/MODIFY	EA	1.000
	700-3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	1.000
IAN-194	700-3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	3.000
	650-1-80	VEHICULAR TRAFFIC SIGNAL, ADJUST/MODIFY EXISTING SIGNAL	AS	1.000
	650-2-105	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, TUNNEL VISOR	EA	2.000
	660-4-52	VEHICLE DETECTION SYSTEM- VIDEO, ADJUST/MODIFY ABOVE GROUND EQUIPMENT	EA	2.000
	682-1-133	ITS CCTV CAMERA, F&I, DOME ENCLOSURE - NON-PRESSURIZED, IP, HIGH DEFINITION	EA	1.000
	682-1-600	ITS CCTV CAMERA, REMOVE & DISPOSAL	EA	1.000
IAN-195	700-3-501	SIGN PANEL, RELOCATE, UP TO 12 SF	EA	1.000
	650-1-14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	1.000
	650-1-60	VEHICULAR TRAFFIC SIGNAL, REMOVE- POLES TO REMAIN	AS	1.000
	650-2-102	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, BACKPLATE- BLACK WITH REFLECT BORDER	EA	1.000
	650-2-105	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, TUNNEL VISOR	EA	9.000
	653-1-40	PEDESTRIAN SIGNAL, RELOCATE (ADJUST)	AS	1.000
	660-4-11	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL CABINET EQUIPMENT	EA	1.000
	660-4-12	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL ABOVE GROUND EQUIPMENT	EA	1.000
	660-4-60	VEHICLE DETECTION SYSTEM- VIDEO, REMOVE	EA	1.000
	685-5-80	UNINTERRUPTIBLE POWER SUPPLY, STANDALONE CABINET, BATTERY DIAGNOSTICS	EA	1.000
IAN-197	685-5-81	UNINTERRUPTIBLE POWER SUPPLY, STANDALONE CABINET, BATTERY REPLACEMENT	EA	1.000
	650-1-80	VEHICULAR TRAFFIC SIGNAL, ADJUST/MODIFY EXISTING SIGNAL	AS	5.000
	650-2-102	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, BACKPLATE- BLACK WITH REFLECT BORDER	EA	2.000
	650-2-105	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, TUNNEL VISOR	EA	14.000
	659-1-101	MOUNTING ASSEMBLY, REPAIR/REPLACE/RETRO- FURNISH & INSTALL, MAST ARM MOUNTING ASSEMBLY	EA	1.000
	660-4-52	VEHICLE DETECTION SYSTEM- VIDEO, ADJUST/MODIFY ABOVE GROUND EQUIPMENT	EA	2.000
	700-3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	1.000
	700-3-501	SIGN PANEL, RELOCATE, UP TO 12 SF	EA	1.000
IAN-198	700-3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	1.000
	650-1-80	VEHICULAR TRAFFIC SIGNAL, ADJUST/MODIFY EXISTING SIGNAL	AS	6.000
	650-2-102	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROGIE- FURNISH & INSTALL, BACKPLATE- BLACK WITH REFLECT BORDER	EA	1.000
	650-2-105	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, TUNNEL VISOR	EA	11.000
	659-1-101	MOUNTING ASSEMBLY, REPAIR/REPLACE/RETRO- FURNISH & INSTALL, MAST ARM MOUNTING ASSEMBLY	EA	2.000
	700-3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	3.000
IAN-199	650-1-80	VEHICULAR TRAFFIC SIGNAL, ADJUST/MODIFY EXISTING SIGNAL	AS	4.000
	650-2-102	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, BACKPLATE- BLACK WITH REFLECT BORDER	EA	1.000
	650-2-105	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, TUNNEL VISOR	EA	11.000
	660-4-52	VEHICLE DETECTION SYSTEM- VIDEO, ADJUST/MODIFY ABOVE GROUND EQUIPMENT	EA	2.000
	700-3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	1.000
	700-5-21	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	1.000
IAN-200	632-7-2	SIGNAL CABLE- REPAIR/REPLACE/OTHER, FURNISH & INSTALL	LF	150.000
	634-4-400	SPAN WIRE ASSEMBLY, ADJUST	PI	1.000
	650-1-14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	1.000
	650-1-60	VEHICULAR TRAFFIC SIGNAL, REMOVE- POLES TO REMAIN	AS	1.000
	650-2-105	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, TUNNEL VISOR	EA	1.000
	659-1-102	MOUNTING ASSEMBLY, REPAIR/REPLACE/RETRO- FURNISH & INSTALL, SPAN WIRE MOUNTING ASSEMBLY	EA	1.000
	685-5-80	UNINTERRUPTIBLE POWER SUPPLY, STANDALONE CABINET, BATTERY DIAGNOSTICS	EA	1.000
	700-3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	3.000
	700-3-501	SIGN PANEL, RELOCATE, UP TO 12 SF	EA	1.000
	700-3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	3.000
IAN-201	715-5-21	LUMINAIRE & BRACKET ARM, REPLACE LUMINAIRE AND ARM ON EXISTING POLE	EA	1.000
	632-7-1	SIGNAL CABLE-NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	1.000
	634-4-152	SPAN WIRE ASSEMBLY, F&I, TWO POINT, DIAGONAL	PI	1.000
	641-2-15	PRESTRESSED CONCRETE POLE, F&I, TYPE P-V	EA	1.000
	641-2-70	PRESTRESSED CONCRETE POLE, SHALLOW POLE REMOVAL- POLE 30' AND GREATER	EA	1.000
	650-1-15	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 2-4 WAYS	AS	1.000
	650-1-60	VEHICULAR TRAFFIC SIGNAL, REMOVE- POLES TO REMAIN	AS	1.000

Attachment 1A
Hurricane Ian Individual Traffic Signal Repair List

	650-1-70	VEHICULAR TRAFFIC SIGNAL, RELOCATE- INCLUDES REMOVAL AND REINSTALLATION	AS	7.000
	659-1-102	MOUNTING ASSEMBLY, REPAIR/REPLACE/RETRO- FURNISH & INSTALL, SPAN WIRE MOUNTING ASSEMBLY	EA	1.000
	685-5-80	UNINTERRUPTIBLE POWER SUPPLY, STANDALONE CABINET, BATTERY DIAGNOSTICS	EA	1.000
IAN-202	632-7-2	SIGNAL CABLE- REPAIR/REPLACE/OTHER, FURNISH & INSTALL	LF	150.000
	634-6-1	MESSENGER WIRE, FURNISH & INSTALL- REPLACE EXISTING	LF	150.000
	650-1-14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	1.000
	650-2-105	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, TUNNEL VISOR	AS	3.000
	685-5-80	UNINTERRUPTIBLE POWER SUPPLY, STANDALONE CABINET, BATTERY DIAGNOSTICS	EA	1.000
	LC-FLAT BAR	FLAT BAR, REPLACE - FURNISH & INSTALL	EA	3.000
IAN-204	LC-FLAT BAR	FLAT BAR, REPLACE - FURNISH & INSTALL	EA	1.000
	632-7-2	SIGNAL CABLE- REPAIR/REPLACE/OTHER, FURNISH & INSTALL	LF	75.000
	650-1-80	VEHICULAR TRAFFIC SIGNAL, ADJUST/MODIFY EXISTING SIGNAL	AS	1.000
	659-1-102	MOUNTING ASSEMBLY, REPAIR/REPLACE/RETRO- FURNISH & INSTALL, SPAN WIRE MOUNTING ASSEMBLY	EA	5.000
	685-5-80	UNINTERRUPTIBLE POWER SUPPLY, STANDALONE CABINET, BATTERY DIAGNOSTICS	EA	1.000
	700-3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	5.000
	700-3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	3.000
IAN-205	715-5-21	LUMINAIRE & BRACKET ARM, REPLACE LUMINAIRE AND ARM ON EXISTING POLE	EA	1.000
	715-5-21	LUMINAIRE & BRACKET ARM, REPLACE LUMINAIRE AND ARM ON EXISTING POLE	EA	2.000
IAN-215	632-7-2	SIGNAL CABLE- REPAIR/REPLACE/OTHER, FURNISH & INSTALL	LF	160.000
	634-6-1	MESSENGER WIRE, FURNISH & INSTALL- REPLACE EXISTING	LF	90.000
	650-1-14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	1.000
	659-1-102	MOUNTING ASSEMBLY, REPAIR/REPLACE/RETRO- FURNISH & INSTALL, SPAN WIRE MOUNTING ASSEMBLY	EA	2.000
	700-3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	1.000
	700-3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	1.000
IAN-233	650-2-102	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, BACKPLATE- BLACK WITH REFLECT BORDER	EA	2.000
	660-4-51	VEHICLE DETECTION SYSTEM- VIDEO, ADJUST/MODIFY CABINET EQUIPMENT	EA	1.000
	660-4-52	VEHICLE DETECTION SYSTEM- VIDEO, ADJUST/MODIFY ABOVE GROUND EQUIPMENT	EA	1.000
	685-5-80	UNINTERRUPTIBLE POWER SUPPLY, STANDALONE CABINET, BATTERY DIAGNOSTICS	EA	1.000
	700-5-22	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL, OVERHEAD MOUNT, 12-18 SF	EA	2.000
	700-5-60	INTERNALLY ILLUMINATED SIGN, REMOVE	EA	2.000
	LC-FLAT BAR	FLAT BAR, REPLACE - FURNISH & INSTALL	EA	1.000
IAN-236	650-1-14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	1.000
	659-1-102	MOUNTING ASSEMBLY, REPAIR/REPLACE/RETRO- FURNISH & INSTALL, SPAN WIRE MOUNTING ASSEMBLY	EA	5.000
	685-5-80	UNINTERRUPTIBLE POWER SUPPLY, STANDALONE CABINET, BATTERY DIAGNOSTICS	EA	1.000
	700-3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	1.000
	LC-FLAT BAR	FLAT BAR, REPLACE - FURNISH & INSTALL	EA	2.000
IAN-239	632-7-2	SIGNAL CABLE-REPAIR/REPLACE/OTHER, FURNISH & INSTALL	LF	150.000
	650-1-14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	3.000
	650-1-60	VEHICULAR TRAFFIC SIGNAL, REMOVE- POLES TO REMAIN	AS	2.000
	659-1-102	MOUNTING ASSEMBLY, REPAIR/REPLACE/RETRO- FURNISH & INSTALL, SPAN WIRE MOUNTING ASSEMBLY	EA	7.000
	700-3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	1.000
	700-3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	1.000
IAN-243	650-1-14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	2.000
	650-1-60	VEHICULAR TRAFFIC SIGNAL, REMOVE- POLES TO REMAIN	AS	1.000
	660-4-11	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL CABINET EQUIPMENT	EA	1.000
	660-4-12	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL ABOVE GROUND EQUIPMENT	EA	4.000
	660-4-90	VEHICLE DETECTION SYSTEM- VIDEO, DIAGNOSIS AND MISCELLANEOUS REPAIR	EA	1.000
	685-5-80	UNINTERRUPTIBLE POWER SUPPLY, STANDALONE CABINET, BATTERY DIAGNOSTICS	EA	1.000
IAN-244	650-2-105	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, TUNNEL VISOR	EA	1.000
	685-5-80	UNINTERRUPTIBLE POWER SUPPLY, STANDALONE CABINET, BATTERY DIAGNOSTICS	EA	1.000
	685-5-81	UNINTERRUPTIBLE POWER SUPPLY, STANDALONE CABINET, BATTERY REPLACEMENT	EA	1.000
IAN-245	632-7-1	SIGNAL CABLE-NEW OR RECONSTRUCTIONED INTERSECTION, FURNISH & INSTALL	PI	1.000
	650-1-70	VEHICULAR TRAFFIC SIGNAL, RELOCATE- INCLUDES REMOVAL AND REINSTALLATION	AS	8.000
	685-5-80	UNINTERRUPTIBLE POWER SUPPLY, STANDALONE CABINET, BATTERY DIAGNOSTICS	EA	1.000
IAN-246	632-7-1	SIGNAL CABLE-NEW OR RECONSTRUCTIONED INTERSECTION, FURNISH & INSTALL	PI	1.000
	646-1-11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	1.000
	646-1-60	ALUMINUM SIGNALS POLE, REMOVE	EA	1.000
	650-1-14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	1.000
	650-1-15	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 2-4 WAYS	AS	1.000
	650-2-105	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, TUNNEL VISOR	EA	2.000
	653-1-12	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 2 WAYS	AS	1.000
	659-1-102	MOUNTING ASSEMBLY, REPAIR/REPLACE/RETRO- FURNISH & INSTALL, SPAN WIRE MOUNTING ASSEMBLY	EA	3.000
	665-1-11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	1.000
	685-5-80	UNINTERRUPTIBLE POWER SUPPLY, STANDALONE CABINET, BATTERY DIAGNOSTICS	EA	1.000
	700-3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	2.000
	700-3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	2.000
IAN-247	632-7-1	SIGNAL CABLE-NEW OR RECONSTRUCTIONED INTERSECTION, FURNISH & INSTALL	PI	1.000
	634-4-152	SPAN WIRE ASSEMBLY, F&I, TWO POINT, DIAGONAL	PI	1.000
	634-5-1	FIBERGLASS INSULATOR, FURNISH & INSTALL	LF	50.000
	650-1-14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	2.000
	650-1-15	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 2-4 WAYS	AS	2.000
	650-1-19	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 5 SECTION CLUSTER, 1 WAY	AS	2.000
	650-1-60	VEHICULAR TRAFFIC SIGNAL, REMOVE- POLES TO REMAIN	AS	4.000
	659-1-102	MOUNTING ASSEMBLY, REPAIR/REPLACE/RETROFURNISH& INSTALL, SPAN WIRE MOUNTING ASSEMBLY	EA	2.000
	660-4-90	VEHICLE DETECTION SYSTEM- VIDEO, DIAGNOSIS AND MISCELLANEOUS REPAIR	EA	1.000
	685-5-80	UNINTERRUPTIBLE POWER SUPPLY, STANDALONE CABINET, BATTERY DIAGNOSTICS	EA	1.000