



**Posted Date:** April 11, 2024

**Solicitation No.:** B240259JJB

**Solicitation Name:** Old Pelican Bay Maintenance Dredge - Hurricane Ian

**Subject:** Addendum Number 1

The following represents clarification, additions, deletions, and/or modifications to the above-referenced bid. This addendum shall hereafter be regarded as part of the solicitation. Items not referenced herein remain unchanged, including the response date. Words, phrases, or sentences with a strikethrough represent deletions to the original solicitation. Underlined words and bolded, phrases or sentences represent additions to the original solicitation.

**1. CLARIFICATIONS**

- a. This Project is to be partially funded by FEMA. Accordingly, all dredged material shall be disposed of outside of the floodplain. No dredge material shall remain on the historic spoil sites. Please refer to the following website for floodplain information;  
<https://www.leegov.com/dcd/flood/floodways/femamapchanges>.

**2. QUESTIONS/ANSWERS**

1.	We received notice that the Old Pelican Bay dredge project was reissued for bid. We were curious as to the reason for the cancellation of the previous bid and if there is a bid tabulation that we could acquire from the results of the previous bid.
<b>Answer</b>	<b>Various changes to the specifications needed to be made and there is no bid tabulation from the previous bid available.</b>
2.	Are the staging sites already confirmed/approved or are the identified locations on the plans still the responsibility of the contractor to finalize? If the contractor has to negotiate the staging site, can you give the developers contact information?
<b>Answer</b>	<b>Refer to the TS-9.0 UPLAND DISPOSAL SITE. The availability of the historic spoil sites identified on the Contract Plans is not guaranteed. The developer does not wish to provide their contact information at this time. CONTRACTOR shall be responsible for the coordination of the proposed disposal site(s).</b>
3.	The bid details show the staging of material on the housing lots. Does the material stay, or does the contractor have to haul to a final disposal location?
<b>Answer</b>	<b>If the historic spoil sites are available and utilized, it is the CONTRACTOR's responsibility to haul material to a final disposal site of their choosing. Material shall be disposed of outside of the floodplains. CONTRACTOR shall provide written verification of disposal location at the time of bid submission. Failure to provide written verification from a disposal location may deem the CONTRACTOR as non-responsive.</b>

4.	The staging locations identified in the plans are inside a current housing development under construction with new utilities, brick road ext. Is it approved for all the heavy equipment, trucking etc. to access through this area? As the contractor, I would be worried of the damage/repairs this could cause.
<b>Answer</b>	<b>The CONTRACTOR shall coordinate directly with the historic spoil site owner for any questions regarding equipment, trucking, etc...</b>
5.	Can you confirm MLW is at -4, and the dredge cut is only to -5.6. This leaves only 1.6' of water at low tide. Does the county's construction schedule take into consideration that dredging will only take place at Hightide? Barges/boats etc. most likely will not be able to float at low tide.
<b>Answer</b>	<b>According to the published tidal information which is shown on the cover sheet of the Contract Plans, Mean Low Water (MLW) is -1.64 feet NAVD88. The design dredge template depth is -4 feet MLW or -5.6 feet NAVD88. In accordance with the Contract Documents, it is the CONTRACTOR's responsibility to utilize plant and equipment suitable for the work and to conduct their own investigation of existing site conditions.</b>
6.	Does the developer have a construction schedule we will have to work around? will there be current housing construction taking place at the same time as the dredge?
<b>Answer</b>	<b>The CONTRACTOR shall coordinate directly with the historic spoil site owner.</b>
7.	Is the 0.5' of over depth tolerance included in the schedule of values bid quantity?
<b>Answer</b>	<b>No, the quantity provided on the bid schedule is the volume within the design template per the design survey. The pay quantity will not exceed that shown on the bid schedule.</b>
8.	Will the contractor be paid unit rates for the volume of over-dredge?
<b>Answer</b>	<b>The CONTRACTOR will only be paid for the sediment removed within the design template.</b>

**BIDDER/PROPOSER IS ADVISED, YOU ARE REQUIRED TO ACKNOWLEDGE RECEIPT OF THIS ADDENDUM WHEN SUBMITTING A BID/PROPOSAL. FAILURE TO COMPLY WITH THIS REQUIREMENT MAY RESULT IN THE BIDDER/PROPOSER CONSIDERED NON-RESPONSIVE.**

**ALL OTHER TERMS AND CONDITIONS OF THE SOLICITATION DOCUMENTS ARE AND SHALL REMAIN THE SAME.**

*Jake Bond*

Jake Bond

Procurement Analyst Direct Line: 239-533-8898

Lee County Procurement Management