



KUHLMAN CONCRETE, LLC
 2690 Rockfill Road
 Fort Myers, FL 33916
 239-334-3111 (Phone)
 239-334-2729 (Fax)



READY-MIXED CONCRETE QUOTATION

Quoted To: Lee County, Florida (Lee County Board of Commissioners)
Attn: Diana Kahn, Procurement Manager: 239-533-2111 (o), 239-485-5460 (f), dkhan@leegov.com
Project: General Pricing--County Wide Deliveries in in Lee County, FL
Quoted By: Linda Mehtlan, Kuhlman Sales Representative, 239-822-0271 (mobile)
Quoted On: April 12, 2016 **Quote Good for 30 Days**
Prices Effective: July 16, 2016 to July 15, 2017

| <u>Kuhlman Concrete Mixes</u> | <u>Price When Paid Within Terms (Net 30 Days)</u> |
|--|---|
| Typical Lee County Mixes (from Previous Contract IW20310) | |
| 3500 psi Regular Mix w/ 21% ash, .49 w/c (16FEF30) | \$95.28 /cubic yard |
| 3500 psi Regular Mix w/ 20% ash, .49 w/c (16FEF32) | \$101.96 /cubic yard |
| 4000 psi Regular Mix w/ 20% ash, .44 w/c (16FEF40) | \$103.50 /cubic yard |
| 5000 psi Regular Mix w/ 20% ash, .45 w/c (1600F51) | \$112.64 /cubic yard |
| 3000 psi Pump Mix w/ 20% ash, .50 w/c (160PF27) | \$95.91 /cubic yard |
| 3000 psi Pump Mix w/ 20% ash, .44 w/c (160PF41) | \$104.26 /cubic yard |
| K-Krete Flowable Fill FDOT 121 (16FFDOT) | \$84.15 /cubic yard |
| Other Suggested Kuhlman Concrete Mixes | |
| 2500 psi Regular Mix w/ 22% ash, .58 w/c (1600F25) Residential Mix | \$92.51 /cubic yard |
| 2500 psi Pump Mix w/ 34% ash, .57 w/c (160PF24) Residential Mix | \$89.87 /cubic yard |
| 2500 psi Coarse Masonry Grout Mix w/ 37% ash, 0.50 w/c (16BFG25) | \$97.63 /cubic yard |
| 3000 psi Regular Mix w/ 11% ash, .57 w/c (160EX31) Residential Mix | \$92.94 /cubic yard |
| 3000 psi Regular Mix w/ 22% ash, .59 w/c (1600F31) Residential Mix | \$92.73 /cubic yard |
| 3000 psi Regular Mix w/ 15% ash, .50 w/c (1600F33) | \$94.15 /cubic yard |
| 3000 psi Sidewinder Blend Mix w/ 15% ash, .50 w/c (160SW30) | \$95.91 /cubic yard |
| 3000 psi Pump Mix w/ 34% ash, .53 w/c (160PF31) Residential Mix | \$90.66 /cubic yard |
| 3000 psi Pump Mix w/ 22% ash, .47 w/c (160PF32) | \$95.91 /cubic yard |
| 3000 psi Coarse Masonry Grout Mix w/ 36% ash, .50 w/c (16BFG30) | \$101.10 /cubic yard |
| 4000 psi Regular Mix w/ 20% ash, .49 w/c (1600F39) | \$98.92 /cubic yard |
| 4000 psi Regular Mix w/ 20% ash, .44 w/c (1600F45) | \$102.06 /cubic yard |
| 4000 psi Sidewinder Blend Mix w/ 20% ash, .49 w/c (160SW40) | \$104.79 /cubic yard |
| 4000 psi Pump Mix w/ 25% ash, .47 w/c (160PF40) | \$100.86 /cubic yard |
| K-Krete Flowable Fill (160FF30) | \$84.15 /cubic yard |

- Kuhlman Concrete, LLC Quotation and Supply Contract Terms and Conditions apply to all orders.
- Payment Terms: Net 30 days. Credit cards not accepted.
- Prices do not include state or local sales taxes.
- Concrete manufactured in accordance with current ASTM Specification C-94, unless otherwise noted and acknowledged.
- Pricing is for delivery in full truckload quantities of six (6) cubic yards or more, Monday through Friday, 7:00 a.m. to 4:00 p.m.
- Fuel Surcharge Per Load: \$0.00 per load.
- Environmental Fee: \$0.00 per load.
- Less than full truckload delivery--six (6) to ten (10) cubic yards:
 - five (5) to less than six (6) cubic yards: \$90.00 per load.
 - four (4) to less than five (5) cubic yards: \$125.00 per load.
 - three (3) to less than four (4) cubic yards: \$150.00 per load.
 - two (2) to less than three (3) cubic yards: \$175.00 per load.
 - one (1) to less than two (2) cubic yards: \$200.00 per load.
- One finish-up load allowed at no charge on all pours exceeding ten (10) cubic yards.
- Waiting time after eight (8) minutes unloading time allowed per yard--maximum 60 minutes per truckload. Calculated from time arrived at jobsite to time pour finished, as shown on delivery ticket. \$1.50 per minute.
- Delivery after 4:00 p.m., Monday through Friday, on orders batched after 4:00 p.m. \$50.00 per load.
- Saturday morning delivery (7:00 a.m. to Noon, when plant is open): \$60.00 per load.
- Deliveries When Plant is Normally Closed--Pricing to be Determined When Delivery Requirements are Defined
- Split-Load Fee for additional destination(s). Charge is for each additional destination. \$100.00 per load.
- Disposal Fee for Returned Concrete after 3 p.m. (more than one cubic yard): \$200.00 per load.
- Surcharge for travel to Alva or Bonita Springs: \$60.00 per load.
- Surcharge for travel to North Fort Myers Beach, Labelle, Matlacha, Pine Island Center, Punta Gorda, or North Naples (between Immokalee Road & Golden Gate Parkway): \$100.00 per load.
- Surcharge for travel to Eastern Sanibel Island, South Fort Myers Beach or Bonita Beach: \$120.00 per load.
- Surcharge for travel to Western Sanibel Island, Captiva Island, Bokeelia, St. James City, or South Naples (South of Golden Gate Parkway): \$140.00 per load.
- Add for Set Retarding Admixture: \$3.90 per cubic yard
- Add for Additional Superplasticizer Not Already in Mix--Added at Jobsite: \$6.10 per cubic yard
- Add for Synthetic Fibers (Euclid Fiberstrand 100) at 3/4 lb. per yard: \$5.35 per cubic yard
- Add for Synthetic Fibers (Euclid Fiberstrand 100) at 1.5 lb. per yard: \$9.35 per cubic yard
- Add for Set Accelerating Admixture (1% dose): \$4.15 per cubic yard
- Add for Set Accelerating Admixture (2% dose): \$8.30 per cubic yard

Thank you for the opportunity to quote and furnish your needs for ready-mixed concrete. We look forward to working with you. Please do not hesitate to contact us if you have any questions on this quotation.