

# LEE COUNTY UTILITIES THREE OAKS WATER RECLAMATION FACILITY DEEP INJECTION WELL IW-2



**LEE COUNTY UTILITIES**  
1500 MONROE STREET  
FORT MYERS, FL 33902  
PHONE (239) 533-8845

## BLACK & VEATCH

**Black & Veatch Corporation**  
4210 Metro Parkway, Suite 200  
Fort Myers, Florida 33916 Certificate No. 8132

MAY 2024

### REGISTERED ENGINEERS STATE OF FLORIDA

PROJECT MANAGER  
GENERAL, CIVIL, MECHANICAL

MARK E. MARTIN, PE  
MO. 67272

STRUCTURAL

JULIE GLOSS, PE  
NO. 86822

ELECTRICAL

DAVID MARTINS, PE  
NO. 91665

INSTRUMENTATION

KYLE PHIPPS, PE  
NO. 94332

THIS ITEM HAS BEEN DIGITALLY SIGNED AND SEALED BY MARK E. MARTIN, PE ON THE DATE INDICATED HERE. PRINTED COPIES OF THIS DOCUMENT ARE NOT CONSIDERED SIGNED AND SEALED AND THE SIGNATURE MUST BE VERIFIED ON ANY ELECTRONIC COPIES.

THIS ITEM HAS BEEN DIGITALLY SIGNED AND SEALED BY JULIA C. GLOSS, PE ON THE DATE INDICATED HERE. PRINTED COPIES OF THIS DOCUMENT ARE NOT CONSIDERED SIGNED AND SEALED AND THE SIGNATURE MUST BE VERIFIED ON ANY ELECTRONIC COPIES.

THIS ITEM HAS BEEN DIGITALLY SIGNED AND SEALED BY DAVID V. MARTINS, PE ON THE DATE INDICATED HERE. PRINTED COPIES OF THIS DOCUMENT ARE NOT CONSIDERED SIGNED AND SEALED AND THE SIGNATURE MUST BE VERIFIED ON ANY ELECTRONIC COPIES.

THIS ITEM HAS BEEN DIGITALLY SIGNED AND SEALED BY KYLE A. PHIPPS, PE ON THE DATE INDICATED HERE. PRINTED COPIES OF THIS DOCUMENT ARE NOT CONSIDERED SIGNED AND SEALED AND THE SIGNATURE MUST BE VERIFIED ON ANY ELECTRONIC COPIES.

ISSUED FOR BID - NOT FOR CONSTRUCTION










DRAWINGS LIST		
<b>GENERAL</b>		
DWG NO.	SHEET NO.	SHEET NAME
1	G-001	COVER SHEET AND GENERAL LOCATION MAP
2	G-002	DRAWINGS LIST, NOTES, SYMBOLS AND LEGENDS
3	G-601	PROCESS FLOW DIAGRAM
<b>CIVIL</b>		
DWG NO.	SHEET NO.	SHEET NAME
4	C-001	LEGENDS, CIVIL AND PROCESS MECHANICAL ABBREVIATIONS
5	C-101	AERIAL SITE PLAN
6	C-102	GRADING AND DRAINAGE PLAN
7	C-103	YARD PIPING PLAN
8	C-501	DETAILS 1
9	C-502	DETAILS 2
10	C-503	DETAILS 3
11	C-504	DETAILS 4
<b>STRUCTURAL</b>		
DWG NO.	SHEET NO.	SHEET NAME
12	S-001	STANDARD NOTES AND LOADING CRITERIA
13	S-101	WELL PAD PLAN AND SECTION
14	S-102	SUCTION PIPING PAD PLAN AND SECTION
15	S-501	CONCRETE DETAILS
16	S-502	PIPE SUPPORT DETAILS
<b>MECHANICAL</b>		
DWG NO.	SHEET NO.	SHEET NAME
17	M-001	LEGENDS AND NOTES
18	M-101	EXISTING EFFLUENT PUMP STATION DEMOLITION PLAN
19	M-102	OVERALL PIPING CONNECTION PLAN
20	M-103	WELL PAD PLAN AND SECTION
21	M-502	INJECTION WELL AND PAD MONITORING WELL DETAILS
22	M-503	INJECTION WELL WELLHEAD DETAILS
<b>ELECTRICAL</b>		
DWG NO.	SHEET NO.	SHEET NAME
23	E-001	LEGENDS
24	E-002	ABBREVIATIONS AND NOTES
25	E-101	ELECTRICAL SITE PLAN
26	E-102	PARTIAL SITE PLAN - DEMOLITION
27	E-103	PARTIAL SITE PLAN
28	E-601	EXISTING SINGLE LINE DIAGRAM, DETAILS AND PANEL SCHEDULE
<b>INSTRUMENTATION &amp; CONTROLS</b>		
DWG NO.	SHEET NO.	SHEET NAME
29	I-001	P&ID - LEGENDS & ABBREVIATIONS
30	I-501	INSTRUMENTATION INSTALLATION DETAILS
31	I-601	P&ID - EFFLUENT PUMPS

**GENERAL**

- ALL WORK SHALL CONFORM TO LATEST REVISION OF THE LEE COUNTY UTILITIES (LCU) DESIGN MANUAL WHICH IS AVAILABLE ON THE WEB-PAGE VIA THE FOLLOWING LINK: [HTTPS://WWW.LEEGOV.COM/UTILITIES/DESIGN-MANUAL](https://www.leegov.com/utilities/design-manual)
- THE CONTRACTOR SHALL COMPLY WITH ALL REGULATORY AND PERMITTING AGENCIES' REQUIREMENTS.
- ANY QUANTITIES SHOWN ON PLANS ARE NOT VERIFIED BY LCU
- ALL CONSTRUCTION PERFORMED MUST BE DONE BY A CONTRACTOR PROPERLY LICENSED IN THE STATE OF FLORIDA.
- A PRE-CONSTRUCTION MEETING IS REQUIRED BEFORE WORK MAY BEGIN. REQUIRED ATTENDEES INCLUDE BUT ARE NOT LIMITED TO; THE ENGINEER OF RECORD OR HIS DESIGNEE, THE UNDERGROUND CONTRACTOR AND THE LCU INSPECTOR AND LCU PROJECT MANAGER ASSIGNED TO THE PROJECT. LCU IS TO BE NOTIFIED A MINIMUM OF TWO (2) WORKING DAYS PRIOR TO THE PRE-CONSTRUCTION MEETING.
- ONE COPY OF THE LCU APPROVED/STAMPED CONSTRUCTION PLANS MUST BE MAINTAINED BY THE CONTRACTOR AT THE SITE AT ALL TIMES.
- ANY AND ALL WORK AND MATERIALS INSTALLED BY THE CONTRACTOR THAT ARE INTENDED FOR OWNERSHIP AND MAINTENANCE BY LCU, WHICH DO NOT CONFORM TO LCU SPECIFICATIONS AND WHICH DO NOT HAVE PRIOR LCU WRITTEN APPROVAL, ARE SUBJECT TO REMOVAL AND REPLACEMENT AT THE CONTRACTOR'S EXPENSE.
- ANY WORK PERFORMED ON INFRASTRUCTURE INTENDED FOR OWNERSHIP AND MAINTENANCE BY LCU WITHOUT THE KNOWLEDGE OF LCU IS SUBJECT TO RE-EXCAVATION, REMOVAL AND REPLACEMENT OF SAME TO BE DONE AT THE CONTRACTOR'S EXPENSE.
- LCU INSPECTION STAFF IS TO BE PRESENT FOR ALL HOT TAPS, PRESSURE TESTS, LIFT STATION START-UPS, AND FOR ANY OTHER NECESSARY INSPECTION. THE CONTRACTOR IS TO PROVIDE A MINIMUM OF TWO (2) WORKING DAYS' NOTICE PRIOR TO SCHEDULING ANY OF THE ABOVE WITH THE EXCEPTION OF THE LIFT STATION START-UP WHICH REQUIRES A MINIMUM OF TWO-WEEK'S NOTICE.
- THE CONTRACTOR IS TO UNCOVER ALL EXISTING LCU UTILITY INFRASTRUCTURE TO VERIFY HORIZONTAL LOCATION, VERTICAL LOCATION, PIPE DIAMETER, AND PIPE MATERIAL PRIOR TO SCHEDULING THE CONNECTION WITH LCU.

**GENERAL NOTES (CONTINUED)**

- LOCATIONS, ELEVATIONS, AND DIMENSIONS OF EXISTING UTILITIES, STRUCTURES AND OTHER FEATURES ARE SHOWN ACCORDING TO THE BEST INFORMATION AVAILABLE AT THE TIME OF PREPARATION OF THESE PLANS, BUT DO NOT PURPORT TO BE ABSOLUTELY CORRECT. LCU WILL NOT GUARANTEE ANY LOCATIONS AS SHOWN ON THESE PLANS OF THOSE OMITTED FROM THESE PLANS.
- THE CONTRACTOR SHALL PROVIDE A MINIMUM OF AT LEAST TWO (2) WORKING DAYS' NOTICE TO THE INDIVIDUAL UTILITY COMPANIES PRIOR TO CONSTRUCTION.
- THE CONTRACTOR SHALL CONTACT THE ENGINEER OF RECORD AND LCU IMMEDIATELY TO REPORT ANY CONFLICT WITH LCU UTILITIES/STRUCTURES ARISING DURING CONSTRUCTION OF ANY FACILITIES SHOWN ON THESE DRAWINGS.
- ALL FRAMES, COVERS, VALVE BOXES, METER BOXES AND MANHOLES SHALL BE ADJUSTED TO FINISHED GRADE UPON COMPLETION OF PAVING OR RELATED CONSTRUCTION. ALL VALVE PADS SHALL BE POURED IN PLACE. NO PRE-CAST VALVE PADS WILL BE ACCEPTED.
- LCU REQUIRES 30" MINIMUM OF COVER FALL ALL UNDERGROUND PIPING EXCEPT UNDER PAVEMENT, WHICH REQUIRES 36" MINIMUM COVER. IF LCU REQUIRED COVER CANNOT BE MAINTAINED, ALTERNATE METHODS OF CONSTRUCTION OR PIPE PROTECTION MUST BE APPROVED BY LCU AND THE ENGINEER, AT NO ADDITIONAL COST TO THE COUNTY. IF STATE AGENCIES REQUIRE ADDITIONAL COVER, MEETING THE REQUIREMENTS SHALL BE DONE AT NOT ADDITIONAL COST TO THE COUNTY.
- LCU REQUIRES THERE TO BE A MINIMUM OF TEN (10) FEET HORIZONTAL AND 18" VERTICAL SEPARATION BETWEEN POTABLE WATER & SANITARY SEWER MAINS. LCU ALSO REQUIRES MINIMUM OF TEN (10) FEET HORIZONTAL SEPARATION BETWEEN OTHER PUBLIC AND/OR PRIVATE UTILITIES, STRUCTURE(S), BUILDING(S), WALL(S), FOUNTAIN(S), FENCE(S) AND LCU INFRASTRUCTURE UNLESS SPECIFICALLY APPROVED BY LCU
- LCU REQUIRES THERE TO BE A MINIMUM OF FIVE (5) FEET HORIZONTAL SEPARATION AND 18" VERTICAL SEPARATION BETWEEN LCU INFRASTRUCTURE AND DRAINAGE INFRASTRUCTURE, MITERED AND SECTIONS, INLETS, ETC. LCU ALSO REQUIRES MINIMUM OF FIVE (5) FEET HORIZONTAL SEPARATION BETWEEN LCU INFRASTRUCTURE AND ALL NEW LIGHT POLE FOUNDATIONS.
- THE TRUNK OF PALM TREES SHALL BE A MINIMUM OF FIVE (5) FEET AND THE TRUNK OF SHADE TREES SHALL BE A MINIMUM OF THE (10) FEET FROM ANY EXISTING OR PROPOSED LCU OWNED MAINTAINED PIPE/INFRASTRUCTURE.
- AS THE WORK PROGRESSES THE CONTRACTOR SHALL PROVIDE FOR ALL CHANGES AND DEVIATIONS FROM THE LCU STAMPED/APPROVED CONSTRUCTION PLANS TO BE RECORDED. THE EXACT LOCATION OF ALL CHANGES IN VERTICAL AND HORIZONTAL ALIGNMENT SHALL BE RECORDED WITH X, Y, AND Z COORDINATES WITH RESPECT TO THE NAVD 1988 STATE PLANE FLORIDA WEST COORDINATE SYSTEM, AS WELL AS ANY OTHER RECORD INFORMATION REQUIRED BY THE LCU DESIGN MANUAL.
- CONTRACTOR SHALL PROTECT AND MAINTAIN ALL EXISTING TREES, SHRUBS, AND PLANTS UNLESS OTHERWISE NOTED. WHERE TREES ARE MARKED TO BE REMOVED, CONTRACTOR SHALL COORDINATE WITH THE COUNTY AND ENGINEER FOR NEW TREE LOCATIONS. NEW TREES SHALL BE EQUAL IN SIZE AND TYPE OF TREES REMOVED.
- CONTRACTOR SHALL INSTALL ALL PIPELINES, PAVING, WALKWAYS, AND CURB AND GUTTER AT A UNIFORM GRADE BETWEEN ELEVATIONS DEPICTED ON THE DRAWINGS.
- FOR ALL SITE GRADING, SMOOTH PARABOLIC TRANSITIONS SHALL BE MADE BETWEEN CHANGES IN SLOPE. PARABOLIC ROUNDING SHALL APPLY TO ALL CUT AND FILL SECTIONS.
- THE CONTRACTOR'S OPERATIONS SHALL CONFORM TO THE RULES AND REGULATIONS OF THE STATE CONSTRUCTION SAFETY ORDERS PERTAINING TO EXCAVATION AND TRENCHING.
- WHERE SPECIAL EXCAVATION ZONES ARE REQUIRED FOR THE WORK, CONTRACTOR SHALL INSTALL EXCAVATION SUPPORT SYSTEMS TO PROTECT EXISTING PIPES OR STRUCTURES. CONTRACTOR TO VERIFY EXACT LOCATION AND MATERIAL OF EXISTING PIPES WITHIN THE EXCAVATION ZONE. THE SYSTEM SHALL BE SIGNED AND SEALED BY A FLORIDA REGISTERED PROFESSIONAL ENGINEER IN GOOD STANDING AND SHALL BE SUBMITTED FOR RECORDS.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY DAMAGE TO EXISTING FACILITIES AS A RESULT OF CONTRACTOR'S OPERATIONS, AND SHALL HAVE ON SITE SUFFICIENT MATERIALS AND EQUIPMENT TO IMMEDIATELY REPAIR ANY DAMAGE TO EXISTING FACILITIES.
- CONTRACTOR SHALL POTHOLE EXISTING UTILITIES PRIOR TO CONSTRUCTION AS REQUIRED.



**REVISIONS AND RECORD OF ISSUE**

DESIGNED:	CLB
DETAILED:	RSF
CHECKED:	MM
APPROVED:	MEM
DATE:	SEPTEMBER 2023
PROJECT NO.:	414567

**PROCESS MECHANICAL**

**DRAWING LIST, NOTES, SYMBOLS, AND LEGENDS**

**BLACK & VEATCH**

Black & Veatch Corporation  
Certificate No. 8132  
4415 Metro Parkway, Suite 200  
Fort Myers, Florida 33916

THIS ITEM HAS BEEN DIGITALLY SIGNED AND SEALED BY MARK E. MARTIN, PE ON THE DATE INDICATED HERE. PRINTED COPIES OF THIS DOCUMENT ARE NOT CONSIDERED SIGNED AND SEALED AND THE SIGNATURE MUST BE VERIFIED ON ANY ELECTRONIC COPIES.

**LEE COUNTY UTILITIES**

THREE OAKS WATER RECLAMATION FACILITY DEEP INJECTION WELL IW-2

**PRELIMINARY - NOT FOR CONSTRUCTION**

G-002 OF

PLOTTED: 8/29/2023 10:44:43 AM  
FILE: C:\PW\WORKING\B\WV\AMERICAS\_201749724\G-002.DWG  
FD11000  
D11000



# CIVIL LEGENDS



**Black & Veatch Corporation**  
 Certificate No. 8132  
 4415 Metro Parkway, Suite 200  
 Fort Myers, Florida 33916

## EXISTING FACILITY LEGEND

	OVERHEAD UTILITY LINE
	TOP OF BANK
	TOE OF SLOPE
	WOODS LINE
	CONTOUR ELEVATION
	WATER LINE ABOVE GROUND
	GUY ANCHOR
	LIGHT POLE
	OAK TREE, UNLESS OTHERWISE NOTED
	PINE TREE
	UTILITY POLE
	SINGLE SUPPORT SIGN
	TELEPHONE SERVICE RISER
	WATER VALVE COVER
	GROUND EL.
	HARD SURFACE EL.
	ELECTRIC METER
	SANITARY SEWER VALVE COVER
	WIRE PULL BOX
	BOLLARD
	ELECTRICAL OUTLET
	FIBER OPTIC CABLE MARKER
	IRRIGATION VALVE
	WELL
	MONITORING WELL
	VENT
	TRANSFORMER
	AIR RELEASE VALVE
	NON-POTABLE WATER LINE
	BURIED ELECTRIC LINE
	BURIED TELEPHONE LINE
	FORCE MAIN
	FIBER OPTIC CABLE
	WATER MAIN
	UNKNOWN UTILITY
	AIR RELEASE VALVE
	UTILITY POLE
	TELEPHONE SERVICE RISER
	WATER VALVE COVER
	WIRE PULL BOX

## NEW FACILITY LEGEND

	DESIGN POINT
	PERCENT SLOPE
	STATION
	SLOPE RUN : RISE
	CURVE NUMBER
	SPOT ELEVATION
	SURFACED STREET, ROAD OR DRIVE
	SURFACED STREET, ROAD OR DRIVE WITH CURBS
	CATCH BASIN
	SEWER OR STORMDRAIN MANHOLE
	CLEAOUT
	DRAINAGE COURSE OR FLOW LINE
	FINISHED GRADE CONTOUR
	BANK OR SLOPE LINES
	BORE HOLE OR TEST HOLE AND NUMBER
	SURVEY LINE WITH PI, PT, OR POT
	CONCRETE ENCASEMENT - PLAN VIEW
	CULVERT
	WHEELCHAIR ACCESSIBILITY MARKER
	IRS-IRON ROD AND CAP SET (LN021)
	IRF-IRON ROD FOUND
	CMF-CONCRETE MONUMENT FOUND
	WIRE PULL BOX CABLE TV
	WIRE PULL BOX ELECTRICAL
	GRATE INLET
	GUY ANCHOR
	MAILBOX
	METER ELECTRIC
	MITERED END SECTION
	SIGN DOUBLE SUPPORT
	SIGN SINGLE SUPPORT
	TELEPHONE PEDESTAL
	VALVE BOX RECLAIMED WATER
	VALVE COVER GAS
	VALVE COVER SANITARY
	VALVE COVER UNKNOWN
	VALVE COVER WATER
	WITNESS - GAS
	WIRE PULL BOX UNKNOWN
	POWER POLE - WOOD
	METER ELECTRIC
	TRANSFORMER
	SILT FENCE
	PARKING SPACE COUNT
	PROPOSED SWALE
	NEW PIPING
	NEW PIPING IN PROFILE

	BUILDINGS, STRUCTURES
	STRUCTURES UNDERGROUND
	FUTURE BUILDINGS, STRUCTURES
	FENCE
	CENTERLINE
	PROPOSED STORM DRAINAGE PIPE
	PROPOSED MESH STRUCTURE
	PROPOSED INLET STRUCTURE
	FIRE HYDRANT
	YARD HYDRANT
	STREET LIGHT POLE
	TO BE DEMOLISHED
	EMERGENCY ACCESS EASEMENT
	EARTH OR GRADE
	BEDROCK
	GRANULAR FILL (CRUSHED ROCK OR GRAVEL)
	SAND
	AC PAVEMENT
	CONCRETE/SIDEWALKS
	ENGINEERED FILL
	RIPRAP
	CHECKERBOARD PLATE
	BAR GRATING (LINES IN DIRECTION OF SPAN)
	PROPOSED PAVEMENT
	PROPOSED SOLAR FIELD
	WETLANDS BOUNDARY HATCH

### PIPING IDENTIFICATION LEGEND

	NEW PIPING
	EXISTING PIPING
	FUTURE PIPING

### EQUIPMENT & VALVE TAG LEGEND

	MECHANICAL EQUIPMENT/VALVE TAG, SEE P&ID LEGEND AND ABBREVIATIONS
--	---

### ABBREVIATION NOTES:

- FOR EQUIPMENT ABBREVIATIONS, INCLUDING FOR VALVES, REFER TO P&ID LEGEND AND ABBREVIATIONS DRAWINGS FUNCTION CODE ABBREVIATIONS.
- FOR SYSTEM AND PROCESS STREAM ABBREVIATIONS, REFER TO P&ID LEGEND AND ABBREVIATIONS DRAWINGS SYSTEM CODE AND PROCESS CODE ABBREVIATIONS.
- FOR PIPE MATERIAL AND INSULATION MATERIAL ABBREVIATIONS REFER TO P&ID LEGEND AND ABBREVIATIONS DRAWINGS PIPELINE MATERIAL CODE AND INSULATION MATERIAL CODE ABBREVIATIONS.

## ABBREVIATIONS

<b>A</b>	AC ASPHALT CONCRETE	FLG FLANGE(D)	<b>P</b>	P&ID PIPING/PROCESS & INSTRUMENTATION DIAGRAM
AD ADDITIONAL	FM FORCE MAIN, FLOW METER	FO FIBER OPTIC	PC POINT OF CURVATURE	PCCP PRESTRESSED CONCRETE CYLINDER PIPE
ALT ALTERNATE, ALTERNATIVE	FPL FIBER OPTIC CABLE	FPS FEET PER SECOND	PG PRESSURE GAUGE, PAGE	PH PIPE HANGER
ANC ANCHOR	FRP FIBERGLASS REINFORCED PLASTIC	FT FOOT, FEET	PI POINT OF INTERSECTION	PID PROPERTY IDENTIFICATION NUMBER
AP ACCESS PANEL, ANGLE POINT	FTG FOOTING	GEN GENERAL, GENERATOR	PIT PRESSURE INDICATOR TRANSMITTER	POT POINT ON CIRCULAR CURVE, POINT OF CONNECTION
APPROX APPROXIMATE, APPROXIMATELY	GEN GAUGE	GAL GALLON	POT POINT ON TANGENT	PP POWER POLE
ASSY ASSEMBLY	GALV GALVANIZED	GB GRADE BREAK	PS PIPE SUPPORT	PSF POUNDS PER SQUARE FOOT
ATM ATMOSPHERE, ATMOSPHERIC	GC GROOVED COUPLING	GD GALLONS PER DAY	PSI POUNDS PER SQUARE INCH	PSIA POUNDS PER SQUARE INCH ABSOLUTE
AUTO AUTOMATIC	GPM GALLONS PER MINUTE	GR GRADE	PSIG POUNDS PER SQUARE INCH GAUGE	PT POINT OF TANGENCY, POINT OF VERTICAL TANGENCY
AUX AUXILIARY	GR GRADE	GV GATE VALVE	PVC POLYVINYL CHLORIDE, POINT OF VERTICAL CURVATURE	PVT POINT OF VERTICAL TANGENCY
AVG AVERAGE	H	HDD HORIZONTAL DIRECTIONAL DRILL	PVCP POLYVINYL CHLORIDE PIPE	PVI POINT OF VERTICAL INTERSECTION
AWG AMERICAN WIRE GAUGE	HDPE HIGH DENSITY POLYETHYLENE	HGT HEIGHT	PW POTABLE WATER	<b>R</b>
AWWA AMERICAN WATER WORKS ASSOCIATION	HH HANDHOLE	HMC HARNESSED MECHANICAL COUPLING	R RADIUS, RISER	R/RW RIGHT OF WAY
AWWF AVERAGE WET-WEATHER FLOW	HMJ HARNESSED MECHANICAL JOINT	HP HORIZONTAL	RCP REINFORCED CONCRETE PIPE	RCCP REINFORCED CONCRETE CYLINDER PIPE
<b>B</b>	HP HIGH POINT, HIGH PRESSURE, HORSEPOWER	HR HORIZONTAL	RED REDUCER, REDUCING	REF REFERENCE
BAL BORE HOLE	HVAC HEATING, VENTILATING AND AIR CONDITIONING	IE INVERT ELEVATION	REINFORCED, REINFORCING	REMOVABLE, REMOVE
BACK OF CURB	IN INCHES	INC INCORPORATED	REQD REQUIRED	RET RETURN
BET BETWEEN	INCL INCLUDING	INCR INCREASE	REV REVISION, REVISED, REVERSED	RMJ RESTRAINED MECHANICAL JOINT
BF BLIND FLANGE	INST INSTRUMENT, INSTRUMENTATION	INSUL INSULATE, INSULATED, INSULATING	RT RIGHT	ROW RIGHT OF WAY
BFV BUTTERFLY VALVE	INT INTERIOR, INTERNAL	INV INVERT	<b>S</b>	S SECOND, SLOPE, SOUTH
BUILDING	IPS IRON PIPE SIZE	J&B JACK & BORE	SAN SANITARY	SCHED SCHEDULE
BLK BLOCK	<b>I</b>	JB JUNCTION BOX	SD STORM DRAIN	SEC SECOND
BM BENCHMARK	ID INSIDE DIAMETER	JT JOINT	SECT SECTION	SF SQUARE FEET
BMP BEST MANAGEMENT PRACTICES	IE INVERT ELEVATION	INSUL INSULATE, INSULATED, INSULATING	SH SHEET	SH STEEL PIPE
BOP BOTTOM OF PIPE	IN INCHES	INT INTERIOR, INTERNAL	SP SPECIFICATION(S)	SS STAINLESS STEEL, SANITARY SEWER
BOT BOTTOM	INCL INCLUDING	IPS IRON PIPE SIZE	ST SWR STORM SEWER	STA STATION
BP BACK PRESSURE BEARING	INCR INCREASE	INSUL INSULATE, INSULATED, INSULATING	STL STANDARD	STR STRUCTURAL
BRG BEARING	INST INSTRUMENT, INSTRUMENTATION	INT INTERIOR, INTERNAL	SYS SYSTEM	<b>T</b>
<b>C</b>	INSUL INSULATE, INSULATED, INSULATING	INV INVERT	T TELEPHONE, TOP	TAN TANGENT
C CURVE	INT INTERIOR, INTERNAL	IPS IRON PIPE SIZE	TBC TO BE DETERMINED	TBD TO BE DETERMINED
CB CATCH BASIN	IPS IRON PIPE SIZE	J&B JACK & BORE	TBM TEMPORARY BENCHMARK	TC TOP OF CURB
CF CUBIC FEET	JT JOINT	JB JUNCTION BOX	TEMP TEMPORARY	TH TEST HOLE
CFM CUBIC FEET PER MINUTE	<b>J</b>	JT JOINT	TNK TANK	TOB TOP OF BANK
CL CENTERLINE	JB JACK & BORE	JB JUNCTION BOX	TOC TOP OF CONCRETE, TABLE OF CONTENTS, TOTAL ORGANIC CARBON	TOP TOP OF PIPE
CL CENTERLINE	J&B JACK & BORE	JB JUNCTION BOX	TOP OF ORGANIC CARBON	TOS TOP OF SLAB, TOE OF SLOPE
CM CONCRETE MONUMENT	JT JOINT	JB JUNCTION BOX	TOP OF WALL	TP TEST PIT
CO CLEAN OUT, COMPANY	INSUL INSULATE, INSULATED, INSULATING	IPS IRON PIPE SIZE	TRANS TRANSFORMER	TYP TYPICAL
COMB SWR COMBINED SEWER	INT INTERIOR, INTERNAL	IPS IRON PIPE SIZE	<b>U</b>	UB UTILITY BOX
CONC CONCRETE	IPS IRON PIPE SIZE	J&B JACK & BORE	UG UNDERGROUND	UG UNDERGROUND ELECTRICAL
CONSTR CONSTRUCTION	INSUL INSULATE, INSULATED, INSULATING	JB JUNCTION BOX	USGS UNITED STATES GEOLOGICAL SURVEY	<b>V</b>
CONT CONTINUED, CONTINUOUS, CONTINUATION, CONTROL CONTRACTOR CORNER	INT INTERIOR, INTERNAL	JB JUNCTION BOX	USGS UNITED STATES GEOLOGICAL SURVEY	VALVE (SEE P&ID ABBREVIATIONS), VERTICAL, VOLT, VENT
CONTR CONTRACTOR	IPS IRON PIPE SIZE	JB JUNCTION BOX	USGS UNITED STATES GEOLOGICAL SURVEY	VB VALVE BOX
COR CORNER	J&B JACK & BORE	JB JUNCTION BOX	USGS UNITED STATES GEOLOGICAL SURVEY	VCP VITRIFIED CLAY PIPE
CP CONTROL POINT, CATHODIC PROTECTION, CATCH POINT	JT JOINT	JB JUNCTION BOX	USGS UNITED STATES GEOLOGICAL SURVEY	VERT VERTICAL
COUPLING	<b>L</b>	JB JUNCTION BOX	USGS UNITED STATES GEOLOGICAL SURVEY	<b>W</b>
CPVC CHLORINATED POLYVINYL CHLORIDE	LAT LATERAL, LATITUDE	JB JUNCTION BOX	USGS UNITED STATES GEOLOGICAL SURVEY	W WEST, WIDE, WATER
CSP CORRUGATED STEEL PIPE	LB LICENSED BUSINESS	JB JUNCTION BOX	USGS UNITED STATES GEOLOGICAL SURVEY	W/O WITHOUT
CTR(S) CENTER(S)	LB(S) POUND(S)	JB JUNCTION BOX	USGS UNITED STATES GEOLOGICAL SURVEY	WS WATERSTOP, WATER SURFACE
CU CUBIC, COPPER	LDR LAND DEVELOPMENT REGULATIONS	JB JUNCTION BOX	USGS UNITED STATES GEOLOGICAL SURVEY	WSL WATER SURFACE LEVEL
CV CONTROL VALVE	LF LINEAR FEET	JB JUNCTION BOX	USGS UNITED STATES GEOLOGICAL SURVEY	WT WEIGHT
CY CUBIC YARD	LIN LINEAL, LINEAR	JB JUNCTION BOX	USGS UNITED STATES GEOLOGICAL SURVEY	<b>X</b>
<b>D</b>	LONG LONGITUDE	JB JUNCTION BOX	USGS UNITED STATES GEOLOGICAL SURVEY	x BY, TIMES
DEED	LT LEFT	JB JUNCTION BOX	USGS UNITED STATES GEOLOGICAL SURVEY	<b>Y</b>
DEED BOOK	<b>M</b>	JB JUNCTION BOX	USGS UNITED STATES GEOLOGICAL SURVEY	YH YARD HYDRANT
DEF DEFLECTION	M MAINT	JB JUNCTION BOX	USGS UNITED STATES GEOLOGICAL SURVEY	
DEG DEGREE	MAX MAXIMUM	JB JUNCTION BOX	USGS UNITED STATES GEOLOGICAL SURVEY	
DEPT DEPARTMENT	MECH MECHANICAL	JB JUNCTION BOX	USGS UNITED STATES GEOLOGICAL SURVEY	
DET DETAIL	MED MEDIUM	JB JUNCTION BOX	USGS UNITED STATES GEOLOGICAL SURVEY	
DHWL DAILY HIGH WATER LINE	MES MEITERED END SECTION	JB JUNCTION BOX	USGS UNITED STATES GEOLOGICAL SURVEY	
DI DROP INLET, DUCTILE IRON	MFR MANUFACTURER	JB JUNCTION BOX	USGS UNITED STATES GEOLOGICAL SURVEY	
DIA DIAMETER	MG MILLION GALLONS	JB JUNCTION BOX	USGS UNITED STATES GEOLOGICAL SURVEY	
DIFF DIFFUSER	MG/L MILLIGRAMS PER LITER	JB JUNCTION BOX	USGS UNITED STATES GEOLOGICAL SURVEY	
DIM DIMENSION	MGD MILLION GALLONS PER DAY	JB JUNCTION BOX	USGS UNITED STATES GEOLOGICAL SURVEY	
DIP DUCTILE IRON PIPE	MH MAINTENANCE HOLE, MANHOLE	JB JUNCTION BOX	USGS UNITED STATES GEOLOGICAL SURVEY	
DIST DISTRIBUTION	MIN MINIMUM, MINUTE	JB JUNCTION BOX	USGS UNITED STATES GEOLOGICAL SURVEY	
DIV DIVISION	MISC MISCELLANEOUS	JB JUNCTION BOX	USGS UNITED STATES GEOLOGICAL SURVEY	
DMJ DISMANTLING JOINT	MJ MECHANICAL JOINT	JB JUNCTION BOX	USGS UNITED STATES GEOLOGICAL SURVEY	
DOT DEPARTMENT OF TRANSPORTATION	MJRJ MECHANICAL JOINT RETAINER GLAND	JB JUNCTION BOX	USGS UNITED STATES GEOLOGICAL SURVEY	
DWG(S) DRAWING(S)	MJTR MECHANICAL JOINT WITH TIE ROD	JB JUNCTION BOX	USGS UNITED STATES GEOLOGICAL SURVEY	
<b>E</b>	<b>N</b>	JB JUNCTION BOX	USGS UNITED STATES GEOLOGICAL SURVEY	
E EAST, EASTING	N NORTH, NORTHING, NITROGEN (TOTAL AS N)	JB JUNCTION BOX	USGS UNITED STATES GEOLOGICAL SURVEY	
EA EACH	N/A NOT APPLICABLE	JB JUNCTION BOX	USGS UNITED STATES GEOLOGICAL SURVEY	
ECL EROSION CONTROL LINE	NAD NORTH AMERICAN DATUM (HORIZONTAL)	JB JUNCTION BOX	USGS UNITED STATES GEOLOGICAL SURVEY	
EFF EFFLUENT, EFFICIENCY	NAVD NORTH AMERICAN VERTICAL DATUM	JB JUNCTION BOX	USGS UNITED STATES GEOLOGICAL SURVEY	
EG EXISTING GRADE	NC NORMALLY CLOSED	JB JUNCTION BOX	USGS UNITED STATES GEOLOGICAL SURVEY	
EJ EXPANSION JOINT	NF NEAR FACE	JB JUNCTION BOX	USGS UNITED STATES GEOLOGICAL SURVEY	
EL ELEVATION	NIC NOT IN CONTRACT	JB JUNCTION BOX	USGS UNITED STATES GEOLOGICAL SURVEY	
ELB ELBOW	NO NORMALLY OPEN	JB JUNCTION BOX	USGS UNITED STATES GEOLOGICAL SURVEY	
ELL ELBOW	NO NUMBER(S)	JB JUNCTION BOX	USGS UNITED STATES GEOLOGICAL SURVEY	
ELEC ELECTRIC, ELECTRICAL	NOID NO IDENTIFICATION	JB JUNCTION BOX	USGS UNITED STATES GEOLOGICAL SURVEY	
ELEV ELEVATION	NPSH NET POSITIVE SUCTION HEAD	JB JUNCTION BOX	USGS UNITED STATES GEOLOGICAL SURVEY	
EMER EMERGENCY	NPSHR NET POSITIVE SUCTION HEAD REQUIRED	JB JUNCTION BOX	USGS UNITED STATES GEOLOGICAL SURVEY	
ENC ENCASEMENT	NPT NATIONAL PIPE THREAD	JB JUNCTION BOX	USGS UNITED STATES GEOLOGICAL SURVEY	
ENG ENGINEERING	NRS NON-RISING STEM	JB JUNCTION BOX	USGS UNITED STATES GEOLOGICAL SURVEY	
EOP EDGE OF PAVEMENT	NTS NOT TO SCALE	JB JUNCTION BOX	USGS UNITED STATES GEOLOGICAL SURVEY	
EOS EDGE OF SLAB	NWL NORMAL WATER LEVEL	JB JUNCTION BOX	USGS UNITED STATES GEOLOGICAL SURVEY	
EOW EDGE OF WATER	<b>O</b>	JB JUNCTION BOX	USGS UNITED STATES GEOLOGICAL SURVEY	
EQ EQUAL	OD OUTSIDE DIAMETER	JB JUNCTION BOX	USGS UNITED STATES GEOLOGICAL SURVEY	
EQUIP EQUIPMENT	OHL OVERHEAD UTILITY LINE	JB JUNCTION BOX	USGS UNITED STATES GEOLOGICAL SURVEY	
ERCP ELLIPTICAL REINFORCED CONCRETE PIPE	OPP OPPOSITE	JB JUNCTION BOX	USGS UNITED STATES GEOLOGICAL SURVEY	
EX EXISTING	OR OFFICIAL RECORDS BOOK	JB JUNCTION BOX	USGS UNITED STATES GEOLOGICAL SURVEY	
EXP EXPANSION, EXPOSED	ORI OFFICIAL RECORDS INSTRUMENT	JB JUNCTION BOX	USGS UNITED STATES GEOLOGICAL SURVEY	
EXT EXTENSION, EXTERIOR, EXTERNAL	OZ OUNCE	JB JUNCTION BOX	USGS UNITED STATES GEOLOGICAL SURVEY	
<b>F</b>	<b>O</b>	JB JUNCTION BOX	USGS UNITED STATES GEOLOGICAL SURVEY	
FCA FLANGED COUPLING ADAPTER	OD OUTSIDE DIAMETER	JB JUNCTION BOX	USGS UNITED STATES GEOLOGICAL SURVEY	
FD FLOOR DRAIN	OHL OVERHEAD UTILITY LINE	JB JUNCTION BOX	USGS UNITED STATES GEOLOGICAL SURVEY	
FDOT FLORIDA DEPARTMENT OF TRANSPORTATION	OPP OPPOSITE	JB JUNCTION BOX	USGS UNITED STATES GEOLOGICAL SURVEY	
FDEP FLORIDA DEPARTMENT OF ENVIRONMENTAL PROTECTION	OR OFFICIAL RECORDS BOOK	JB JUNCTION BOX	USGS UNITED STATES GEOLOGICAL SURVEY	
FF FINISHED FLOOR	ORI OFFICIAL RECORDS INSTRUMENT	JB JUNCTION BOX	USGS UNITED STATES GEOLOGICAL SURVEY	
FFE FINISHED FLOOR ELEVATION	OZ OUNCE	JB JUNCTION BOX	USGS UNITED STATES GEOLOGICAL SURVEY	
FG FINISHED GRADE	<b>Y</b>	JB JUNCTION BOX	USGS UNITED STATES GEOLOGICAL SURVEY	
FHA FIRE HYDRANT ASSEMBLY	YH YARD HYDRANT	JB JUNCTION BOX	USGS UNITED STATES GEOLOGICAL SURVEY	
FIG FIGURE		JB JUNCTION BOX	USGS UNITED STATES GEOLOGICAL SURVEY	
FL FLOOR, FLOW LINE		JB JUNCTION BOX	USGS UNITED STATES GEOLOGICAL SURVEY	

### LEGENDS NOTES:

- REFER TO PROCESS MECHANICAL LEGENDS FOR VALVE, PIPE JOINT, AND PIPE FITTING SYMBOLS.
  - LEGEND SYMBOLS AND ABBREVIATIONS SHOWN IN THIS DRAWING ARE BASED ON A TEMPLATE THAT IS NOT PROJECT SPECIFIC.
- NOT USED ON THIS SPECIFIC PROJECT, BUT ARE SHOWN TO PROVIDE A DICTIONARY FOR SYMBOLS AND ABBREVIATIONS THAT MAY ALSO BE USED DURING THE PROJECT CONSTRUCTION PHASE.

THIS ITEM HAS BEEN DIGITALLY SIGNED AND SEALED BY MARK E. MARTIN, PE ON THE DATE INDICATED HERE. PRINTED COPIES OF THIS DOCUMENT ARE NOT CONSIDERED SIGNED AND SEALED AND THE SIGNATURE MUST BE VERIFIED ON ANY ELECTRONIC COPIES.

## LEE COUNTY UTILITIES

## THREE OAKS WATER RECLAMATION FACILITY DEEP INJECTION WELL IW-2

## PRELIMINARY - NOT FOR CONSTRUCTION

REVISIONS AND RECORD OF ISSUE	
DESIGNED:	CLB
DETAILED:	AIP
CHECKED:	MM
APPROVED:	MEM
DATE:	SEPTEMBER 2023
PROJECT NO.:	414567

## CIVIL

## LEGENDS, CIVIL AND PROCESS MECHANICAL ABBREVIATIONS

PLOTTED: 8/31/2023 2:28:48 PM  
 FILE: C:\PW\WORKING\B\WV\_AMERICAS\_201749730\C-0



**LEGEND:**

 PROPOSED CONTRACTOR STAGING AREA

**BLACK & VEATCH**

Black & Veatch Corporation  
 Certificate No. 8132  
 4415 Metro Parkway, Suite 200  
 Fort Myers, Florida 33916

THIS ITEM HAS BEEN DIGITALLY SIGNED AND SEALED BY MARK E. MARTIN, PE ON THE DATE INDICATED HERE. PRINTED COPIES OF THIS DOCUMENT ARE NOT CONSIDERED SIGNED AND SEALED AND THE SIGNATURE MUST BE VERIFIED ON ANY ELECTRONIC COPIES.

**LEE COUNTY UTILITIES**

THREE OAKS WATER RECLAMATION FACILITY  
 DEEP INJECTION WELL IW-2


**PRELIMINARY - NOT FOR CONSTRUCTION**

NO.	DESCRIPTION	DATE

REVISIONS AND RECORD OF ISSUE	
DESIGNED:	CLB
DETAILED:	CJC
CHECKED:	MM
APPROVED:	MEM
DATE:	SEPTEMBER 2023
PROJECT NO.:	414567

CIVIL

AERIAL SITE PLAN



PLOTTED: 8/31/2023 2:22:14 PM  
 FILE: C:\PW\_WORKING\BWW\_AMERICAS\_201748730\C-101.DWG  
 FD11000  
 D11000

(SCALE BAR IS 4" AT FULL SCALE) 0 1/2 1 2 3 4

THIS ITEM HAS BEEN DIGITALLY SIGNED AND SEALED BY MARK E. MARTIN, PE ON THE DATE INDICATED HERE. PRINTED COPIES OF THIS DOCUMENT ARE NOT CONSIDERED SIGNED AND SEALED AND THE SIGNATURE MUST BE VERIFIED ON ANY ELECTRONIC COPIES.

**LEE COUNTY UTILITIES**

THREE OAKS WATER RECLAMATION FACILITY  
 DEEP INJECTION WELL IW-2

**PRELIMINARY - NOT FOR CONSTRUCTION**

REVISIONS AND RECORD OF ISSUE

DESIGNED:	RS
DETAILED:	AIP
CHECKED:	MM
APPROVED:	MEM
DATE:	NOVEMBER 2023
PROJECT NO.:	414567

CIVIL

GRADING AND DRAINAGE PLAN

C-102

OF




20' 10' 0 20' 40'  
 SCALE = 1"=20'

**LEGEND**

- STREET LIGHT
- OAK TREE
- PINE TREE
- STORM DRAIN INLET
- ELECTRICAL POLE
- GUY WIRE
- OVERHEAD POWER
- BOLLARD
- SIGN
- SILT FENCE
- HAY BALE
- TOC TOP OF CURB
- TOP TOP OF PAD

NOTE: EXISTING FEATURES ARE SCREENED.



COORDINATE TABLE			
Point NO.	Northing	Easting	Elevation
①	777244.66	723673.70	19.01
②	777244.37	723674.60	18.35
③	777235.93	723656.64	18.56
④	777235.03	723656.35	17.90
⑤	777285.94	723631.06	18.16
⑥	777286.23	723630.17	17.50
⑦	777294.66	723648.12	18.56
⑧	777295.56	723648.41	17.90
⑨	777224.83	723672.04	17.65
⑩	777224.71	723675.69	17.70
⑪	777220.38	723667.23	17.70
⑫	777227.50	723663.58	17.65
⑬	777289.55	723623.87	17.16
⑭	777238.53	723635.60	16.62
⑮	777188.99	723656.86	16.91

**GRADING AND DRAINAGE PLAN**  
 SCALE = 1" = 20'

NOTE: ALL ELEVATION ARE REFERENCE TO NORTH AMERICAN VERTICAL DATUM OF 1988. (NAVD 88)

PLOTTED: 2/29/2024 1:46:33 PM  
 FILE: C:\PW\_WORKING\BWW\_AMERICAS\_201749730\C-102.DWG  
 PLOT: 01/10/00  
 D:\11000

(SCALE BAR IS 4" AT FULL SCALE) 0 1/2 1 2 3 4

THIS ITEM HAS BEEN DIGITALLY SIGNED AND SEALED BY MARK E. MARTIN, PE ON THE DATE INDICATED HERE. PRINTED COPIES OF THIS DOCUMENT ARE NOT CONSIDERED SIGNED AND SEALED AND THE SIGNATURE MUST BE VERIFIED ON ANY ELECTRONIC COPIES.

**LEE COUNTY UTILITIES**

**THREE OAKS WATER RECLAMATION FACILITY DEEP INJECTION WELL IW-2**

**PRELIMINARY - NOT FOR CONSTRUCTION**


REVISIONS AND RECORD OF ISSUE	
DESIGNED:	CLB
DETAILED:	CJC
CHECKED:	MM
APPROVED:	MEM
DATE:	SEPTEMBER 2023
PROJECT NO.:	414567

CIVIL

**YARD PIPING PLAN**

**C-103**

OF




**EXISTING PIPING PLAN**  
 SCALE = 1" = 20'

- NOTES:**
- DRAIN LINE SHALL BE INSTALLED AT A SLOPE OF 0.5%.
  - FOUR SURFICIAL AQUIFER MONITOR WELLS, IDENTIFIED AS PAD MONITORING WELLS (PMWs), SHALL BE LOCATED NEAR THE CORNERS OF THE PAD TO BE CONSTRUCTED FOR THE INJECTION WELL, AND SHALL BE IDENTIFIED BY NUMBER OR PAD LOCATION, I.E. NW, NE, SW, AND SE. IF LOCATED IN A TRAFFIC AREA, THE WELL HEAD(S) MUST BE PROTECTED BY TRAFFIC BEARING ENCLOSURE(S) AND COVER(S). EACH COVER MUST LOCK AND BE SPECIFICALLY MARKED TO IDENTIFY THE WELL AND ITS PURPOSE. THE PMWs SHALL BE SAMPLED IN ACCORDANCE WITH THE FDEP CONSTRUCTION PERMIT AND SPECIFICATIONS.
  - EXISTING WET WELL IS FIBERGLASS REINFORCED POLYESTER (FRP). SEE PART 1 SPECIFICATIONS - ATTACHMENT 1 FOR DRAWING D-120-105 OF THE EXISTING LIFT STATION FOR REFERENCE. FIELD PENETRATIONS FOR INLET HUBS AND CUTOUTS CAN BE MADE WITH A HOLE OR JIGSAW AND SHALL BE SEALED WITH WATERPROOF EPOXY COMPATIBLE WITH THE EXISTING FRP WET WELL. WET WELL INLETS OR HUBS CAN BE FIELD FABRICATED WITH SHORT PIECES OF PVC PIPE, PIPE COUPLING OR A BELL END OF A GASKET JOINT PVC PIPE. TURN THE GASKET JOINT "UP STREAM" TO MAKE IT A FLEXIBLE CONNECTION. CUT A REASONABLE ROUND HOLE, INSERT PIPE INTO WET WELL, AND "MUD AND WIPE" THE JOINT BOTH INSIDE AND OUTSIDE WITH SUITABLE EPOXY. COORDINATE WITH OWNER FOR THE SUPPLIER OF THE EXISTING FRP WET WELL TO DETERMINE SUITABLE WATERPROOF EPOXY.

PLOTTED: 8/31/2023 2:22:48 PM  
 FILE: C:\PW\_WORKING\BWW\_AMERICAS\_201749730\C-103.DWG  
 FD11000  
 D11000


STANDARD DETAIL NO. 6.2  
LEE COUNTY UTILITIES  
VALVE INSTALLATION



- ① BRASS PLATE: SIZE OF VALVE, VALVE TYPE  
No. OF TURNS & DIRECTION TO OPEN  
VALVE M.F.G. & YEAR INSTALL  
SYSTEM "WATER" OR "SEWER" OR "REUSE" OR "FIRE"
- ② ANCHOR
- ③ EIGHT (8) #4 BARS OVERLAP EACH CORNER BY 2"
- ④ 30" SQ X 4" THK CONC. PAD SURROUNDING BOX, MIN.  
3,000 P.S.I. POURED IN PLACE
- ⑤ SET TOP OF BOX FLUSH WITH FINISHED GRADE
- ⑥ HEAVY DUTY TRAFFIC BEARING CAST IRON VALVE BOX, ADJUSTABLE SCREW  
TYPE, 5 1/4" DIAMETER SHAFT THAT IS LCU APPROVED
- ⑦ EXTENSION STEM WITH 2" OPERATING NUT AS REQUIRED, IF NUT IS  
MORE THAN 30" BELOW FINISH GRADE
- ⑧ RISER NOT TO BEAR ON VALVE OR PIPE
- ⑨ CAST IRON DROP COVER MARKED "WATER" OR "SEWER" OR "REUSE OR "FIRE"
- ⑩ COMPACTED SUITABLE EARTH BACKFILL
- ⑪ 3/4" GRANULAR MATERIAL #57 STONE
- ⑫ 12 GAUGE DOUBLE INSULATED COPPER LOCATING WIRE (SEE LCU STANDARD DETAIL)

REV: 12/10/2015


STANDARD DETAIL NO. 6.5  
LEE COUNTY UTILITIES  
TRENCH CROSS SECTION



- ① EXCAVATED TRENCH
- ② FINISHED GRADE
- ③ MARKING TAPE 12" DEPTH MAX.
- ④ MATERIALS CLEAN DRY SAND, FINE LIME ROCK OR PIT SHELL  
MECHANICALLY COMPACTED IN  
6" LIFTS TO AT LEAST 95% OF  
MAX. DENSITY, OR 98% IF UNDER  
PAVED AREA OF ROADWAY.
- ⑤ #57 STONE LOCATED UNDER PIPE  
OR EXISTING UNDISTURBED  
SUITABLE MATERIAL
- ⑥ SPRING LINE
- ⑦ STANDARD 8" MIN TRENCH UNDERCUT  
AND BACKFILL WITH #57 STONE  
COMPACTED IN 6" LIFTS  
ADDITIONAL UNDERCUT AND CRUSHED ROCK  
BEDDING FOUNDATION WHEN DIRECTED BY  
L.C.U. THE CONTRACTOR IS TO REMOVE  
UNSTABLE MATERIAL FROM THE TRENCH  
FOUNDATION. THEN INSTALL STABILIZED  
CRUSHED ROCK BACKFILL WITH #57 STONE  
COMPACTED IN 6" LIFTS
- ⑧ LOCATING WIRE IS REQUIRED FOR ALL  
PRESSURIZED PIPELINES.

REV: 12/10/2015



STANDARD DETAIL NO. 6.40  
LEE COUNTY UTILITIES  
6" OR 8" SEWER CLEAN-OUT DETAIL



- ① IN ALL CASES USE TRAFFIC BEARING HANDHOLE RING & COVER OR EQUAL ADJUSTED TO FINAL GRADE WITH CLEANOUT RECESSER
- ② 6" OR 8" THREADED CAP
- ③ 6" OR 8" PVC FEMALE ADAPTER
- ④ 6" OR 8" PVC RISER
- ⑤ CONCRETE COLLAR 24"x24"x4"
- ⑥ 6" OR 8" 45° ELBOW
- ⑦ W/WATERTIGHT PLUG
- ⑧ THE CONNECTION MUST BE MADE TO THE DOUBLE 45° WYE (SIZE TBD)
- ⑨ 6" OR 8" PVC SEWER PIPE


REV: 08/28/2019

STANDARD DETAIL NO. 6.8  
LEE COUNTY UTILITIES  
WATER AND SEWER CROSSING DETAIL



REV: 12/10/2015

STANDARD DETAIL NO. 6.44  
LEE COUNTY UTILITIES  
BOLLARD POST DETAIL



- ① FILL AND TOP PIPE WITH CONCRETE
  - ② 6" DIA. x 6'-0" LONG PRESSURE CLASS 350 DUCTILE IRON PIPE
  - ③ 3'-0" MINIMUM
  - ④ PAVEMENT
  - ⑤ FINISHED GRADE
  - ⑥ 3"
  - ⑦ 18" DIA. CONCRETE ENCASEMENT 3000 P.S.I.
- NOTE:  
1. PAINT BOLLARD TO LCU STANDARDS

REV: 12/10/2015



A STORAGE TANK OVERFLOW  
C-101 NO SCALE

THIS ITEM HAS BEEN DIGITALLY SIGNED AND SEALED BY MARK E. MARTIN, PE ON THE DATE INDICATED HERE. PRINTED COPIES OF THIS DOCUMENT ARE NOT CONSIDERED SIGNED AND SEALED AND THE SIGNATURE MUST BE VERIFIED ON ANY ELECTRONIC COPIES.

LEE COUNTY UTILITIES

THREE OAKS WATER RECLAMATION FACILITY  
DEEP INJECTION WELL IW-2

PRELIMINARY - NOT FOR CONSTRUCTION

REVISIONS AND RECORD OF ISSUE	
DESIGNED:	CLB
DETAILED:	AIP
CHECKED:	MM
APPROVED:	MEM
DATE:	SEPTEMBER 2023
PROJECT NO.:	414567

CIVIL

DETAILS 1

C-501

OF

THIS ITEM HAS BEEN DIGITALLY SIGNED AND SEALED BY MARK E. MARTIN, PE ON THE DATE INDICATED HERE. PRINTED COPIES OF THIS DOCUMENT ARE NOT CONSIDERED SIGNED AND SEALED AND THE SIGNATURE MUST BE VERIFIED ON ANY ELECTRONIC COPIES.

LEE COUNTY UTILITIES

THREE OAKS WATER RECLAMATION FACILITY  
 DEEP INJECTION WELL IW-2

PRELIMINARY - NOT FOR CONSTRUCTION

REVISIONS AND RECORD OF ISSUE	
DESIGNED:	RS
DETAILED:	ELJ
CHECKED:	MM
APPROVED:	MEM
DATE:	SEPTEMBER 2023
PROJECT NO.:	414567

CIVIL


DETAILS 2

C-502


OF

EROSION CONTROL NOTES:

1. CONTRACTOR TO PROVIDE SILT FENCE, COMPOSITE SOCK FILTER AND OTHER APPROPRIATE MEASURES TO AFFECT THE FILTRATION OF SURFACE WATER FLOWS AND TO PROVIDE EROSION PROTECTION DURING CONSTRUCTION ACTIVITIES. PROTECTION IS TO BE MAINTAINED DURING THE CONSTRUCTION PERIOD UNTIL DISTURBED SOILS HAVE BEEN STABILIZED WITH GRASS OR SUITABLE EROSION PROTECTION TREATMENT.
2. REFER TO FDOT INDEX NO. 102 AND 103 FOR EROSION CONTROL APPLICATIONS.
3. PRIOR TO COMMENCEMENT OF CONSTRUCTION ACTIVITY, APPROPRIATE EROSION CONTROL DEVICES SHALL BE INSTALLED TO CONTROL AND REDUCE SOIL EROSION AND SEDIMENT TRANSPORT TO OFF SITE AREAS. THE CONTRACTOR SHALL MAINTAIN THESE DEVICES THROUGHOUT THE DURATION OF CONSTRUCTION. ALL DEVICES SHALL REMAIN IN PLACE UNTIL THE SURROUNDING AREAS ARE ESTABLISHED.
4. AFTER 0.5 INCH OF RAIN OR EVERY SEVEN DAYS THE EROSION CONTROL SYSTEM IS TO BE INSPECTED.



**CHART I**  
 RECOMMENDED SPACING FOR BALED HAY BARRIERS AND TYPE III SILT FENCE



2006 FDOT Design Standards

Last Revision  
00

Sheet No.  
1 of 3

TEMPORARY EROSION AND SEDIMENT CONTROL

Index No.  
102


THIS ITEM HAS BEEN DIGITALLY SIGNED AND SEALED BY MARK E. MARTIN, PE ON THE DATE INDICATED HERE. PRINTED COPIES OF THIS DOCUMENT ARE NOT CONSIDERED SIGNED AND SEALED AND THE SIGNATURE MUST BE VERIFIED ON ANY ELECTRONIC COPIES.

LEE COUNTY UTILITIES


THREE OAKS WATER RECLAMATION FACILITY  
 DEEP INJECTION WELL IW-2

PRELIMINARY - NOT FOR CONSTRUCTION


REVISIONS AND RECORD OF ISSUE	
DESIGNED:	RS
DETAILED:	ELJ
CHECKED:	MM
APPROVED:	MEM
DATE:	SEPTEMBER 2023
PROJECT NO.:	414567



**PROTECTION AROUND INLETS OR SIMILAR STRUCTURES**




**BARRIER FOR PAVED DITCH**



**ALONG FILL SLOPE**

**ELEVATION**

Note:  
 Where the slope length exceeds 25 feet, construct one row of bale barriers at 0% longitudinal grade midway up the slope. Construct two rows of bale barriers where the slope length exceeds 50 feet.




**ELEVATION**

**ELEVATION**

**TYPE II**

**TYPE I**

**BARRIERS FOR UNPAVED DITCHES**



**ELEVATION**

**ELEVATION**

TO BE USED WHERE THE NATURAL GROUND SLOPES TOWARD THE TOE OF SLOPE


TO BE USED WHERE THE NATURAL GROUND SLOPES AWAY FROM THE TOE OF SLOPE

**AT TOE OF SLOPE**

**BARRIERS FOR FILL SLOPES**

**NOTES FOR BALED HAY OR STRAW BARRIERS**

- Type I and II Barriers should be spaced in accordance with Chart 1, Sheet 1.
- Hay bales shall be trenched 3" to 4" and anchored with 2 - 1" x 2" (or 1" dia.) x 4' wood stakes. Stakes of other material or shape providing equivalent strength may be used if approved by the Engineer. Stakes other than wood shall be removed upon completion of the project.
- Rails and posts shall be 2" x 4" wood. Other materials providing equivalent strength may be used if approved by the Engineer.
- Adjacent bales shall be butted firmly together. Unavoidable gaps shall be plugged with hay or straw to prevent silt from passing.
- Where used in conjunction with silt fence, hay bales shall be placed on the upstream side of the fence.
- Bales to be paid for under the contract unit price for Baled Hay or Straw, EA. The unit price shall include the cost of filter fabric for Type I and II Barriers. Sand bags shall be paid for under the unit price for Sandbagging, CY. Rock bags to be paid for under the contract unit price for Rock Bags, EA.



2006 FDOT Design Standards

**TEMPORARY EROSION AND SEDIMENT CONTROL**

Last Revision 00 Sheet No. 2 of 3

Index No. 102

CIVIL

DETAILS 3

C-503

OF

THIS ITEM HAS BEEN DIGITALLY SIGNED AND SEALED BY MARK E. MARTIN, PE ON THE DATE INDICATED HERE. PRINTED COPIES OF THIS DOCUMENT ARE NOT CONSIDERED SIGNED AND SEALED AND THE SIGNATURE MUST BE VERIFIED ON ANY ELECTRONIC COPIES.

**LEE COUNTY UTILITIES**

THREE OAKS WATER RECLAMATION FACILITY  
 DEEP INJECTION WELL IW-2

**PRELIMINARY - NOT FOR CONSTRUCTION**

REVISIONS AND RECORD OF ISSUE	
DESIGNED:	RS
DETAILED:	ELJ
CHECKED:	MM
APPROVED:	MEM
DATE:	SEPTEMBER 2023
PROJECT NO.:	414567

CIVIL

DETAILS 4

C-504

OF

**TYPE III SILT FENCE**

**TYPE IX SILT FENCE**

**SILT FENCE APPLICATIONS**

**NOTES FOR SILT FENCES**

- Type III Silt Fence to be used at most locations. Where used in ditches, the spacing for Type III Silt Fence shall be in accordance with Chart 1, Sheet 1.
- Type IX Silt Fence to be used where large sediment loads are anticipated. Suggested use is where fill slope is 1:2 or steeper and length of slope exceeds 25 feet. Avoid use where the detained water may back into travel lanes or off the right of way.
- Do not construct silt fences across permanent flowing watercourses. Silt fences are to be at upland locations and turbidity barriers used at permanent bodies of water.
- Where used as slope protection, Silt Fence is to be constructed on 0% longitudinal grade to avoid channelizing runoff along the length of the fence.
- Silt Fence to be paid for under the contract unit price for Staked Silt Fence, (LF).

**JOINING TWO SILT FENCES**

Place the end post of one fence behind the end post of the other fence as shown.

Rotate both posts at least 180 degrees in a clockwise direction to create a tight seal with the fabric material.

Drive both posts into the ground and bury flap.

2006 FDOT Design Standards

TEMPORARY EROSION AND SEDIMENT CONTROL

Last Revision: 07/01/05 | Sheet No. 3 of 3 | Index No. 102


**EROSION CONTROL NOTES:**

- CONTRACTOR TO PROVIDE SILT FENCE, COMPOSITE SOCK FILTER AND OTHER APPROPRIATE MEASURES TO AFFECT THE FILTRATION OF SURFACE WATER FLOWS AND TO PROVIDE EROSION PROTECTION DURING CONSTRUCTION ACTIVITIES. PROTECTION IS TO BE MAINTAINED DURING THE CONSTRUCTION PERIOD UNTIL DISTURBED SOILS HAVE BEEN STABILIZED WITH GRASS OR SUITABLE EROSION PROTECTION TREATMENT.
- REFER TO FDOT INDEX NO. 102 AND 103 FOR EROSION CONTROL APPLICATIONS.
- CONTRACTOR TO USE APPROPRIATE SEDIMENT CONTROL METHOD FOR THE DITCH BOTTOM INLETS. I.E. COMPOSITE SOCKS.

**CROSSED SLOPED SECTION**

**CROWNED SECTION**

ASPHALT PAVEMENT  
NO SCALE



- DESIGN CRITERIA:**
- A stabilized construction entrance (SCE) IS APPROPRIATE IN THE FOLLOWING LOCATIONS:
    - WHEREVER VEHICLES ARE LEAVING A CONSTRUCTION SITE AND ENTER ONTO A PUBLIC ROAD
    - AT ANY UNPAVED ENTRANCE/EXIT LOCATION WHERE THERE IS RISK OF TRANSPORTING MUD OR SEDIMENT ONTO PAVED ROADS.
  - THE WIDTH SHOULD BE AT LEAST 10 FEET TO 12 FEET OR AS WIDE AS THE ENTIRE WIDTH OF THE ACCESS. AT SITES WHERE TRAFFIC VOLUME IS HIGH, THE ENTRANCE SHOULD BE WIDE ENOUGH FOR TWO VEHICLES TO PASS SAFELY.
  - RUNOFF FROM A STABILIZED CONSTRUCTION ENTRANCE SHOULD DRAIN TO A SEDIMENT TRAP OR SEDIMENT BASIN.
  - PRIOR TO PLACING GEOTEXTILE (FILTER FABRIC) MAKE SURE THAT THE ENTRANCE IS PROPERLY GRADED AND COMPACTED.
  - INSPECT THE STABILIZED CONSTRUCTION ENTRANCE ON A REGULAR BASIS AND AFTER THERE HAS BEEN A HIGH VOLUME OF TRAFFIC OR STORM EVENT. APPLY ADDITIONAL STONE PERIODICALLY AND WHEN REPAIR IS REQUIRED.
  - IMMEDIATELY REMOVE SEDIMENTS OR ANY OTHER MATERIALS TRACKED ONTO THE PUBLIC ROADWAY.

**STABILIZED CONSTRUCTION ENTRANCE**  
NOT TO SCALE

**SECTION NTS**

**PLAN NTS**

**Compost Socks for Sediment Control**  
NTS

**NOTES:**

- ALL MATERIAL TO MEET SPECIFICATIONS.
- COMPOST SOCKS FILL TO MEET APPLICATION REQUIREMENTS
- FILTER MEDIA TO BE DISPERSED ON SITE, AS DETERMINED BY ENGINEER.

**STRUCTURAL NOTES**

**GENERAL**

1. THE APPLICABLE BUILDING CODE IS INDICATED ON THE LOADING CRITERIA DRAWING.
2. THE REQUIREMENTS INDICATED ON THIS SHEET ARE INTENDED AS A BASIC SUMMARY OF THE MATERIAL AND CONSTRUCTION REQUIREMENTS FOR THE PROJECT. ADDITIONAL, MORE STRINGENT REQUIREMENTS ARE GIVEN IN THE PROJECT DETAIL DRAWINGS AND SPECIFICATIONS.
3. ALL STRUCTURAL RELATED SHOP DRAWINGS SHALL BE REVIEWED BY THE ENGINEER PRIOR TO CONSTRUCTION.
4. STRUCTURES MAY BE BUOYANT WHEN EMPTY DURING CONSTRUCTION. CONTRACTOR SHALL PROTECT STRUCTURES AGAINST FLOTATION UNTIL CONSTRUCTION IS COMPLETE.
5. STRUCTURES MAY BE UNSTABLE UNTIL THEY ARE CONSTRUCTED IN THEIR ENTIRETY. CONTRACTOR IS RESPONSIBLE FOR DESIGNING TEMPORARY STRUCTURAL SUPPORTS TO RESIST WIND LOADS, CONSTRUCTION LOADS, AND ANY OTHER TEMPORARY CONDITIONS THAT MAY OCCUR DURING CONSTRUCTION. IN ORDER TO MAINTAIN STABILITY OF THE CONSTRUCTION WORK, ANCHORS FOR CONTRACTOR'S TEMPORARY SUPPORT SYSTEMS THAT ATTACH TO CONCRETE OR MASONRY SHALL BE LOCATED TO AVOID DAMAGING EMBEDDED REINFORCEMENT OR UTILITIES.

**CAST-IN-PLACE CONCRETE**

1. A MINIMUM 28 DAY COMPRESSIVE STRENGTH ( $f'_c$ ) OF 4,000 PSI WAS UTILIZED IN THE DESIGN OF STRUCTURAL REINFORCED CONCRETE. SEE SPECIFICATIONS FOR CONSTRUCTION STRENGTH REQUIREMENTS.
2. THE LOCATION OF ALL CONSTRUCTION JOINTS AND OTHER TYPES OF JOINTS, OTHER THAN THOSE SPECIFIED OR SHOWN ON THE PLANS, SHALL BE ACCEPTABLE TO THE ENGINEER PRIOR TO PLACING CONCRETE.

**REINFORCING STEEL**

1. ALL REINFORCING BAR SHALL BE GRADE 60, DEFORMED, ASTM A615, UNLESS NOTED OTHERWISE.
2. DIMENSIONS TO REINFORCING BARS ARE TO BAR CENTERLINES, UNLESS NOTED OTHERWISE. BAR COVER IS THE CLEAR DISTANCE BETWEEN THE BAR AND THE CONCRETE SURFACE.
3. NO WELDING OF REINFORCING BARS SHALL BE PERMITTED UNLESS APPROVAL IS OBTAINED FROM THE ENGINEER PRIOR TO CONSTRUCTION.
4. FOR CONCRETE SLABS THAT HAVE A SLOPING TOP FACE, THE TOP LAYERS OF REINFORCEMENT SHALL BE PLACED ON A SIMILAR SLOPE SO THAT SPECIFIED COVER IS MAINTAINED.

**POST-INSTALLED ANCHORS**

1. POST-INSTALLED ANCHORS SHALL INCLUDE ADHESIVE ANCHORS (THREADED RODS, BOLTS OR REINFORCING BARS), EXPANSION ANCHORS, AND UNDERCUT ANCHORS INSTALLED INTO HARDENED CONCRETE OR MASONRY. SEE THE ANCHORAGE IN CONCRETE AND MASONRY SPECIFICATION SECTION FOR ADDITIONAL REQUIREMENTS.
2. POST-INSTALLED ANCHORS SHALL ONLY BE USED WHERE INDICATED ON THE DRAWINGS. CONTRACTOR SHALL OBTAIN APPROVAL FROM ENGINEER PRIOR TO USING POST-INSTALLED ANCHORS FOR MISSING OR MISPLACED CAST-IN-PLACE ANCHORS.
3. CARE SHALL BE TAKEN TO AVOID CONFLICTS WITH EXISTING REINFORCING STEEL AND OTHER EMBEDDED ITEMS WHEN DRILLING HOLES. REINFORCING BARS SHALL NOT BE DAMAGED DURING DRILLING OR ANCHOR INSTALLATION. HOLES SHALL BE DRILLED AND CLEANED PER THE PRODUCT MANUFACTURER'S INSTRUCTIONS. ANCHORS SHALL BE INSTALLED PER THE PRODUCT MANUFACTURER'S INSTRUCTIONS AT NOT LESS THAN MINIMUM EDGE DISTANCES AND/OR SPACING INDICATED IN THE MANUFACTURER'S LITERATURE.
4. SUBSTITUTION REQUESTS FOR PRODUCTS OTHER THAN THOSE LISTED IN THE SPECIFICATION OR INDICATED ON THE DRAWINGS SHALL BE SUBMITTED TO ENGINEER FOR REVIEW AND APPROVAL. PRODUCT ICC-ESR EVALUATION REPORTS SHALL BE INCLUDED WITH THE SUBMITTAL PACKAGE. IF REQUESTED, CALCULATIONS PREPARED BY A REGISTERED PROFESSIONAL ENGINEER USING METHODS AND PROCEDURES REQUIRED BY THE BUILDING CODE MAY BE REQUIRED AS PART OF THE SUBMITTAL PACKAGE.
5. UNLESS NOTED OTHERWISE, THE MINIMUM EMBEDMENT PROVIDED FOR ADHESIVE ANCHORED REINFORCING BARS SHALL DEVELOP THE FULL TENSILE STRENGTH OF THE BAR.
6. SPECIAL INSPECTION WILL BE PROVIDED FOR ALL POST-INSTALLED ANCHORS.

**STAINLESS STEEL**

1. STAINLESS STEEL BOLTS SHALL CONFORM TO ASTM F593, ALLOY GROUP 1 OR 2, UNLESS NOTED OTHERWISE. MINIMUM YIELD STRENGTH SHALL BE 45 KSI.
2. STAINLESS STEEL PLATES SHALL CONFORM TO ASTM A240, TYPE 316L.
3. STAINLESS STEEL STRUCTURAL SHAPES SHALL CONFORM TO ASTM A1069 OR ASTM A276, TYPE 316L.

**ALUMINUM**

1. UNLESS NOTED OTHERWISE, ALUMINUM ALLOY IN ALL ALUMINUM STRUCTURAL MATERIALS SHALL BE 6061-T6. PIPE AND TUBING FOR GUARDRAIL AND HANDRAIL SHALL BE ALLOY 6061-T6 OR 6005A-T61.
2. ALL ALUMINUM SURFACES IN CONTACT WITH CONCRETE OR DISSIMILAR METALS SHALL BE COATED OR COVERED WITH A HEAVY COAT OF BITUMINOUS PAINT TO PREVENT ALUMINUM-CONCRETE REACTION OR ELECTROLYTIC ACTION.

**STRUCTURAL STEEL**

1. ROLLED WIDE FLANGE SHAPES SHALL HAVE A MINIMUM YIELD STRENGTH OF 50 KSI; CHANNELS, PLATES, AND ANGLES A MINIMUM OF 36 KSI; STRUCTURAL PIPES A MINIMUM OF 35 KSI; ROUND STRUCTURAL TUBES A MINIMUM OF 46 KSI; RECTANGULAR STRUCTURAL TUBES A MINIMUM OF 50 KSI.
2. WELDING SHALL BE DONE WITH A FILLER MATERIAL HAVING A MINIMUM TENSILE STRENGTH OF 70 KSI.
3. BOLTED CONNECTIONS SHALL USE 3/4" DIA ASTM F3125, GRADE A325 BOLTS OR GRADE F1852 TWIST-OFF BOLTS, WITH THE THREADS EXCLUDED FROM THE SHEAR PLANE, UNLESS NOTED OTHERWISE.
4. CARBON STEEL OR GALVANIZED STEEL ANCHOR RODS AND ANCHOR BOLTS SHALL CONFORM TO ASTM F1554 GRADE 36.
5. HOLES FOR ANCHOR RODS AND ANCHOR BOLTS IN COLUMN BASE PLATES USING ASTM F844 OR F436 FLAT CIRCULAR WASHERS SHALL BE AS FOLLOWS:  
  
 BOLTS/RODS 3/4" TO 1" - 5/16" OVERSIZE  
 BOLTS/RODS 1" TO 2" - 1/2" OVERSIZE  
 BOLTS/RODS OVER 2" - 1" OVERSIZE  
  
 AT THE CONTRACTORS OPTION, OVERSIZE HOLES LARGER THAN THOSE LISTED ABOVE MAY BE USED, PROVIDED THAT 3/8" PLATE WASHERS ARE USED WITH STANDARD HOLES AND FIELD WELDED WITH A 5/16" FILLET WELD TO THE BASE PLATE ALONG A MIN OF 3 SIDES.

**EXCAVATION, BACKFILL, AND FOUNDATIONS**

1. FOUNDATION CONSTRUCTION SHALL NOT BEGIN UNTIL ANY REQUIRED INSPECTION HAS BEEN COMPLETED AND THE CONTRACTOR NOTIFIED TO PROCEED.
2. TO FACILITATE SCHEDULING, AT LEAST 48 HOURS ADVANCE NOTICE SHALL BE GIVEN TO THE ENGINEER PRIOR TO THE REQUIRED INSPECTIONS.
3. UNLESS NOTED OTHERWISE, BACKFILL SHALL NOT BE PLACED AGAINST WALLS WHICH SUPPORT A CONCRETE SLAB OR WALKWAY UNTIL THE TOP SLAB OR WALKWAY HAS BEEN PLACED IN ITS ENTIRETY AND ALL CONCRETE HAS REACHED THE SPECIFIED DESIGN STRENGTH.
4. OVER-EXCAVATION OF SOIL, OR OVER-BREAKING OF ROCK, THAT WOULD RESULT IN A STRUCTURAL CONCRETE THICKNESS GREATER THAN INDICATED ON THE DRAWINGS SHALL BE CLASSIFIED AS UNAUTHORIZED EXCAVATION. CONTRACTOR SHALL SELECT ONE OF TWO METHODS TO ADDRESS UNAUTHORIZED EXCAVATION.
  - REPLACE UNAUTHORIZED EXCAVATION MATERIAL WITH LEAN CONCRETE THAT IS PLACED SEPARATELY FROM THE STRUCTURAL CONCRETE INDICATED ON THE DRAWINGS. CONTRACTOR WILL RECEIVE NO ADDITIONAL PAYMENT FOR THE LEAN CONCRETE.
  - REPLACE UNAUTHORIZED EXCAVATION MATERIAL WITH STRUCTURAL CONCRETE THAT IS PLACED MONOLITHICALLY WITH THE STRUCTURAL CONCRETE INDICATED ON THE DRAWINGS. CREATING AN ENLARGED SECTION. CONTRACTOR SHALL NOTIFY ENGINEER FOR DIRECTION PRIOR TO PERFORMING THIS WORK. THE INCREASED CONCRETE THICKNESS MAY REQUIRE ADDITIONAL REINFORCEMENT AND/OR OTHER DESIGN MODIFICATIONS. IF THE INCREASED CONCRETE THICKNESS EXCEEDS 36 INCHES, ENGINEER MAY REQUIRE CONTRACTOR TO IMPLEMENT MASS CONCRETE HEAT MITIGATION PROCEDURES. CONTRACTOR WILL RECEIVE NO ADDITIONAL PAYMENT FOR EXTRA STRUCTURAL CONCRETE, ADDITIONAL REINFORCEMENT, OTHER DESIGN MODIFICATIONS, OR MASS CONCRETING PROCEDURES.
5. THE FOLLOWING NET ALLOWABLE BEARING PRESSURES WERE UTILIZED IN THE DESIGN OF THE FOUNDATIONS.  
  
 MAT FOUNDATIONS.....1500 PSF

**EXISTING STRUCTURES**

1. THE DRAWINGS DEPICT WORK AT EXISTING STRUCTURES. ALL DIMENSIONS AND ALL DEPICTIONS SHALL BE FIELD VERIFIED BY THE CONTRACTOR PRIOR TO ORDERING MATERIALS, STARTING FABRICATION, OR STARTING CONSTRUCTION.
2. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY DAMAGE, REPAIRS OR STRUCTURAL MODIFICATIONS THAT ARE REQUIRED DUE TO DEMOLITION BEYOND THE LIMITS IDENTIFIED IN THE DRAWINGS.
3. REINFORCEMENT FOR ANY EXISTING CONCRETE OR MASONRY ELEMENT SHALL NOT BE DAMAGED UNLESS THE ELEMENT IS TO BE DEMOLISHED. WHEN LOCATING EXISTING REINFORCEMENT IS REQUIRED, IT SHALL BE LOCATED USING NON-DESTRUCTIVE METHODS. REINFORCING STRANDS IN EXISTING PRESTRESSED CONCRETE SHALL NOT BE CUT UNLESS INDICATED ON THE DRAWINGS OR OTHERWISE AUTHORIZED BY THE ENGINEER. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY DAMAGE, REPAIRS OR STRUCTURAL MODIFICATIONS THAT ARE REQUIRED DUE TO DAMAGE OF CONCRETE, MASONRY OR REINFORCEMENT THAT HAS BEEN IDENTIFIED ON THE DRAWINGS TO REQUIRE FIELD VERIFICATION.
4. CORE DRILLING AND SAW CUTTING SHALL NOT BE PERFORMED UNLESS INDICATED ON THE DRAWINGS OR APPROVED BY ENGINEER.
5. EXPOSED CONCRETE SURFACES THAT REMAIN AFTER DEMOLITION SHALL BE REPAIRED TO MATCH ADJACENT CONCRETE SURFACES.
6. UNLESS OTHERWISE INDICATED ON THE DRAWINGS, EXPOSED CONCRETE SURFACES WITH REINFORCEMENT, ANCHOR BOLTS, HANGER RODS, OR OTHER EXPOSED METAL EMBEDMENTS SHALL BE REPAIRED BY CUTTING OFF THE METAL AT THE FACE OF THE CONCRETE, GRINDING SMOOTH, AND COATING. COATING SHALL EXTEND A MINIMUM OF 1" BEYOND THE EDGE OF ANY EXPOSED METAL.

**SPECIAL INSPECTIONS**

1. THERE ARE NO THRESHOLD BUILDINGS AS DEFINED BY FLORIDA BUILDING CODE. THEREFORE, SPECIAL INSPECTIONS ARE NOT REQUIRED.


**DELEGATED DESIGN**

1. THE FOLLOWING ITEMS ARE IDENTIFIED IN THE DRAWINGS AND SPECIFICATIONS AS BEING DESIGNED AND SEALED BY THE CONTRACTOR OR THE CONTRACTOR'S SUPPLIER IN ACCORDANCE WITH THE SPECIFICATIONS INDICATED BELOW. SUBMITTALS FOR THESE ITEMS SHALL BE PREPARED BY THE SUPPLIERS AND SUBMITTED TO ENGINEER AND CODE OFFICIAL FOR REVIEW.  
  
 SECTION 016700- EQUIPMENT AND NON-STRUCTURAL COMPONENTS.  
 SECTION 058100- EQUIPMENT ANCHORAGE.

**BASIC LOADING CRITERIA**

THE APPLICABLE BUILDING CODE IS THE 2020 FLORIDA BUILDING CODE, BASED ON THE 2018 INTERNATIONAL BUILDING CODE.

1. DEAD LOAD ..... CALCULATED
2. LIVE LOADS:  
 OPERATING AND PROCESS FLOORS..... 150 PSF  
 STAIRS, SERVICE PLATFORMS & LANDINGS..... 100 PSF  
 ALL FLOORS NOT INDICATED..... 100 PSF
3. LATERAL EARTH PRESSURE (EQUIVALENT FLUID PRESSURE)  
 NON-SATURATED..... 70 PSF/FT  
 SATURATED..... 100 PSF/FT
4. LATERAL SURCHARGE..... EQUIVALENT TO 2 FEET OF SOIL WHERE ADJACENT TO A ROADWAY
5. COMPACTIVE SURCHARGE LOAD..... 400 PSF AT FINISH GRADE ELEVATION DECREASING LINEARLY AT SAME RATE AS BACKFILL LOAD INCREASES. FOR WALLS 8 FEET OR LESS IN HEIGHT, USE CRITERIA 4 ABOVE AS COMPACTIVE SURCHARGE.
6. HYDROSTATIC FLUID PRESSURE..... 63 PSF/FT
7. SNOW LOAD:  
 GROUND SNOW LOAD ( $P_g$ )..... 0 PSF
8. SEISMIC LOAD:  
 MAPPED MCE SHORT PERIOD SPECTRAL RESPONSE ACCELERATION ( $S_s$ )..... 0.047g  
 MAPPED MCE ONE SECOND PERIOD SPECTRAL RESPONSE ACCELERATION ( $S_1$ )..... 0.023g  
 DESIGN SPECTRAL RESPONSE ACCELERATION AT SHORT PERIODS ( $S_{ps}$ )..... 0.050g  
 DESIGN SPECTRAL RESPONSE ACCELERATION AT ONE SECOND PERIOD ( $S_{p1}$ )..... 0.037g  
 SITE CLASS ..... D  
 SEISMIC DESIGN CATEGORY..... A
9. WIND LOAD:  
 BASIC (ULTIMATE) DESIGN WIND SPEED..... 169 MPH  
 ALLOWABLE STRESS (NOMINAL) DESIGN WIND SPEED..... 134 MPH  
 GROUND ELEVATION FACTOR ( $K_z$ )..... 1.0  
 EXPOSURE..... C
10. FLOOD DESIGN DATA:  
 DESIGN FLOOD ELEVATION..... NOT LOCATED IN FEMA FLOOD ZONE



**LEE COUNTY UTILITIES**

**THREE OAKS WATER RECLAMATION FACILITY DEEP INJECTION WELL IW-2**

**PRELIMINARY - NOT FOR CONSTRUCTION**

REVISIONS AND RECORD OF ISSUE	
DESIGNED:	JCG
DETAILED:	ERB
CHECKED:	yy
APPROVED:	JCG
DATE:	SEPTEMBER 2023
PROJECT NO.:	414567


STRUCTURAL

STANDARD NOTES AND LOADING CRITERIA

S-001

OF

PLOTTED: 8/30/2023 9:08:25 AM  
 FILE: C:\PW\WORKING\BWW\_AMERICAS\_2\01748735\5-001.DWG  
 FD11000  
 D11000



THIS ITEM HAS BEEN DIGITALLY SIGNED AND SEALED BY JULIA C. GLOSS, PE ON THE DATE INDICATED HERE. PRINTED COPIES OF THIS DOCUMENT ARE NOT CONSIDERED SIGNED AND SEALED AND THE SIGNATURE MUST BE VERIFIED ON ANY ELECTRONIC COPIES.

**LEE COUNTY UTILITIES**

**THREE OAKS WATER RECLAMATION FACILITY  
 DEEP INJECTION WELL IW-2**


**PRELIMINARY - NOT FOR CONSTRUCTION**

REVISIONS AND RECORD OF ISSUE	
DESIGNED:	JCG
DETAILED:	ERB
CHECKED:	YY
APPROVED:	JCG
DATE:	SEPTEMBER 2023
PROJECT NO.:	414567


STRUCTURAL

**WELL PAD PLAN AND SECTION**


**S-101** OF



**PLAN**  
 1/4" = 1'-0"



**SECTION**  
 S-101 3/8" = 1'-0"



(SCALE BAR IS 4" AT FULL SCALE) 0 1/2 1 2 3 4

PLOTTED: 8/30/2023 9:16:30 AM  
 FILE: C:\PW\WORKING\B\W\AMERICAS\_201748735\S-101.DWG  
 PLOT: 000  
 D:\11000

THIS ITEM HAS BEEN DIGITALLY SIGNED AND SEALED BY JULIA C. GLOSS, PE ON THE DATE INDICATED HERE. PRINTED COPIES OF THIS DOCUMENT ARE NOT CONSIDERED SIGNED AND SEALED AND THE SIGNATURE MUST BE VERIFIED ON ANY ELECTRONIC COPIES.

**LEE COUNTY UTILITIES**

**THREE OAKS WATER RECLAMATION FACILITY DEEP INJECTION WELL IW-2**

**PRELIMINARY - NOT FOR CONSTRUCTION**

REVISIONS AND RECORD OF ISSUE

DESIGNED:	JCG
DETAILED:	ERB
CHECKED:	YY
APPROVED:	JCG
DATE:	SEPTEMBER 2023
PROJECT NO.:	414567


STRUCTURAL

**SUCTION PIPING PAD PLAN AND SECTION**

**S-102**


OF

TO BE CONSTRUCTED BY OTHERS



**PLAN**  
3/8" = 1'-0"

**SECTION**  
S-101 3/8" = 1'-0"



(SCALE BAR IS 4" AT FULL SCALE) 0 1/2 1 2 3 4

THIS ITEM HAS BEEN DIGITALLY SIGNED AND SEALED BY JULIA C. GLOSS, PE ON THE DATE INDICATED HERE. PRINTED COPIES OF THIS DOCUMENT ARE NOT CONSIDERED SIGNED AND SEALED AND THE SIGNATURE MUST BE VERIFIED ON ANY ELECTRONIC COPIES.

**LEE COUNTY UTILITIES**

THREE OAKS WATER RECLAMATION FACILITY  
 DEEP INJECTION WELL IW-2

**PRELIMINARY - NOT FOR CONSTRUCTION**

REVISIONS AND RECORD OF ISSUE


DESIGNED:	JCG
DETAILED:	ERB
CHECKED:	YY
APPROVED:	JCG
DATE:	SEPTEMBER 2023
PROJECT NO.:	414567

STRUCTURAL

CONCRETE DETAILS


S-501

OF



NOTE: TYPICAL REQUIRED UNLESS ADDITIONAL REINFORCEMENT SPECIFICALLY INDICATED AT OPENINGS ON DRAWINGS

**TYPICAL EXTRA REINFORCEMENT AT ISOLATED RE-ENTRANT CORNERS**  
 NO SCALE




NOTE: WHEN CURB WIDTH EXCEEDS 8", PROVIDE ABOVE REINFORCEMENT IN EACH FACE OF CURB

**TYPICAL CONCRETE CURB DETAIL**  
 1" = 1'-0"


TYPICAL REQUIRED UNLESS ADDITIONAL REINFORCEMENT SPECIFICALLY INDICATED AT OPENINGS ON DRAWINGS

**TYPICAL EXTRA REINFORCEMENT AT OPENINGS 12" TO <= 54"**  
 NO SCALE




NOTE: FOUNDATION DIMENSIONS DETERMINED BY EQUIPMENT FURNISHED AND EQUIPMENT ANCHORAGE EDGE DISTANCE REQUIREMENTS.

**EXTERIOR EQUIPMENT FOUNDATION**  
 3/4" = 1'-0"




NOTES:  
 1. PLACE CONDUIT ONLY IN SHADED AREA.  
 2. FOR CONDUIT REQUIREMENTS SEE THE ELECTRICAL DRAWINGS AND SPECIFICATIONS.  
 3. CONDUIT THAT IS TOO LARGE OR CONGESTED TO FIT WITHIN THE SLAB AND REINFORCEMENT AS INDICATED SHALL BE ROUTED BELOW THE SLAB AS INDICATED IN THE ELECTRICAL SPECIFICATIONS OR ON THE DRAWINGS.

**CONDUIT PLACING DETAIL**  
 1" = 1'-0"



LENGTH OF LAPPED SPLICES FOR REINFORCEMENT (INCHES)					CONCRETE COVER FOR REINFORCEMENT	
UNLESS NOTED OTHERWISE ON THE DRAWINGS					UNLESS NOTED OTHERWISE ON THE DRAWINGS	
BAR SIZE *	BEAMS & COLUMNS		WALLS & SLABS		LOCATION	SPECIFIED COVER
	**TOP BARS	OTHERS	**TOP BARS	OTHERS		
#3	16	16	16	16	UNFORMED SURFACES ADJACENT TO EXCAVATION.....	3"
#4	19	16	19	16	SURFACES INSIDE OF OZONE CONTACTORS EXPOSED TO OZONE IN WATER OR AIR.....	3"
#5	24	18	24	18	TOP SURFACES OF SLABS THAT ARE SUBMERGED.....	3"
#6	33	26	29	22	FORMED SURFACES THAT ARE SUBMERGED, AND FORMED OR TOP SURFACES EXPOSED TO WEATHER, SATURATED AIR, OR EARTH.....	2"
#7	55	42	48	37	OTHER LOCATIONS:	
#8	69	53	60	46	BEAMS AND GIRDERS.....	1 1/2"
#9	84	65	74	57	SLABS, WALLS AND JOISTS:	
#10	103	79	91	70	#6 AND LARGER.....	1 1/2"
#11	122	94	108	83	#5 AND SMALLER.....	1"


NOTES:  
 1. COVER IS MEASURED TO NEAREST BAR, STIRRUP, TIE, OR SPIRAL, AS APPLICABLE.  
 2. TOLERANCES FOR CONCRETE COVER AND THE FABRICATION AND PLACING OF REINFORCEMENT SHALL CONFORM TO ACI 117.



GRATING THICKNESS 'T'	L SIZE AxAx1/4" INCHES	L SIZE 'B' INCHES	'C' ANCHOR	
			DIA	MIN 'E'
1"	1 3/4 x 1 3/4"	2 1/2x2 1/2x1/4	1/2"	3 1/4"
1 1/4"	1 3/4 x 1 3/4"	2 1/2x2 1/2x1/4	1/2"	3 1/4"
1 1/2"	1 3/4 x 1 3/4"	2 1/2x2 1/2x1/4	1/2"	3 1/4"
1 3/4"	2x2	3x3x3/8	3/4"	4 3/4"
2"	2 1/2x2 1/2"	3x3x3/8	3/4"	4 3/4"
2 1/4"	2 1/2x2 1/2"	3x3x3/8	3/4"	4 3/4"
2 1/2"	3x3"	3x3x3/8	3/4"	4 3/4"

NOTES:  
 1. ALL GRATING SUPPORTED ON CONCRETE SHALL HAVE AN EMBEDDED ANGLE RECESSED AS SHOWN UNLESS NOTED OTHERWISE. GRATING SUPPORTED BY THE FACE MOUNTED ANGLE SHALL BE USED WHERE THE CONCRETE EXTENDS ABOVE THE TOP OF THE GRATING OR AT EXISTING STRUCTURES.  
 2. WHERE GRATING IS REQUIRED TO BE STAINLESS STEEL, SUPPORT ANGLES SHALL ALSO BE STAINLESS STEEL.

**METAL GRATING SUPPORT**  
 NO SCALE



THIS ITEM HAS BEEN DIGITALLY SIGNED AND SEALED BY JULIA C. GLOSS, PE ON THE DATE INDICATED HERE. PRINTED COPIES OF THIS DOCUMENT ARE NOT CONSIDERED SIGNED AND SEALED AND THE SIGNATURE MUST BE VERIFIED ON ANY ELECTRONIC COPIES.

**LEE COUNTY UTILITIES**

THREE OAKS WATER RECLAMATION FACILITY  
 DEEP INJECTION WELL IW-2

**PRELIMINARY - NOT FOR CONSTRUCTION**


REVISIONS AND RECORD OF ISSUE	
DESIGNED:	JCG
DETAILED:	ERB
CHECKED:	YY
APPROVED:	JCG
DATE:	SEPTEMBER 2023
PROJECT NO.:	414567

STRUCTURAL


PIPE SUPPORT DETAILS

**S-502**


OF



**A CONCRETE SADDLE PIPE SUPPORT**  
 1" = 1'-0"



**D CONCRETE SUPPORT FOR BASE TEE OR BASE ELBOW**  
 1" = 1'-0"



THIS ITEM HAS BEEN DIGITALLY SIGNED AND SEALED BY MARK E. MARTIN, PE ON THE DATE INDICATED HERE. PRINTED COPIES OF THIS DOCUMENT ARE NOT CONSIDERED SIGNED AND SEALED AND THE SIGNATURE MUST BE VERIFIED ON ANY ELECTRONIC COPIES.

**LEE COUNTY UTILITIES**

THREE OAKS WATER RECLAMATION FACILITY  
 DEEP INJECTION WELL IW-2

**PRELIMINARY - NOT FOR CONSTRUCTION**


REVISIONS AND RECORD OF ISSUE	
DESIGNED:	JP
DETAILED:	AIP
CHECKED:	PC
APPROVED:	MEM
DATE:	SEPTEMBER 2023
PROJECT NO.:	414567

PROCESS MECHANICAL

LEGENDS AND NOTES


M-001 OF

**PIPE, EQUIPMENT & VALVE TAG LEGEND**




**PIPE & FITTINGS SYMBOL LEGEND**


**DOUBLE LINE**



**SINGLE LINE**




**ACTUAL VALVE SYMBOL LEGEND**





**GENERAL PROCESS MECHANICAL NOTES**

- LEGENDS SHOWN IN THIS DRAWING ARE BASED ON A TEMPLATE THAT IS NOT PROJECT SPECIFIC. SOME LEGEND SYMBOLS ARE NOT USED ON THIS PROJECT, BUT ARE SHOWN TO PROVIDE A DICTIONARY FOR SYMBOLS THAT MAY ALSO BE USED DURING THE PROJECT CONSTRUCTION PHASE.
- FOR PROCESS MECHANICAL ABBREVIATIONS, REFER TO GENERAL ABBREVIATIONS.
- REFER TO THE P&ID LEGEND AND ABBREVIATIONS FOR SINGLE-LINE VALVE, GATE, ACTUATOR, FITTING, EQUIPMENT, AND OTHER SYMBOLS.
- FITTING TYPES IN THE LEGEND ON THIS SHEET SHOW FLANGED END CONNECTIONS. FITTINGS FOR OTHER END CONNECTION TYPES ARE SIMILAR.
- VALVE TYPES IN THE LEGEND ON THIS SHEET REPRESENT THE TYPICAL APPEARANCE FOR EACH TYPE OF VALVE. THE ACTUAL VALVES USED FOR THIS PROJECT MAY VARY IN APPEARANCE.
- LAY PIPE TO UNIFORM GRADE BETWEEN INDICATED ELEVATION POINTS.
- SIZE OF FITTINGS SHOWN ON DRAWINGS SHALL MATCH CONNECTING PIPING, UNLESS OTHERWISE INDICATED. TYPE OF JOINT AND FITTING MATERIAL SHALL BE THE SAME AS CONNECTING PIPING.
- ALL REQUIRED HANGERS, SUPPORTS, BRACES, INSERTS, AND ACCESSORIES ARE NOT SHOWN ON THE DRAWINGS. PIPE SUPPORTS FOR 12-INCH DIAMETER AND SMALLER PIPES SHALL BE DESIGNED AND FURNISHED BY THE CONTRACTOR AS SPECIFIED.
- ALL PRESSURIZED OR SURCHARGED PIPELINES, PIPE FITTINGS, COUPLINGS, JOINTS, EXPANSION JOINTS, TANK CONNECTIONS, AND CHANNEL CONNECTIONS SHALL BE PROVIDED WITH THRUST RESTRAINT BASED ON SPECIFIED PRESSURES AND TEMPERATURES.
- NUMBER AND LOCATION OF UNIONS AND COUPLINGS SHOWN ON DRAWINGS IS ONLY APPROXIMATE. CONTRACTOR SHALL PROVIDE ALL UNIONS AND COUPLINGS REQUIRED BY THE SPECIFICATIONS AND AS NECESSARY TO FACILITATE CONVENIENT REMOVAL OF VALVES AND MECHANICAL EQUIPMENT.
- WHERE A GROOVED END JOINT IS SHOWN, IT SHALL BE THE RIGID JOINT TYPE UNLESS OTHERWISE SPECIFIED. WHERE A FLANGED COUPLING ADAPTER IS SHOWN, A STANDARD FLANGE SHALL BE JOINED TO THE COUPLING ADAPTER.
- CONTRACTOR SHALL ORIENT VALVES AS SPECIFIED.
- NOT ALL LEGEND SYMBOLS APPLY. THESE PROJECT IS UTILIZING THE SCHEMATIC VALVE SYMBOL LEGEND FOR VALVES DISPLAYED ON DRAWINGS FOR THIS PROJECT.

**SCHEMATIC VALVE SYMBOL LEGEND**





TO BE  
CONSTRUCTED  
BY OTHERS

**DEMOLITION PLAN**  
3/8" = 1'-0"

**GENERAL SHEET NOTES**

1. REUSE PIPE AND FITTINGS AS NECESSARY.
2. REMOVE PART OF SPOOL AS REQUIRED TO INSTALL NEW PLUG VALVE.



**Black & Veatch Corporation**  
Certificate No. 8132  
4415 Metro Parkway, Suite 200  
Fort Myers, Florida 33916

THIS ITEM HAS BEEN  
DIGITALLY SIGNED AND  
SEALED BY MARK E.  
MARTIN, PE ON THE DATE  
INDICATED HERE. PRINTED  
COPIES OF THIS DOCUMENT  
ARE NOT CONSIDERED  
SIGNED AND SEALED AND  
THE SIGNATURE MUST BE  
VERIFIED ON ANY  
ELECTRONIC COPIES.

**LEE COUNTY  
UTILITIES**

THREE OAKS WATER  
RECLAMATION FACILITY  
DEEP INJECTION  
WELL IW-2

**PRELIMINARY -  
NOT FOR  
CONSTRUCTION**



REVISIONS AND RECORD OF ISSUE	
DESIGNED:	JP
DETAILED:	RSF, ERB
CHECKED:	PC
APPROVED:	MEM
DATE:	SEPTEMBER 2023
PROJECT NO.:	414567

PROCESS MECHANICAL

EXISTING EFFLUENT  
PUMP STATION  
DEMOLITION PLAN

**M-101** OF

**LEGEND**



(SCALE BAR IS 4" AT FULL SCALE)

PLOTTED: 9/11/2023 12:54:58 PM  
 FILE: C:\PW\WORKING\B\W\AMERICAS\_201749735\M-101.DWG  
 PLOT: 011000  
 D:\11000

THIS ITEM HAS BEEN DIGITALLY SIGNED AND SEALED BY MARK E. MARTIN, PE ON THE DATE INDICATED HERE. PRINTED COPIES OF THIS DOCUMENT ARE NOT CONSIDERED SIGNED AND SEALED AND THE SIGNATURE MUST BE VERIFIED ON ANY ELECTRONIC COPIES.

**LEE COUNTY UTILITIES**

**THREE OAKS WATER RECLAMATION FACILITY DEEP INJECTION WELL IW-2**

**PRELIMINARY - NOT FOR CONSTRUCTION**

REVISIONS AND RECORD OF ISSUE


DESIGNED:	JP
DETAILED:	ERB, RSF
CHECKED:	PC
APPROVED:	MEM
DATE:	SEPTEMBER 2023
PROJECT NO.:	414567

MECHANICAL


**OVERALL PIPING CONNECTION PLAN**

**M-102**


OF



**OVERALL PIPING CONNECTION PLAN**  
 3/16" = 1'-0"



(SCALE BAR IS 4" AT FULL SCALE) 0 1/2 1 2 3 4



**GENERAL SHEET NOTES**

- MOTORIZED VALVE.
- OWNER PROVIDED VALVE. CONTRACTOR TO COORDINATE WITH VALVE MANUFACTURER AND ACTUATOR MANUFACTURER TO TEST AND CERTIFY CONDITION AND OPERATION OF THIS VALVING EQUIPMENT. REFER TO PART 2 - SECTION 40 05 62.16 FOR MORE INFORMATION. THIS CERTIFICATION MUST BE COMPLETED BEFORE THE VALVING EQUIPMENT IS INSTALLED IN THE PIPING.

**BLACK & VEATCH**

Black & Veatch Corporation  
 Certificate No. 8132  
 4415 Metro Parkway, Suite 200  
 Fort Myers, Florida 33916

THIS ITEM HAS BEEN DIGITALLY SIGNED AND SEALED BY MARK E. MARTIN, PE ON THE DATE INDICATED HERE. PRINTED COPIES OF THIS DOCUMENT ARE NOT CONSIDERED SIGNED AND SEALED AND THE SIGNATURE MUST BE VERIFIED ON ANY ELECTRONIC COPIES.

LEE COUNTY UTILITIES

THREE OAKS WATER RECLAMATION FACILITY  
 DEEP INJECTION WELL IW-2


PRELIMINARY - NOT FOR CONSTRUCTION

REVISIONS AND RECORD OF ISSUE	
DESIGNED:	JP
DETAILED:	RSF
CHECKED:	PC
APPROVED:	MEM
DATE:	SEPTEMBER 2023
PROJECT NO.:	414567

PROCESS MECHANICAL


WELL PAD PLAN AND SECTION

M-103 OF




TO BE CONSTRUCTED BY OTHERS

**WELL PAD PLAN**  
 1/4" = 1'-0"



TO BE CONSTRUCTED BY OTHERS

**SECTION**  
 1/4" = 1'-0"



(SCALE BAR IS 4" AT FULL SCALE)

PLOTTED: 9/15/2023 12:28:53 PM  
 FILE: C:\PW\WORKING\BWW\_AMERICAS\_201749735\M-103.DWG  
 FD11000  
 D11000

THIS ITEM HAS BEEN DIGITALLY SIGNED AND SEALED BY MARK E. MARTIN, PE ON THE DATE INDICATED HERE. PRINTED COPIES OF THIS DOCUMENT ARE NOT CONSIDERED SIGNED AND SEALED AND THE SIGNATURE MUST BE VERIFIED ON ANY ELECTRONIC COPIES.

**LEE COUNTY UTILITIES**

THREE OAKS WATER RECLAMATION FACILITY  
 DEEP INJECTION WELL IW-2

**PRELIMINARY - NOT FOR CONSTRUCTION**




REVISIONS AND RECORD OF ISSUE	
DESIGNED:	AS
DETAILED:	AJP
CHECKED:	PC
APPROVED:	MEM
DATE:	SEPTEMBER 2023
PROJECT NO.:	414567

MECHANICAL

**INJECTION WELL AND PAD MONITORING WELL DETAILS**

**M-502**

OF



(SCALE BAR IS 4" AT FULL SCALE)

THIS ITEM HAS BEEN DIGITALLY SIGNED AND SEALED BY MARK E. MARTIN, PE ON THE DATE INDICATED HERE. PRINTED COPIES OF THIS DOCUMENT ARE NOT CONSIDERED SIGNED AND SEALED AND THE SIGNATURE MUST BE VERIFIED ON ANY ELECTRONIC COPIES.

**LEE COUNTY UTILITIES**

THREE OAKS WATER RECLAMATION FACILITY  
 DEEP INJECTION WELL IW-2

**PRELIMINARY - NOT FOR CONSTRUCTION**

REVISIONS AND RECORD OF ISSUE


DESIGNED:	AS
DETAILED:	AIP, RSF
CHECKED:	PC
APPROVED:	MEM
DATE:	SEPTEMBER 2023
PROJECT NO.:	414567

MECHANICAL


INJECTION WELL WELLHEAD DETAILS

**M-503**

OF




**A** INJECTION WELLHEAD DETAIL  
 M-103 3/4" = 1'-0"




**NOTE:**  
 1. ALL PIPE AND FITTINGS SHALL BE STAINLESS STEEL.

**B** COMPANION FLANGE WITH BLOWOUT CONNECTION (BOF)  
 NO SCALE



**NOTE:**  
 1. 1" AND 2" THREADOLET SHALL BE WELDED ON IN FIELD AFTER TAPPING FINAL CASING FOR HOLE OF EQUAL SIZE.


**1** SECTION  
 3/4" = 1'-0"



(SCALE BAR IS 4" AT FULL SCALE)

# ELECTRICAL LEGENDS


## ONE-LINE DIAGRAM LEGEND




## SCHEMATIC SYMBOLS




## SWITCH & OUTLET SYMBOLS




## MISCELLANEOUS SYMBOLS




## BREAKER DETAILS



## CONDUIT & WIRING INSTALLATION LEGEND



## COMMUNICATION SYMBOLS



## PROTECTION/RELAY DEVICE NUMBERS

- 25 - SYNCHRONIZING OR SYNCHRONISM-CHECK DEVICE
- 27 - UNDERVOLTAGE RELAY
- 32 - DIRECTIONAL POWER RELAY
- 37 - UNDERCURRENT OR UNDERPOWER RELAY
- 46 - REV. PHASE OR PHASE-BAL. CURRENT RELAY
- 47 - PHASE SEQ. OR PHASE BAL. VOLTAGE RELAY
- 49 - MACHINE OR TRANSFORMER THERMAL RELAY
- 50 - INSTANTANEOUS OVERCURRENT
- 51 - AC TIME OVERCURRENT RELAY
- 52 - AC CIRCUIT BREAKER
- 59 - OVERVOLTAGE RELAY
- 63 - PRESSURE SWITCH
- 64 - GROUND DETECTOR RELAY
- 67 - AC DIRECTIONAL OVERCURRENT RELAY
- 71 - LIQUID OR GAS LEVEL RELAY
- 81 - FREQUENCY RELAY
- 83 - AUTOMATIC SELECTIVE CONTROL OR TRANSFER RELAY
- 86 - LOCKOUT RELAY
- 87 - DIFFERENTIAL PROTECTIVE RELAY

## LEE COUNTY UTILITIES

## THREE OAKS WATER RECLAMATION FACILITY DEEP INJECTION WELL IW-2

## PRELIMINARY - NOT FOR CONSTRUCTION

REVISIONS AND RECORD OF ISSUE	
DESIGNED:	DM
DETAILED:	DMF
CHECKED:	SJA
APPROVED:	DVM
DATE:	SEPTEMBER 2023
PROJECT NO.:	414567

## ELECTRICAL

## LEGENDS

PLOTTED: 8/29/2023 7:06:39 AM  
 FILE: C:\PW\WORKING\BWW\_AMERICAS\_2017487281E-001.DWG  
 PLOT: 000  
 D:\1000

# ELECTRICAL ABBREVIATIONS & NOTES



**Black & Veatch Corporation**  
 Certificate No. 8132  
 4415 Metro Parkway, Suite 200  
 Fort Myers, Florida 33916

## ELECTRICAL GENERAL NOTES

- SOLID LINES (————) INDICATE NEW WORK OR EQUIPMENT.
- SCREENED LINES (———) INDICATE EXISTING WORK OR EQUIPMENT.
- DASHED LINES (-----) INDICATE FUTURE WORK OR EQUIPMENT.
- REFER TO INDIVIDUAL DISCIPLINE CONTRACT DRAWINGS FOR ADDITIONAL ABBREVIATIONS, DETAILS, AND GENERAL DESIGN NOTES.
- LEGEND SHEETS ARE GENERAL. SOME SYMBOLS AND ABBREVIATIONS MAY NOT BE UTILIZED ON THIS SPECIFIC PROJECT.
- INFORMATION RELATED TO CIRCUIT IDENTIFICATION, WIRE & CONDUIT SIZES, AND ROUTING, IS ON THE FOLLOWING DRAWING TYPES.
  - A. ONE-LINE DIAGRAMS SHOW CIRCUIT IDENTIFICATION, WIRE QUANTITY AND SIZES, AND CONDUIT SIZE WITHIN STRUCTURES. ONE-LINE DIAGRAMS ALSO INDICATE ORIGIN AND DESTINATION OF CIRCUITS, AND IDENTIFY CIRCUITS ROUTED UNDERGROUND.
  - B. FOR CIRCUITS WITHOUT UNDERGROUND PORTIONS, BUILDING FLOOR PLANS SHOW LOCATION OF EQUIPMENT FOR DETERMINING CIRCUIT LENGTH WITHIN THE STRUCTURE. FOR CIRCUITS WITH UNDERGROUND PORTIONS, ANTICIPATED PENETRATION OF UNDERGROUND CONDUITS ARE SHOWN ON STRUCTURE PLANS FOR DETERMINING THE LENGTH OF THE IN-STRUCTURE PORTIONS OF CIRCUITS. BUILDING FLOOR PLANS MAY ALSO SHOW HOME RUNS FOR LIGHTING, RECEPTACLE, AND OTHER MISCELLANEOUS EQUIPMENT CIRCUITS.
  - C. SITE PLANS INDICATE THE GENERAL ROUTING OF UNDERGROUND CONDUITS AND DUCT BANKS. CIRCUITS ROUTED IN UNDERGROUND CONDUITS OR DUCT BANKS ARE INDICATED IN DUCT BANK SECTIONS REFERENCED ON THE SITE PLAN.
  - D. DUCT BANK SECTIONS AND SCHEDULES IDENTIFY CONDUIT SIZE, CONDUIT MATERIAL, ARRANGEMENT OF THE UNDERGROUND CONDUITS, AND CIRCUITS ROUTED IN EACH UNDERGROUND CONDUIT.

## AREA DESIGNATIONS

THE SPECIAL AREA DESIGNATION BOXES, AS DEFINED BELOW, ARE LOCATED ON THE PLAN DRAWINGS TO DEFINE ELECTRICAL INSTALLATION REQUIREMENTS. DESIGNATION BOXES ARE LOCATED WITHIN ROOM OR BELOW ROOM NUMBER. ALL INDOOR AREAS NOT INDICATED OTHERWISE ARE AREA TYPE 1 AND MINIMUM NEMA TYPE 1 ENCLOSURES.

- AREA TYPE 1A** CORROSIVE CHEMICAL FEED AND STORAGE ROOMS. CONDUIT SYSTEM SHALL BE EXPOSED SCHEDULE 80 PVC RIGID NON-METALLIC CONDUIT WITH PVC FITTINGS, BOXES AND ACCESSORIES.
- AREA TYPE 4** INDOOR WET LOCATIONS SUCH AS VAULTS, HOSEDOWN AREAS, BASEMENTS, ETC. MINIMUM NEMA TYPE 4 ENCLOSURE FOR EQUIPMENT AND GASKETED FITTINGS IN A CONDUIT SYSTEM.
- AREA TYPE 7A** CLASS 1, DIVISION 1 AREA AS DEFINED BY NEC. ALL EQUIPMENT AND CONDUIT SYSTEMS SHALL BE RATED FOR USE IN THIS AREA.
- AREA TYPE 7B** CLASS 1, DIVISION 2, GROUP C AND D (METHANE, GASOLINE) AS DEFINED BY NEC. EQUIPMENT AND CONDUITS SYSTEMS SHALL BE RATED FOR USE IN THIS AREA.
- AREA TYPE 12** INDOOR, DRY, DIRTY AREA. REQUIRES MINIMUM NEMA TYPE 12 GASKETED ENCLOSURES FOR ALL EQUIPMENT AND GASKETED FITTINGS IN CONDUIT SYSTEMS.

## GENERAL REQUIREMENTS

- THE CONTRACTOR SHALL BE RESPONSIBLE FOR ROUTING ALL CONDUITS NOT SHOWN ON THE PLANS. THIS SHALL INCLUDE ALL CONDUITS SHOWN ON THE ONE-LINES AND HOME-RUNS SHOWN ON THE PLAN DRAWINGS. CONDUITS SHALL BE ROUTED AS DEFINED IN THE SPECIFICATION.
- SPARE WIRES SHALL BE TAPED AND COILED AND LABELED TO INDICATE WHERE OTHER END OF SPARE WIRE IS LOCATED.
- IF EQUIPMENT SUPPLIED BY MANUFACTURER HAS A LARGER LOAD THAN VALUE SHOWN, THE CABLE CONDUIT AND ELECTRICAL EQUIPMENT SHALL BE ENLARGED, AS REQUIRED, TO ACCOMMODATE THE HIGHER VALUE.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR FURNISHING PROPERLY SIZED STARTER OVERLOADS FOR EQUIPMENT FURNISHED.
- LIGHTING AND RECEPTACLE CIRCUITS DESIGNATED ON THE FLOOR PLANS ARE NOT SHOWN ON THE ONE-LINES. CONDUCTORS FOR LIGHTING, RECEPTACLES, AND MISCELLANEOUS 120VAC CIRCUITS SHALL BE MINIMUM NO. 12AWG. CONDUIT FOR LIGHTING, RECEPTACLES, AND MISCELLANEOUS 120VAC CIRCUITS SHALL BE MINIMUM 3/4".
- IN AREAS WHERE THERE ARE OVERHEAD BRIDGE CRANES, HOISTS, ETC. NO CONDUITS SHALL BE RUN OVERHEAD THAT WILL INTERFERE WITH THE OPERATION OF THE EQUIPMENT.

## ELECTRICAL ABBREVIATIONS

<b>A</b>	AMBER, AMPERE, ALARM ALTERNATING CURRENT AIR CIRCUIT BREAKER ACCESS CARD READER AMPERE FRAME ADJUSTABLE FREQUENCY DRIVE ARC-FLASH REDUCTION DEVICE AMMETER ANNUNCIATOR ALARM RELAY AMMETER SWITCH, AMPERE SENSOR AMPERE TRIP AUTOMATIC TRANSFER SWITCH AUXILIARY AMERICAN WIRE GAUGE	<b>I</b>	INPUT/OUTPUT INSTANTANEOUS INTERCOM JUNCTION BOX	<b>S</b>	SHORT-TIME, SHIELDED, STARTER SURGE ARRESTER, SPEAKER AMPLIFIER SUPERVISORY CONTROL AND DATA ACQUISITION SULFUR HEXAFLUORIDE SPACE HEATER SOLID NEUTRAL SOLENOID OILER SINGLE POLE SURGE PROTECTION DEVICE SINGLE POLE DOUBLE THROW SINGLE POLE SINGLE THROW SELECTOR SWITCH, START/STOP, STAINLESS STEEL SOLID-STATE METERING SOLID STATE STARTER SOLID-STATE TRIP SUPERVISORY CONTROL SOLENOID VALVE SWB, SWBD SWITCHBOARD SWG, SWGR SWITCHGEAR
<b>B</b>	BUS BATTERY CHARGER BREAKER BRAKE BEARING TEMPERATURE	<b>J</b>	JUNCTION BOX	<b>T</b>	THERMOSTAT, TIMER, TOTALIZER, TRANSFORMER TACHOMETER TERMINAL BLOCK TIMER CLUTCH TIME DELAY RELAY TEMPERATURE TIMER MOTOR TORQUE TIMER RELAY, TRIAD TEMPERATURE SWITCH TELEPHONE TERMINAL BOARD
<b>C</b>	CLOSE, COUNTER, CONTACTOR, CONTROL, CCTV CAMERA CAPACITOR CIRCUIT BREAKER CIRCUIT BREAKER AUXILIARY CONTACT (OPEN WHEN BREAKER IS OPEN) CIRCUIT BREAKER AUXILIARY CONTACT (CLOSED WHEN BREAKER IS OPEN) CONTROL DAMPER CELL INTERLOCK CIRCUIT CHLORINE CABLE OPERATED SWITCH CONTROL PANEL CONTROL POWER TRANSFORMER CURRENT OF CONTROL RELAY, CARD READER CONTROL STATION CYCLE TIMER OR CURRENT TRANSFORMER CYCLE TIMER CLUTCH CYCLE TIMER MONITOR 2 CONDUCTOR 4" CONDUIT	<b>K</b>	KEY INTERLOCK THOUSAND AMPERES INTERRUPTING CURRENT THOUSAND CIRCULAR MIL KEY OPERATED KILOVOLT KILOVOLT AMPERE KILOVAR KILOWATT KILOWATT HOUR	<b>U</b>	UNDERGROUND UNINTERRUPTIBLE POWER SUPPLY
<b>D</b>	DIRECT CURRENT, DOOR CONTACT DOOR INTERLOCK DAMPER MOTOR, DEMAND METER, DIMMER SWITCH DOUBLE POLE DOUBLE THROW DOUBLE POLE SINGLE THROW DIFFERENTIAL PRESSURE REGULATOR DIFFERENTIAL PRESSURE SWITCH DISCONNECT SWITCH, DOOR SWITCH, DESKTOP STATION DISCHARGE VALVE LIMIT SWITCH	<b>L</b>	LOW, LEVEL, LONG-TIME LIGHTNING ARRESTER LOCAL AREA NETWORK LIGHTING CONTRACTOR LIGHTING CONTACTOR ENCLOSURE LIGHTING CONTROL ENCLOSURE LOCAL CONTROL PANEL LOCAL CONTROL STATION LOCAL-OFF-AUTO LOCAL-OFF-REMOTE LOCK OUT STOP LIGHTING PANEL LIMIT OR LEVEL SWITCH LIGHTING LOW WATER CUTOFF	<b>V</b>	VOLTS, VOLTAGE RESTRAINED VOLT AMPERE VARIOMETER VARIABLE FREQUENCY DRIVE VACUUM INTERRUPTER VALVE LIMIT SWITCH VOLTMETER VALVE POSITION INDICATOR VOLTMETER SWITCH
<b>E</b>	ELECTRIC OPERATOR FOR CONTROL DAMPER OR VALVE EMPTY CONDUIT ELECTRICAL DOOR STRIKE ELEVATION, EMERGENCY LIGHT ELECTRICAL MANHOLE ELECTRODE RELAY END SWITCH, REQUEST TO EXIT SENSOR EMERGENCY STOP ELAPSED TIME METER EXISTING EXPLOSION PROOF	<b>M</b>	MAGNETIC MOTOR STARTER MILLIAMPERE MAIN CIRCUIT BREAKER MOTOR CONTROL CENTER MOTOR CONTROL LINEUP MOISTURE DETECTOR, MOTION DETECTOR MAGNETIC DOOR LOCK MANUFACTURER MANHOLE, MOUNTING HEIGHT MOTOR OPERATED VALVE MOTOR PROTECTION RELAY MANUAL MOTOR STARTER MOTOR SPACE HEATER MANUAL TRANSFER SWITCH MILLIVOLT, MEDIUM VOLTAGE MEGAVOLT AMPERE	<b>W</b>	WHITE, WATTS WATTHOUR METER WATT METER WEATHERPROOF WEATHERPROOF IN-USE WALL STATION
<b>F</b>	FORWARD, FIELD FIBER OPTIC FEEDER PROTECTION RELAY FLOW SWITCH	<b>N</b>	NEUTRAL NEUTRAL GROUNDING RESISTOR NEUTRAL GROUNDING TRANSFORMER NORMALLY CLOSED NORMALLY OPEN, NUMBER	<b>X</b>	AUXILIARY RELAY TRANSFORMER EXPLOSION PROOF
<b>G</b>	GREEN, GROUND, GENERATOR, GROUND FAULT GROUND DETECTOR GENERATOR GROUND FAULT CURRENT INTERRUPTOR, GROUND FAULT INTERRUPTOR	<b>O</b>	OPEN OVERLOAD ON-OFF-AUTO ON-OFF-REMOTE OCCUPANCY SENSOR OVER/UNDER	<b>Y</b>	YELLOW
<b>H</b>	HIGH, HUMIDISTAT HANDHOLE HIGH MOTOR TEMPERATURE HAND-OFF-AUTO HAND-OFF-REMOTE HORSEPOWER HAND STATION HIGH WATER CUTOFF HERTZ (CYCLE)	<b>P</b>	PRIMARY, POWER, POLE PLANT CONTROL SYSTEM PUSH BUTTON, PULL BOX PHOTOELECTRIC SENSOR, PHOTOCCELL POWER FACTOR POWER FACTOR CORRECTION CAPACITOR PHASE PILOT LIGHT PROGRAMMABLE LOGIC CONTROLLER POWER PANEL PAIR PROXIMITY SWITCH PRESSURE SWITCH POTENTIAL TRANSFORMER, PROGRAM TIMER	<b>Z</b>	AUXILIARY RELAY, IMPEDANCE POSITION SWITCH ZERO SPEED SWITCH
		<b>Q</b>	NOT USED	<b>1-1PR#16S</b>	ONE, SINGLE PAIR, TWISTED SHIELDED #16 CABLE
		<b>R</b>	RED, RAISE, RELAY, REVERSE RECEPTACLE RESISTOR REMOTE HANDSET REPEATING TIMER RESISTANCE TEMPERATURE DETECTOR REMOTE TERMINAL UNIT REDUCED VOLTAGE SOLID STATE STARTER	<b>3-7/C#14</b>	THREE, SINGLE, SEVEN CONDUCTOR #14 MULTICONDUCTOR CONTROL CABLES

THIS ITEM HAS BEEN  
 DIGITALLY SIGNED AND  
 SEALED BY DAVID V.  
 MARTINS. PE ON THE DATE  
 INDICATED HERE. PRINTED  
 COPIES OF THIS DOCUMENT  
 ARE NOT CONSIDERED  
 SIGNED AND SEALED AND  
 THE SIGNATURE MUST BE  
 VERIFIED ON ANY  
 ELECTRONIC COPIES.

LEE COUNTY  
 UTILITIES

THREE OAKS WATER  
 RECLAMATION FACILITY  
 DEEP INJECTION  
 WELL IW-2

PRELIMINARY -  
 NOT FOR  
 CONSTRUCTION


REVISIONS AND RECORD OF ISSUE	
DESIGNED:	DM
DETAILED:	DMF
CHECKED:	SJA
APPROVED:	DVM
DATE:	SEPTEMBER 2023
PROJECT NO.:	414567

ELECTRICAL

ABBREVIATIONS AND  
 NOTES

E-002

OF



THIS ITEM HAS BEEN DIGITALLY SIGNED AND SEALED BY DAVID V. MARTINS, PE ON THE DATE INDICATED HERE. PRINTED COPIES OF THIS DOCUMENT ARE NOT CONSIDERED SIGNED AND SEALED AND THE SIGNATURE MUST BE VERIFIED ON ANY ELECTRONIC COPIES.

**LEE COUNTY UTILITIES**

THREE OAKS WATER RECLAMATION FACILITY  
 DEEP INJECTION WELL IW-2

**PRELIMINARY - NOT FOR CONSTRUCTION**

REVISIONS AND RECORD OF ISSUE


DESIGNED:	DM
DETAILED:	DMF
CHECKED:	SJA
APPROVED:	DVM
DATE:	SEPTEMBER 2023
PROJECT NO.:	414567

ELECTRICAL

ELECTRICAL SITE PLAN

E-101

OF



(SCALE BAR IS 4" AT FULL SCALE) 0 1/2 1 2 3 4

THIS ITEM HAS BEEN DIGITALLY SIGNED AND SEALED BY DAVID V. MARTINS, PE ON THE DATE INDICATED HERE. PRINTED COPIES OF THIS DOCUMENT ARE NOT CONSIDERED SIGNED AND SEALED AND THE SIGNATURE MUST BE VERIFIED ON ANY ELECTRONIC COPIES.

**LEE COUNTY UTILITIES**

THREE OAKS WATER RECLAMATION FACILITY  
 DEEP INJECTION WELL IW-2


**PRELIMINARY - NOT FOR CONSTRUCTION**

REVISIONS AND RECORD OF ISSUE

DESIGNED:	DV
DETAILED:	DMF
CHECKED:	SJA
APPROVED:	DVM
DATE:	SEPTEMBER 2023
PROJECT NO.:	414567

ELECTRICAL

PARTIAL SITE PLAN  
 DEMOLITION



5.0 MG GROUND  
 STORAGE TANK 80-T-3

5.0 MG GROUND  
 STORAGE TANK 80-T-4

CUT EXISTING 6\"/>

80-FCV-7

30\"/>

NOTE 1

EXISTING HP4


EXISTING LP4

EXISTING LIGHT FIXTURE

**NOTES:**

1. INTERCEPT EXISTING UNDERGROUND CONDUITS AND STUB UP INTO NEW MANHOLE. FIELD VERIFY EXACT LOCATION AND QUANTITY OF CONDUITS AND CONDUCTORS

**ELECTRICAL PARTIAL PLAN DEMOLITION**  
 3/32" = 1'-0"



(SCALE BAR IS 4" AT FULL SCALE) 0 1/2 1 2 3 4

PLOTTED: 8/30/2023 9:33:35 AM  
 FILE: C:\PW\WORKING\B\W\_AMERICAS\_2017487281E-102.DWG  
 PLOT: 000  
 D:\11000

THIS ITEM HAS BEEN DIGITALLY SIGNED AND SEALED BY DAVID V. MARTINS, PE ON THE DATE INDICATED HERE. PRINTED COPIES OF THIS DOCUMENT ARE NOT CONSIDERED SIGNED AND SEALED AND THE SIGNATURE MUST BE VERIFIED ON ANY ELECTRONIC COPIES.

**LEE COUNTY UTILITIES**

THREE OAKS WATER RECLAMATION FACILITY  
 DEEP INJECTION WELL IW-2

**PRELIMINARY - NOT FOR CONSTRUCTION**

REVISIONS AND RECORD OF ISSUE	
DESIGNED:	DV
DETAILED:	DMF
CHECKED:	SJA
APPROVED:	DVM
DATE:	SEPTEMBER 2023
PROJECT NO.:	414567

ELECTRICAL


PARTIAL SITE PLAN

E-103

OF

**5.0 MG GROUND STORAGE TANK 80-T-3**

**5.0 MG GROUND STORAGE TANK 80-T-4**




**GENERAL NOTES**

1. ALL NEW ELECTRICAL CIRCUITS SHOWN ON THIS SHEET SHALL BE 2#12G, 1#12G., UNLESS NOTES OTHERWISE

**NOTES:**

- SEE DRAWING E-001 AND E-002 FOR ELECTRICAL LEGEND & ABBREVIATIONS AND GENERAL REQUIREMENTS.
- REFER TO THE LIGHTING FIXTURE SCHEDULE ON SHEET E-601. LIGHT POLES SHALL BE PROVIDED BY THE SAME LIGHTING FIXTURE MANUFACTURER AND SHALL HAVE A HANDHOLE FOR A RECEPTACLE MOUNTED AT 18" AFF. PROVIDE AND INSTALL DEDICATED WIRES FROM LP4 TO THIS LIGHT FIXTURE. NO SPLICES ARE ALLOWED IN ANY HAND HOLE OR JUNCTION BOX.
- GFCI RECEPTACLE TO BE INSTALLED ON LIGHTING POLE. REFER TO NOTE #2 ABOVE. PROVIDE AND INSTALL DEDICATED WIRES FROM LP4 TO THIS RECEPTACLE. NO SPLICES ARE ALLOWED IN ANY HAND HOLE OR JUNCTION BOX.
- INTERCEPT EXISTING UNDERGROUND CONDUITS AND STUB UP INTO NEW HANDHOLE. FIELD VERIFY EXACT LOCATION AND QUANTITY OF CONDUITS AND CONDUCTORS. SPLICE AND PROVIDE NEW CONDUITS AND CONDUCTORS BETWEEN HANDHOLES AS REQUIRED TO MATCH EXISTING CONDITIONS. IN ACCORDANCE WITH THE EXISTING RECORD DRAWINGS POWER FOR GST #4 LEVEL TRANSMITTER IS FROM CIRCUIT #10 ON PANEL LP4 AND POWER FOR GST #4 EFFLUENT MOV IS FROM PANEL HP4 CIRCUIT 14,16,18. SEE HANDHOLE DETAIL ON SHEET E-601.
- PROVIDE HANDHOLE PER TYPICAL ELECTRICAL HANDHOLE DETAIL ON SHEET E-601.
- PROVIDE AND INSTALL (2) 2" CONDUITS TO PLC-2 AT THE EXISTING ELECTRICAL BUILDING.
- EXISTING PANELS HP4 AND LP4 ARE SQUARE D.
- 80-FCV-07 IS AN EXISTING 30" BUTTERFLY VALVE TO BE MOTORIZED.

**ELECTRICAL PARTIAL PLAN**  
 3/32" = 1'-0"



(SCALE BAR IS 4" AT FULL SCALE) 0 1/2 1 2 3 4

THIS ITEM HAS BEEN DIGITALLY SIGNED AND SEALED BY DAVID V. MARTINS. PE ON THE DATE INDICATED HERE. PRINTED COPIES OF THIS DOCUMENT ARE NOT CONSIDERED SIGNED AND SEALED AND THE SIGNATURE MUST BE VERIFIED ON ANY ELECTRONIC COPIES.

**LEE COUNTY UTILITIES**

**THREE OAKS WATER RECLAMATION FACILITY DEEP INJECTION WELL IW-2**

**PRELIMINARY - NOT FOR CONSTRUCTION**

REVISIONS AND RECORD OF ISSUE	
DESIGNED:	DM
DETAILED:	DMF
CHECKED:	SJA
APPROVED:	DVM
DATE:	SEPTEMBER 2023
PROJECT NO.:	414567

**ELECTRICAL**

**EXISTING SINGLE LINE DIAGRAM, DETAILS AND PANEL SCHEDULE**

EXISTING PANELBOARD: LP4				BUS: COPPER				MAINS: 3P-100A MAIN BREAKER				PHASE			
SERVICE: 120/208V, 3PH, 4W, S/N				RATING: 100A				LOCATION: INJECTION WELL / EFFLUENT PUMP STATION							
PHASE	"A"	"B"	"C"	LOAD	P	BKR	CKT #	BKR	P	LOAD	P	"A"	"B"	"C"	
V.A.	V.A.	V.A.	V.A.									V.A.	V.A.	V.A.	
				(E) MONITORING WELL LEVEL	1	20	1	2	20	1	(E) DEEP INJECTION WELL				
				(E) INJUMONT POLE RECEIPT	1	20	3	4	20	1	(N) INJECTION WELL N POLE LTG		237		
				(E) SPARE	1	20	5	6	20	1	(N) INJECTION WELL N POLE RCPT			540	
				(E) INJECTION WELL AIR COMPRESSOR	1	20	7	8	20	1	(N) MOV 80-FCV-11		372		
				(E) GST #3 LEVEL TRANSMITTER	1	20	9	10	20	1	(N) MOV 80-FCV-12		372		
				(E) REUSE DISTRIBUTION FIT	1	20	11	12	20	1	(E) GST #4 LEVEL TRANSMITTER				
				(E) INJECTION WELL N POLE RECEIPT	1	20	13	14	20	1	(E) INJECTION WELL S POLE RCPT				
				(E) SPARE	1	20	15	16	20	1	(N) MOV 80-FCV-7		360		
				(E) LIGHTING CONTROL	1	20	17	18	20	1	(N) FIT-80-11			100	
				(E) SPARE	1	20	19	20	20	1	(E) GST #2 LEVEL TRANSMITTER				
				(E) SPARE	1	20	21	22	20	1	(E) SPARE				
				(E) SPARE	1	20	23	24	20	1	(E) SPARE				
				(E) MAIN BREAKER	3	100	25	26	20	1	(E) SPACE				
					-	-	27	28	20	1	(E) SPACE				
					-	-	29	30	20	1	(E) SPACE				
0				TOTAL "A"							TOTAL "A"	372			
0				TOTAL "B"							TOTAL "B"	969			
0				TOTAL "C"							TOTAL "C"	640			
				TOTAL (NOTE 1) =				1981							





**NOTES:**  
 1. TOTAL LOAD IS THE NEW LOAD ADDED TO THIS EXISTING PANEL WITHIN THIS PROJECT SCOPE. EXISTING CONNECTED LOADS ARE NOT KNOWN. PROVIDE A 30-DAY LOAD STUDY PER NEC 220.87 TO ENSURE THE PANEL HAS THE CAPACITY FOR NEWLY ADDED LOADS.

**EXISTING LP4 PANEL SCHEDULE**



EXISTING PANELBOARD: HP4				BUS: COPPER				MAINS: MLO				PHASE			
SERVICE: 480V, 3PH, 3W, S/N				RATING: 100A				LOCATION: INJECTION WELL / EFFLUENT PUMP STATION							
PHASE	"A"	"B"	"C"	LOAD	P	BKR	CKT #	BKR	P	LOAD	P	"A"	"B"	"C"	
V.A.	V.A.	V.A.	V.A.									V.A.	V.A.	V.A.	
				MOV 80-V-4F TANK 4 DISCHARGE	3	20	1	2	20	1	MOV 80-2E TANK 2 INLET				
				MOV 80-V-2F TANK 2 DISCHARGE	3	20	3	4	20	1	MOV 80-V-3F TANK 3 DISCHARGE				
				SPARE	3	20	5	6	20	1	SPARE				
				UPPER ZONE PUMP CP	3	20	7	8	20	1	SPARE				
				LOWER ZONE PUMP CP	3	20	9	10	20	1	SPACE				
							11	12	20	1	SPACE				
							13	14	20	1	SPACE				
							15	16	20	1	SPACE				
							17	18	20	1	SPACE				
							19	20	20	1	SPACE				
							21	22	20	1	SPACE				
							23	24	20	1	SPACE				
							25	26	20	1	SPACE				
							27	28	20	1	SPACE				
							29	30	20	1	SPACE				
0				TOTAL "A"							TOTAL "A"	0			
0				TOTAL "B"							TOTAL "B"	0			
0				TOTAL "C"							TOTAL "C"	0			
				TOTAL =								0			

**EXISTING HP4 PANEL SCHEDULE**

LIGHTING FIXTURE SCHEDULE					
FIXTURE	LAMP	MTG HGT	DESCRIPTION	MANUFACTURER	
1	LED 79W 3,666 LUMENS	10'-0"	DSX0 LED SERIES, FORWARD OPTICS, LIMITED WAVELENGTH AMBER TYPE III MEDIUM, 120V-277V, SQUARE POLE MOUNTING, HIGH/LOW MOTION/AMBIENT SENSOR ENABLED AT 2FC, NATURAL ALUMINUM, PHOTOCELL-SSL TWIST-LOCK (120-277V)	(FIXTURE) LITHONIA DSX0 LED P2 AMBLW AMCRI T3M MVOLT SPA PIR DNAXD DLL127F 1.5 JU (LIGHT POLE LITHONIA SSA 10-0 4C)	



A	B	C	POLE LENGTH
1'-0"	2"	3'-0"	10' TO 12'
1'-6"	2"	4'-0"	12' TO 20'
2'-0"	2"	5'-0"	20' TO 40'



**NOTES:**  
 1. SEE DRAWING E-001 AND E-002 FOR ELECTRICAL LEGEND & ABBREVIATIONS AND GENERAL REQUIREMENTS.  
 2. FUSE SIZE FOR MOTOR ACTUATORS SHALL BE AS RECOMMENDED BY ACTUATOR MANUFACTURER.

PLOTTED: 9/11/2023 7:21:12 AM  
 FILE: C:\PW\WORKING\BWW\_AMERICAS\_2017497281E-601.DWG  
 FD1000  
 D11000

THIS ITEM HAS BEEN DIGITALLY SIGNED AND SEALED BY KYLE A. PHIPPS, PE ON THE DATE INDICATED HERE. PRINTED COPIES OF THIS DOCUMENT ARE NOT CONSIDERED SIGNED AND SEALED AND THE SIGNATURE MUST BE VERIFIED ON ANY ELECTRONIC COPIES.

**LEE COUNTY UTILITIES**



**THREE OAKS WATER RECLAMATION FACILITY DEEP INJECTION WELL IW-2**

**PRELIMINARY - NOT FOR CONSTRUCTION**


REVISIONS AND RECORD OF ISSUE	
DESIGNED:	LJB
DETAILED:	DRS
CHECKED:	MJC
APPROVED:	KAP
DATE:	SEPTEMBER 2023
PROJECT NO.:	414567

**INSTRUMENTATION & CONTROL**


**P&ID - LEGEND AND ABBREVIATIONS**



**GENERAL INSTRUMENT SYMBOLS**



**DIGITAL SYSTEMS INTERFACE SYMBOLS**





- △ DISCRETE INPUT
- ▽ DISCRETE OUTPUT
- ▲ ANALOG INPUT

**INSTRUMENT AND I/O ABBREVIATION DEFINITIONS**

AAH ANALYZER ALARM HIGH	PDAH DIFFERENTIAL PRESSURE ALARM HIGH
AAHH ANALYZER ALARM HIGH-HIGH	PDAHh DIFFERENTIAL PRESSURE ALARM HIGH-HIGH
AAL ANALYZER ALARM LOW OR STROBE ALARM LIGHT	PDG DIFFERENTIAL PRESSURE GAUGE
AALL ANALYZER ALARM LOW-LOW	PDI DIFFERENTIAL PRESSURE INDICATOR (LED OR SCREEN)
AAX ALARM HORN	PDIT DIFFERENTIAL PRESSURE INDICATING TRANSMITTER
AE ANALYZER SENSOR	PDSH DIFFERENTIAL PRESSURE SWITCH HIGH
AI ANALYZER INDICATION	PDSHh DIFFERENTIAL PRESSURE SWITCH HIGH-HIGH
AIT ANALYZER INDICATING TRANSMITTER	PDSL DIFFERENTIAL PRESSURE SWITCH LOW
ASH ANALYZER SWITCH HIGH	PDSLl DIFFERENTIAL PRESSURE SWITCH LOW-LOW
ASHH ANALYZER SWITCH HIGH-HIGH	PE PRESSURE SENSOR
CB CONTROL BLOCK REFERENCE (SCADA LEVEL)	PG PRESSURE GAUGE
FAH FLOW ALARM HIGH	PI PRESSURE INDICATOR (LED OR SCREEN)
FAL FLOW ALARM LOW	PIT PRESSURE INDICATING TRANSMITTER
FC FLOW CONTROLLER	PSH PRESSURE SWITCH HIGH
FE PRIMARY FLOW ELEMENT/SENSOR	PSL PRESSURE SWITCH LOW
FG FLOW SIGHT GAUGE	SC SPEED CONTROL
FI FLOW DIGITAL INDICATOR (LED OR SCREEN)	SI SPEED INDICATION (LED OR SCREEN)
FIC FLOW INDICATING CONTROLLER	SIT SPEED INDICATING TRANSMITTER
FIT FLOW INDICATING TRANSMITTER	SSL SPEED SWITCH LOW
FOG FLOW TOTALIZING GAUGE	TAH TEMPERATURE ALARM HIGH
FOIT FLOW TOTALIZING INDICATING TRANSMITTER	TAHH TEMPERATURE ALARM HIGH-HIGH
FSH FLOW SWITCH HIGH	TAL TEMPERATURE ALARM LOW
FSL FLOW SWITCH LOW	TALh DIFFERENTIAL TEMPERATURE INDICATOR (LED OR SCREEN)
FY FLOW SIGNAL CONVERTER, REPEATER, OR ISOLATOR	TDIT DIFFERENTIAL TEMPERATURE TRANSMITTER
HIC HAND INDICATING CONTROLLER	TE TEMPERATURE SENSOR/RESISTANCE
HMS MOMENTARY PUSHBUTTON OR SELECTOR SWITCH	TG TEMPERATURE GAUGE
HS HAND SWITCH	TI TEMPERATURE INDICATOR (LED OR SCREEN)
IAH CURRENT ALARM HIGH (MOTOR OVERLOAD)	TIT TEMPERATURE INDICATING TRANSMITTER
IE CURRENT ELEMENT/SENSOR	TSH TEMPERATURE SWITCH HIGH
ISH CURRENT SWITCH HIGH USED TO DETECT HIGH TORQUE	TSHH TEMPERATURE SWITCH HIGH HIGH
JA POWER FAILURE ALARM	TSL TEMPERATURE SWITCH LOW
JI POWER INDICATOR	UA MULTIVARIABLE/Common Alarm/Common Fault
JIT POWER INDICATING TRANSMITTER	UCR RUN COMMAND
JL POWER INDICATING LIGHT	UCS STOP COMMAND
KQI TIME TOTALIZING INDICATOR	VAH VIBRATION ALARM HIGH
LAH LEVEL ALARM HIGH	WE PRIMARY WEIGHT SENSOR/LOAD CELL
LAHH LEVEL ALARM HIGH-HIGH	WG WEIGHT GAUGE
LAL LEVEL ALARM LOW	WIT WEIGHT INDICATING TRANSMITTER
LALL LEVEL ALARM LOW-LOW	YA GENERAL ALARM EVENT
LE PRIMARY LEVEL ELEMENT/SENSOR	YI EVENT INDICATION (LED OR SCREEN)
LG LEVEL SIGHT GAUGE	YIR RUNNING INDICATION
LI LEVEL INDICATOR (LED OR SCREEN)	YIS STOPPED INDICATION
LIT LEVEL INDICATING TRANSMITTER	YL EVENT INDICATING LIGHT
LSH LEVEL SWITCH HIGH	YLR RUNNING INDICATING LIGHT
LSHH LEVEL SWITCH HIGH-HIGH	YLS STOPPED INDICATING LIGHT
LSL LEVEL SWITCH LOW	ZI POSITION INDICATOR
LSLL LEVEL SWITCH LOW LOW	ZIC CLOSED INDICATION
LY LEVEL SIGNAL CONVERTER, ISOLATOR, OR REPEATER	ZIO OPEN INDICATION
QAH TORQUE ALARM HIGH	ZIT POSITION INDICATING TRANSMITTER
QAHH TORQUE ALARM HIGH HIGH	ZLC CLOSED INDICATING LIGHT
QSH TORQUE SWITCH HIGH	ZLO OPEN INDICATING LIGHT
QSHH TORQUE SWITCH HIGH-HIGH	ZSC CLOSED POSITION SWITCH
PAH PRESSURE ALARM HIGH	ZSO OPEN POSITION SWITCH
PAHH PRESSURE ALARM HIGH-HIGH	ZT POSITION TRANSMITTER
PAL PRESSURE ALARM LOW	ZC POSITION COMMAND
PALL PRESSURE ALARM LOW-LOW	

**INSTRUMENT AND I/O ABBREVIATIONS MEANINGS OF IDENTIFICATION LETTERS**

LETTER	FIRST LETTER		SUCCEEDING LETTERS		
	MEASURED OR INITIATING VARIABLE	VARIABLE MODIFIER	READOUT OR PASSIVE FUNCTION	OUTPUT OR ACTIVE FUNCTION	FUNCTION MODIFIER
A	ANALYSIS		ALARM		
B	BURNER, COMBUSTION		USER'S CHOICE	USER'S CHOICE	USER'S CHOICE
C	USER'S CHOICE			CONTROL	CLOSE
D	USER'S CHOICE	DIFFERENTIAL			DEVIATION
E	VOLTAGE (EMF)		SENSOR, PRIMARY ELEMENT		
F	FLOW, FLOW RATE	RATIO (FRACTION)			
G	USER'S CHOICE		GLASS, GAUGE, VIEWING DEVICE		
H	HAND (MANUALLY INITIATED)				HIGH
I	CURRENT (ELECTRICAL)		INDICATE		
J	POWER		SCAN		
K	TIME OR TIME-SCHEDULE	TIME RATE OF CHANGE		CONTROL STATION	
L	LEVEL		LIGHT		LOW
M	USER'S CHOICE	MOMENTARY			MIDDLE OR INTERMEDIATE
N	USER'S CHOICE		USER'S CHOICE	USER'S CHOICE	USER'S CHOICE
O	USER'S CHOICE		ORIFICE (RESTRICTION)		OPEN
P	PRESSURE OR VACUUM		POINT (TEST CONNECTION)		
Q	QUANTITY	INTEGRATE OR TOTALIZE	INTEGRATE OR TOTALIZE		
R	RADIATION		RECORD		RUN
S	SPEED OR FREQUENCY	SAFETY		SWITCH	STOP
T	TEMPERATURE			TRANSMIT	
U	MULTIVARIABLE		MULTIFUNCTION	MULTIFUNCTION	
V	VIBRATION OR MECHANICAL ANALYSIS			VALVE, DAMPER OR LOUVER	
W	WEIGHT OR FORCE		WELL, PROBE		
X	UNCLASSIFIED	X-AXIS	ACCESSORY DEVICES OR UNCLASSIFIED	UNCLASSIFIED	UNCLASSIFIED
Y	EVENT, STATE, OR PRESENCE	Y-AXIS		AUXILIARY DEVICES	
Z	POSITION, DIMENSION	Z-AXIS		DRIVE, ACTUATOR OR FINAL CTRL ELEMENT	



**HAND SWITCH DESIGNATIONS**

LOR	LOCAL-OFF-REMOTE
OSC	OPEN-STOP-CLOSE

**FUNCTION CODE DESIGNATIONS**

FCV	VALVE, FLOW CONTROL
V	VALVE, GENERAL OR UNSPECIFIED
P	PUMP, POSITIVE DISPLACEMENT, ROTARY, DRUM OR BELL MOUNTED

**POWER SUPPLY ABBREVIATIONS**

480V	480 VAC
120V	120 VAC
POWER SUPPLY SOURCE LABEL, USED ONLY WHERE NECESSARY TO HELP CLARIFY AN INSTRUMENT OR SYSTEM FUNCTION.	

**GENERAL NOTES**

- IN GENERAL, THE P&ID SYMBOLS AND DEVICE IDENTIFICATIONS ARE BASED ON INTERNATIONAL SOCIETY OF AUTOMATION, STANDARD PRACTICE ANSI/ISA-5.1 (2009). SOME MODIFICATIONS, ADDITIONS, AND ALTERATIONS HAVE BEEN MADE AS NEEDED TO ACCOMMODATE THE PROJECT REQUIREMENTS.
- SOME CONTROL AND INTERLOCK REQUIREMENTS WHICH CAN BE MORE CLEARLY ILLUSTRATED ON SCHEMATIC DRAWINGS HAVE BEEN OMITTED FROM THE P&ID DRAWINGS.
- THIS IS A GENERAL LEGEND SHEET. SOME SYMBOLS AND ABBREVIATIONS MAY NOT BE UTILIZED ON THIS SPECIFIC PROJECT.

PLOTTED: 8/31/2023 11:16:09 AM  
 FILE: C:\USERS\BJD\2262\APPDATA\LOCAL\AUTODESK\AUTOCAD PLANT 3D\COLORATION\CACHE\414567\PID.DWG\I-001.DWG  
 FD11000  
 D11000

THIS ITEM HAS BEEN DIGITALLY SIGNED AND SEALED BY KYLE A. PHIPPS, PE ON THE DATE INDICATED HERE. PRINTED COPIES OF THIS DOCUMENT ARE NOT CONSIDERED SIGNED AND SEALED AND THE SIGNATURE MUST BE VERIFIED ON ANY ELECTRONIC COPIES.

**LEE COUNTY UTILITIES**

THREE OAKS WATER RECLAMATION FACILITY  
DEEP INJECTION WELL IW-2


**PRELIMINARY - NOT FOR CONSTRUCTION**

REVISIONS AND RECORD OF ISSUE

DESIGNED:	LJB
DETAILED:	AWR
CHECKED:	MJC
APPROVED:	KAP
DATE:	SEPTEMBER 2023
PROJECT NO.:	414567


INSTRUMENTATION & CONTROL

INSTRUMENTATION INSTALLATION DETAILS





**A FLOW METER-MAGNETIC  
INSTALLATION DETAIL**  
NO SCALE

NOTE:  
1. PIPE TO BE SUPPORTED ON BOTH SIDES OF METER




**B PRESSURE GAUGE & TRANSMITTER  
INSTALLATION DETAIL**  
NO SCALE

- NOTES:
1. PRESSURE GAUGES AND PRESSURE SWITCH FOR CHEMICAL SERVICE SHALL BE AS SPECIFIED IN 46 30 50.
  2. ISOLATION VALVES SHALL BE PER MECHANICAL DRAWINGS.



**SIDE VIEW**



**FRONT VIEW**

**C OUTDOOR INSTRUMENT  
MOUNTING DETAIL**  
NO SCALE

THIS ITEM HAS BEEN DIGITALLY SIGNED AND SEALED BY KYLE A. PHIPPS, PE ON THE DATE INDICATED HERE. PRINTED COPIES OF THIS DOCUMENT ARE NOT CONSIDERED SIGNED AND SEALED AND THE SIGNATURE MUST BE VERIFIED ON ANY ELECTRONIC COPIES.

**LEE COUNTY UTILITIES**


**THREE OAKS WATER RECLAMATION FACILITY DEEP INJECTION WELL IW-2**

**PRELIMINARY - NOT FOR CONSTRUCTION**

REVISIONS AND RECORD OF ISSUE	
DESIGNED:	LJB
DETAILED:	DRS
CHECKED:	MJC
APPROVED:	KAP
DATE:	SEPTEMBER 2023
PROJECT NO.:	414567

**INSTRUMENTATION & CONTROL**

**P&ID - EFFLUENT PUMPS**



SCADA HMI

PLC-2

SCADA HMI

PLC-2

**NOTES:**  
1. EXISTING VALVE. REFER TO SPECIFICATION SECTION 40.05.57. CONTRACTOR TO COORDINATE WITH OWNER TO CONFIRM DETAILS ON VALVE LOCATION, TYPE, INSTALLATION, ETC.

PLOTTED: 8/31/2023 11:15:43 AM  
 FILE: C:\USERS\BJD7262\APPDATA\LOCAL\AUTODESK\AUTOCAD PLANT 3D\COLORATION\CACHE\414567\PID DWG\I-601.DWG