

Lee County Board Of County Commissioners

Blue Sheet No. 20060027

Agenda Item Summary

1. ACTION REQUESTED/PURPOSE: Approve Change Order No. 1 under RFQ-02-04 Justice Center Expansion Phase VI (Foundation & Utility Package 1), with Centex Construction (Contract #3083) to include the Guaranteed Maximum Price (GMP) for Phase VI (Tower Package 2) in the amount of \$44,904,292.00 (which includes the CM Fee of 4% or \$1,688,108.00 and additional preconstruction amount of \$152,207.00). Also request Board approve waiving of any formal process (if needed) and authorize the use of the Direct Material Purchase Orders as provided for in the CM Agreement with Lee County, which allows the County to purchase directly from suppliers of equipment and/or materials as a cost/time saving measure. Further Authorize Chairwoman execute Change Order No. 1. Also approve Budget Transfer in the amount of \$ 30 million from General Fund Reserves and Budget Resolution in Capital Improvement Fund and increase the Justice Center Expansion Project and amend FY 05/06 – 09/10 CIP accordingly.

2. WHAT ACTION ACCOMPLISHES: For work to be performed for Pod E Courts Addition Tower & Judges Parking Garage. Includes a ten-story addition of approximately 16,000 square feet per floor. The new addition will house new courtrooms on floors 1 through 8 and judges levels on floors 9 and 10. Floors 1, 2 3, 5, 6 and 10 will be finished out in the initial construction. Floors 4, 7, 8 and 9 will be shelled for finish at a future date. To the north of the courtroom tower will be a new three-story judges parking structure.

3. MANAGEMENT RECOMMENDATION: Staff recommends approval

4. Departmental Category: 2.		CZE	5. Meeting Date: 01-24-2006
6. Agenda: <input checked="" type="checkbox"/> Consent <input type="checkbox"/> Administrative <input type="checkbox"/> Appeals <input type="checkbox"/> Public <input type="checkbox"/> Walk-On	7. Requirement/Purpose: (specify)		8. Request Initiated:
	<input type="checkbox"/> Statute		Commissioner
	<input type="checkbox"/> Ordinance		Department Construction & Design
	<input checked="" type="checkbox"/> Admin. Code	AC-4-4	Division
	<input type="checkbox"/> Other		By: Jim Lavender, Director

9. Background:
 On July 9, 2002, the Board approved award to Centex Rooney Construction Company for RFQ-02-04, Construction Management for Justice Center Expansion in the amount of five percent (5%) of the total construction project and also authorized staff to enter into a Construction Manager Agreement.

At this time the Department of Construction & Design is requesting Board approve Change Order No. 1 to Phase VI (Tower & Parking Garage), with Centex Construction (Contract #3083) to include the Guaranteed Maximum Price (GMP) for Phase VI in the amount of \$44,904,292.00 (which includes the CM Fee of 4% or \$1,688,108.00 and additional preconstruction amount of \$152,207.00). Also request Board approve waiving of any formal process (if needed) and authorize the use of the Direct Material Purchase Orders as provided for in the CM Agreement with Lee County, which allows the County to purchase directly from suppliers of equipment and/or materials as a cost/time saving measure.

On September 22, 2005, the Board approved the use of \$30 million from General Fund Reserves to fund additional costs associated with the expansion of the Justice Center
 Funds will be available in accounts: 20864631407.506540.817 and 20864630100.506540.817

Attachments: (1) Proposal from Centex Rooney dated November 18, 2005
 (2) Transfer of Funds

10. Review for Scheduling:

Department Director	Purchasing or Contracts	Human Resources	Other	County Attorney	Budget Services			County Manager/P.W. Director
<i>[Signature]</i>	<i>[Signature]</i>	N/A	<i>[Signature]</i>	<i>[Signature]</i>	Analyst	Risk	Grants	<i>[Signature]</i>
					<i>[Signature]</i>	<i>[Signature]</i>	<i>[Signature]</i>	<i>[Signature]</i>

11. Commission Action:

- Approved
- Deferred
- Denied
- Other

RECEIVED BY COUNTY ADMIN:

1-11-06

1:45

COUNTY ADMIN FORWARDED TO:

1-11-06

300

Ret. by CoAtty

Date: 1/11/06

Time: 1:45 PM

Forwarded To:

REQUEST FOR TRANSFER OF FUNDS

FUND NAME: General Fund DATE: 1-11-06 BATCH NO.:

FISCAL YEAR: 05-06 FUND NO.: 00100 DOC. TYPE: YB LEDGER TYPE: BA

TO: Non-Departmental Reserves
 (Division Name) (Program Name)

NOTE: Please list the account number below in the following order:
 Business Unit (dept/div, program, fund, subfund); Object Account; Subsidiary; Subledger
 (Example: BB 5120100100.503450)

<u>Account Number</u>	<u>Object Name</u>	<u>DEBIT</u>
GC5890100100.509930	Reserves for Fund Balance	\$ 30,000,000

TOTAL TO: \$ 30,000,000

FROM: Non-Departmental Interfund Transfers
 (Division Name) (Program Name)

<u>Account Number</u>	<u>Object Name</u>	<u>CREDIT</u>
GC5810100100.509110.T30100	Interfund Transfer to 30100	\$ 30,000,000

TOTAL FROM: \$ 30,000,000

EXPLANATION: To transfer funds to Reserves for the Loan for the Justice Center Expansion.

DIVISION DIRECTOR SIGNATURE/DATE

DEPARTMENT HEAD SIGNATURE/DATE

DBO: APPROVAL DENIAL

Emma K. Wall 1-11-06
 OPS. ANALYST SIGNATURE DATE

OPS. MGR.: APPROVAL DENIAL

She Lang 1/11/06
 OPS. MGR. SIGNATURE DATE

CO. MGR.: APPROVAL DENIAL

CO. MANAGER SIGNATURE DATE

BCC APPROVAL DATE: _____

BCC CHAIRMAN SIGNATURE

BA. NO. _____

AUTH CODE _____

TRANS DATE _____

RESOLUTION

Amending the Budget of Capital Improvements-Fund 30100 to incorporate the unanticipated receipts into Estimated Revenues and Appropriations for the fiscal year 2005-2006.

WHEREAS, in compliance with the Florida Statutes 129.06(2), it is the desire of the Board of County Commissioners of Lee County, Florida, to amend the Capital Improvements-Fund 30100 budget for \$30,000,000 of the unanticipated revenue from the General Fund Reserves and an appropriation of a like amount for construction costs and;

WHEREAS, the Capital Improvements-Fund 30100 budget shall be amended to include the following amounts which were previously not included.

ESTIMATED REVENUES		
Prior Total:		\$98,608,336
Additions		
GC5810130100.381000.900100	Transfer from General Fund	30,000,000
Amended Total Estimated Revenues		\$128,608,336

APPROPRIATIONS		
Prior Total:		98,608,336
20864630100.506540	Construction Improvements	30,000,000
Amended Total Appropriations		\$128,608,336

NOW, THEREFORE, BE IT RESOLVED by the Board of County Commissioners of Lee County, Florida, that the Capital Improvements-Fund 30100 budget is hereby amended to show the above additions to its Estimated Revenue and Appropriation accounts.

Duly voted upon and adopted in Chambers at a regular Public Hearing by the Board of County Commissioners on this ____ day of _____, 2006.

ATTEST:
CHARLIE GREEN, EX-OFFICIO CLERK

BOARD OF COUNTY COMMISSIONERS
LEE COUNTY, FLORIDA

BY: _____
DEPUTY CLERK

CHAIRWOMAN

APPROVED AS TO FORM

DOC TYPE YA
LEDGER TYPE BA

OFFICE OF COUNTY ATTORNEY

Lee County Justice Center – Courts Addition Tower & Judges Parking Garage

Fort Myers, Florida

**Guaranteed Maximum Price
100% Construction Documents
November 18, 2005**

*Executed Change
Order No. 1 to
follow —*



CENTEX
CONSTRUCTION



**LEE COUNTY JUSTICE CENTER
EXPANSION PROJECT
FORT MYERS, FLORIDA**

**Guaranteed Maximum Price
Courts Addition Tower & Judges Parking Garage
Phase VI**

November 18, 2005

TABLE OF CONTENTS

SECTION 1	PROJECT DESCRIPTION Executive Summary
SECTION 2	CLARIFICATIONS A. Qualifications / Assumptions B. Exclusions C. Allowances
SECTION 3	COST SUMMARY A. Bid Day B. Bid Alternates C. Potential Value Engineering
SECTION 4	SCHEDULE Schedule Narrative
SECTION 5	LIST OF DOCUMENTS Document List

SECTION 1

Executive Summary

The Lee County Justice Center Expansion is designed to be a multiphase project to increase Lee County's capacity to provide constitutional services.

Phase VI (Courts Addition Tower) includes a ten-story addition of approximately 16,000 square feet per floor. The new addition will house new courtrooms on floors 1 through 8 and judges levels on floors 9 and 10. Floors 1, 2, 3, 5, 6 and 10 will be finished out in the initial construction. Floors 4, 7, 8, & 9 will be shelled for finish at a future date.

The building design allows for courtrooms to be vertically stacked, providing separated and secured vertical circulation for the public, judges, and prisoners. To the north of the courtroom tower will be a new three-story judges parking structure which will extend to the north property line at Main Street. The ground level of the judges parking structure will include a vehicle sally-port for prisoner delivery and pick-up, the FP & L main power vault and entrance and exit points for the secured judges parking on the ground level and two levels above.

Between the Courtroom Addition and the Justice Center Annex will be a public plaza which extends from Dr. Martin Luther King Jr. Blvd. to Main Street. In the middle of this plaza is a 2 story Entry Pavilion which will serve as the new principal entry or "Front Door" for the Justice Center Complex. A public entry will remain off Monroe Street and will primarily serve the public functions of the Clerk of the Court. The tower addition will have internal connections at five levels of the existing Justice Center as well as a ground level covered walkway connection between the new addition and the Justice Center Annex.

The parking garage required to serve the Justice Center Courts Addition Tower is not included in this GMP.

SECTION 2

SECTION 2A



Lee County Justice Center
100% CD GMP Estimate
11/18/05

Qualifications & Assumptions

DIVISION 1 – GENERAL REQUIREMENTS

General

1. This GMP includes costs for a Builder's Risk Policy for the cost of the construction contract. The premiums for Builder's Risk coverage contained in this GMP represent an indication from our underwriters. The actual cost of the program will be determined by our underwriter at the time coverage is bound.
2. The cost for a Performance and Payment Bond for Centex Construction is included.
3. The GMP includes items designated as allowances. See the Allowance Sheet for a list of items designated as allowances. It is agreed and understood that the final costs for these line items of work may be higher or lower than the allowances included. All direct cost savings on allowance items will be returned to the Owner upon project completion.
4. This Guaranteed Maximum Price guarantees the total cost of the scope of the work. Costs of individual line items are not guaranteed.
5. The Construction Contingencies as identified in the GMP are established for the use by the Construction Manager to cover costs incurred as a result of the further refinement and development of the plans and specifications and any other unforeseen conditions that are properly reimbursable as a cost of the work but not basis for a change order.
6. Alternates number 1 and 2 are additive alternates and are not included in this GMP proposal. Alternate number 3 is a deductive alternate and is included in this GMP proposal.
7. Costs associated with work arising from plan review revisions required by the City of Ft Myers for issue of the building permit have not been included in this GMP.



Lee County Justice Center
100% CD GMP Estimate
11/18/05

Qualifications & Assumptions

DIVISION 2 – SITEWORK

Demolition

1. We have included saw cutting the existing asphalt street 6” away from the existing street curb for removal.

Fencing

1. The aluminum fence and gates are included with a standard color selection, powder coat finish.

Paving & Pavers

1. We have included 710 SF of ADA Detectable Warning Pavers.
2. We have included a 3” thick concrete subslab under all brick pavers.
3. We have included asphalt paving at the north garage exit and the service yard entrance. Reference AS1.0.3.
4. Pavers will be set on a sand leveling bed over 3” concrete base. Paver joints will be filled with sand to lock pavers in place.

Landscape & Irrigation

1. The tag quantities shown on the drawings supercede quantities shown on plant schedules. The tag quantities have been included in this GMP proposal.



Lee County Justice Center
100% CD GMP Estimate
11/18/05

Qualifications & Assumptions

DIVISION 3 – CONCRETE

Cast in Place Concrete

1. This GMP is based on the columns and shear walls to the underside of the first elevated deck as well as the elevator pit walls and CMU stem walls being purchased via allowances and contingencies in the Tower Foundation Bid Package No. 1.
2. The combination of the items procured in item 1 above and the work included in this GMP proposal will provide a complete concrete structure as required by the contract documents.
2. It is assumed that the concrete strength & location requirements on S100 govern and supercede the requirements of the division 03300 specification.
3. Section 03300-16 3.11.2 a F(f) does not apply to cambered floors and is not included in this GMP proposal as defined in this section.

Architectural Precast Concrete

1. The larger exterior precast panels will need to be re-sized to accommodate the weight limits of the crane as well as that of the structure. These modifications will be addressed in the shop drawings for the A/E approval.
2. An allowance of \$200/cy has been established for face mix concrete designs.

DIVISION 4 – MASONRY

Unit Masonry

1. Prisoner holding masonry cell walls (Type JC) will have their vertical cells grouted at 32" o/c per detail 70/S304. The remaining vertical masonry cells will be filled with sound attenuation materials. See detail 4/A3.1.1. Solid grouting of these masonry walls is not indicated, see S100.

DIVISION 5 – METALS

Lee County Justice Center
100% CD GMP Estimate
11/18/05

Qualifications & Assumptions

Structural Steel

1. We have included one additional steel tube columns 4x6x5/16" (approx. 2 tons) at south side of the public elevator shafts per elevator manufacturer's requirement to support the rail and or counter weights. Columns are added at each floor of the elevator shaft.
2. We have assumed 4x4x1/4" steel tube columns in drywall partitions at Judges corridor wall at details shown on A5.1.1, since no size is shown on plans.

Miscellaneous Metals

1. The glass rail system called for in specification 05721 does not match details shown on plans, we have included Livers Metro glass rail system per details shown on plan A4.2.1. Railing system shall have 2" OD stainless steel tube top rail, extruded aluminum posts with powder coat finish; 1/2" laminated /tempered glass w/ green interlayer, ceramic frit dot pattern, eased corners and polished edges; 1 1/2" OD stainless steel assist rail and stainless steel post brackets with #4 finishes.
2. Steel pan stairs shall be manufactured by our Division 5 subcontractor.
3. Standard shop primer will be used on all interior metal pan stairs.

DIVISION 6 – WOOD & PLASTICS

Architectural Woodwork

1. Millwork on the 4th floor is limited to the lobby / public access spaces only as indicated on the architectural drawings.

DIVISION 7 – THERMAL AND MOISTURE PROTECTION

Lee County Justice Center
100% CD GMP Estimate
11/18/05

Qualifications & Assumptions

Caulking & Waterproofing

1. Waterproofing system is Voltex by CETCO.
2. Waterproofing mastic is Bentomastic by CETCO.
3. Granules are by CETCO.
4. Waterstop is Hydrobar tube by CETCO.

Roofing

1. Our GMP includes the NVS lightweight concrete roof insulation system on both the concrete and metal deck areas. A 2" thickness over the metal deck is included, in lieu of, 1-1/2" shown.
2. Roof hatches will be steel with red oxide paint, in lieu of kynar finish.

DIVISION 8 - DOORS & WINDOWS

Doors/Frames/Hardware

1. The narrow door lite openings, designated as "NL" on the door schedules, are 3" wide x 33" high, in lieu of, 4" wide x 28" high so as to maintain continuity with narrow lites in fire rated openings.
2. Interior hollow metal frames are fabricated from .0478" thick sheet steel. G60 galvanized
3. Interior hollow metal frames over 48" wide are fabricated from .0598" thick sheet steel. G60 galvanized
4. Exterior hollow metal frames are fabricated from .0785" thick sheet steel. G60 galvanized.
5. Interior hollow metal doors are fabricated from .0598" thick sheet steel, A40



Lee County Justice Center
100% CD GMP Estimate
11/18/05

Qualifications & Assumptions

galvaneal with core as specified.

6. Exterior hollow metal doors are fabricated from .0635" thick sheet steel, G60 galvanized with core as specified. Edges are welded seamless with closed flush tops and bottoms.
7. STC 28 is the highest acoustical rating available on a 90 min. fire rated door.
8. 20 min. rated acoustical doors must have STC 28 rating but the glass lite voids the rating.
9. Wood doors to have wood beads at lites in non-rated doors and metal beads at lites in rated doors.
10. STC doors with lites have an STC rating of 39. The lite is restricted to 400sq inches
11. Detention Doors – Habersham's door construction is equal to STC 44 per mass law calculations. These doors have not been tested for acoustical properties.
12. Shelves at attorney / prisoner interview room to be Habersham 12ga. Stainless steel plate style construction.

Glass & Glazing

Lee County Justice Center
100% CD GMP Estimate
11/18/05

Qualifications & Assumptions

1. Glass is based upon the glazing schedule provided on the plan drawings sheets A2.4.1 & A2.4.2, in lieu of the schedule listed in Specification 08800 Section 3.5/A-K.
2. Blue Max or equal temporary window protection is included.
3. Laminated, ceramic frit and reflective glass each have a five (5) year warranty, in lieu of a ten (10) year warranty.
4. All internal guttering of the curtainwall is mill finish, in lieu of anodized. All indicated components are concealed and will not be visible.
5. Large missile impact glazing has been included up to and elevation of 30'-0". Small missile impact glazing has been included above elevation 30'-0".

DIVISION 9 - FINISHES

Drywall/Stucco

1. All painted Gypsum Board will receive a level 4 finish with a skip trowel surface.
2. Scaffolding and swing stag equipment required for installation of stucco is included. Engineer will need to confirm that the mechanical penthouse joist & deck roof will support the required working loads.

Acoustical

1. Pricing for all curved ceiling profile work for Acoustical Ceilings is based on providing field notched & bent main tees and wall mould for the radius installation. The curve will be achieved using a series of straight sections and will not be a true radius. Standard wall mould will be used at the radius ceiling sections because the specified shadow mould will not work.

Carpet & Resilient Flooring

CENTEX CONSTRUCTION

Lee County Justice Center **100% CD GMP Estimate** **11/18/05**

Qualifications & Assumptions

1. We are providing two coats wash and wax for resilient tiles.

DIVISION 10 – SPECIALTIES

Louvers & Vents

1. We have included louvers and vision screens by Construction Specialties and take exception to the louver specification section 10200 as it calls for Aerolite.

Sunshades

1. The finish on the Construction Specialties sun screen devices is not available in an anodized finish, included is a Kynar finish to match the specified anodized finish.

DIVISION 11 – EQUIPMENT

Projection Screens

1. We have included ten 6'-0"x8'-0" projection screens.

Detention Equipment

1. The X-ray screening units and metal detection units are furnished by the Owner, installed by the Contractor.
2. The detention equipment and hardware is included as an allowance as no specification was provided for these detention items. See Allowances.

Residential Equipment

1. We are providing Model# PSC23MG in lieu of PTC22MFM which is discontinued for the full size refrigerator.

DIVISION 12 – FURNISHINGS

Lee County Justice Center
100% CD GMP Estimate
11/18/05

Qualifications & Assumptions

Window Treatment

1. The 5% extra material called for in the specifications has been provided in the form of additional cloth or louvers, not warranted components such as motors, controllers, etc.

Entrance Mats

1. We have included a clear anodized finish for Entrance mat frames.

DIVISION 14 – CONVEYING SYSTEMS

Lifts

1. No manufacturer fabricates incline lifts which will travel upward first then downward as shown on plans. All inclined lifts will travel only in one direction. We have included Two inclined lifts in each courtroom to comply with all the landing requirements. The Florida Building Code may not allow us to install the inclined lifts in the corridors.
2. We will provide manufacturer's standard warranties.

DIVISION 15 – MECHANICAL

Fire Protection

1. We have included a filler tube for filling the fire pump diesel day tank from inside the garage.
2. A total of 75 ft. of underground fire main has been included to bring the fire service line into the new Fire Pump Room and to go back out to an FDC located on a site wall, not yet shown on the plans.
3. The FM-200 systems are included for MDF room 212 and IDF room 114, each contain a floor mounted cylinder containing 36 lbs of FM-200 agent.

Plumbing

Lee County Justice Center
100% CD GMP Estimate
11/18/05

Qualifications & Assumptions

1. We have included connection to the icemaker supplied with the refrigerator located in the Judge's Lounge 10010.
2. (1) Point-Of-Use Instantaneous water heater is included on the first floor. Floors 3, 5 & 6 each have a 40 gallon water heater for the mop sinks. The 10th floor has a hot water recirculation system, supplied by a 120 gallon water heater located in the mechanical penthouse.

DIVISION 16 - ELECTRICAL

Electrical

1. Fire shutters are considered manual type and no electrical circuits are included for them.
2. A standard wiring system is included for any electric work under access flooring; a prefabricated modular wiring system is not included.
3. A new "Master Label" lightning protection system is included for the New Tower and the Judges Parking Garage.
4. We assume that FPL will provide the primary electrical service to the new electrical vault.
5. A Simplex fire alarm system is included.
6. Telecommunications and Security outlets will stub to the ceiling space as per the drawings. Cabling is by Div. 13 subcontractor.
7. Electrical connection is included for the motorized shades, any additional wiring for controls is not shown and is not included.
8. The security consultant will have an opportunity to review the qualifications of the security electronics subcontractor.

SECTION 2B



Lee County Justice Center
100% CD GMP Estimate
11/18/05

Exclusions From G.M.P.

DIVISION 1 – GENERAL REQUIREMENTS

General

1. The GMP does not include costs for hazardous material handling.
2. Finishes for 7th, 8th and 9th floor are excluded. The core/lobby space only on the 4th floor is finished.
3. Costs for all permits and fees, Florida Water Management Department (FWMD), National Pollutant Discharge Elimination System (NPDES), Environmental Protection Agency (EPA), Florida Department of Environmental Protection (FDEP) and Storm Water Pollution Protection Program (SWPPP) permits costs.
4. Inspection costs for NPDES Permit.
5. Testing and inspections.
6. Owner's Protective Liability Insurance.
7. Monroe Street site improvements.

DIVISION 2 – SITEWORK

Site Furnishings

1. All artwork monuments, granite walls, monument signs and monument structures on site.



Lee County Justice Center
100% CD GMP Estimate
11/18/05

Exclusions From G.M.P.

DIVISION 3 – CONCRETE

Cast-in-Place Concrete

1. Any under-slab drainage stone.
2. Curing of underside of concrete slabs, beams etc. is excluded.

DIVISION 4 – MASONRY

Unit Masonry

1. Solid grouting of the vertical masonry cells for the prisoner holding cells.

DIVISION 5 – METALS

Miscellaneous Metals

1. Steel framing and supports for counter tops, shelf angles and misc. steel trim including steel angle corner guards, per Para 1.2.A, since none are shown on the plans.
2. Railing gates at the level of exit discharge per Para 1.2.A.5 of the spec. section 05500, since none shown on plans.
3. Zinc rich primer is excluded at interior metal pan stairs.

Ornamental Railings

1. Mock up for glass rail system, since none called in specification 05721.

Lee County Justice Center
100% CD GMP Estimate
11/18/05

Exclusions From G.M.P.

DIVISION 6 – WOOD & PLASTICS

Architectural Woodwork

1. All jury seating are assumed be movable chairs furnished as part of FF&E.
2. Finish carpentry on floors 7, 8 & 9 is excluded. Millwork on the 4th floor is limited to the lobby & core spaces.
3. The fire treated wood is excluded as specified in section 06402 2.3 B because it is not applicable to architectural woodwork.

DIVISION 8 - DOORS & WINDOWS

Doors/Frames/Hardware

1. Door louvers, as none are shown on the drawings.

Overhead Doors

1. Specification Section 08334 – Overhead Coiling Grilles, as none are shown on the plans.

DIVISION 9 - FINISHES

Drywall/Stucco

1. Level 5 finish.

Acoustical

1. No manufactured pre-curved grid or acoustical ceiling panels are included in this GMP.

Carpet & Resilient Flooring

1. Carpet material and installation is excluded.

Lee County Justice Center
100% CD GMP Estimate
11/18/05

Exclusions From G.M.P.

DIVISION 10 – SPECIALTIES

Visual Display Boards

1. Visual display conference units per Para 3.4B of the specification, since none are shown on the drawings.

Corner Guards

1. Specification Section 10265 – Impact Resistant Wall Protection, as none are shown on the drawings.

Identifying Devices

1. Interior, exterior and site signage, as this work is by the Owner.
2. All directories and plaques.

Lockers & Benches

1. We assumed that the extra material of lockers are not required as specified in section 10505 1.10.
2. Locker benches and pedestals are excluded as specified in section 10505 2.4 because they are not shown on plans.

DIVISION 11 – EQUIPMENT

Audio/Visual Equipment

1. Court Smart system.
2. Audio / Visual equipment not shown or indicated on the documents.

Window Washing Equipment

1. No window washing equipment, davits or tie-backs are included.



Lee County Justice Center
100% CD GMP Estimate
11/18/05

Exclusions From G.M.P.

DIVISION 12 – FURNISHINGS

Entrance Mats

1. Protective coating is not included, because it is not available.

DIVISION 13 – SPECIAL CONSTRUCTION

Security Electronics

1. Hydraulic bollards at the south plaza entrance.
2. Replacement of any existing Security, CCTV, Detention Lock or Access Control equipment or panels.

DIVISION 14 – CONVEYING SYSTEMS

Lifts

1. We assumed that the future incline lifts in the Judge's Corridors are not in the GMP.

DIVISION 15 – MECHANICAL

Fire Protection

1. 15380 2.04 E 4 calling for a fuel containment area is excluded, as we have a double wall fuel tank as called for in 2.04 E 1.

Lee County Justice Center
100% CD GMP Estimate
11/18/05

Exclusions From G.M.P.

Plumbing

1. 15250 3.01 A calling for preformed insulation products to be used where available. The piping will be insulated per code using code acceptable products.
2. Removal of existing above ground 2000 gal. ConVault fuel oil tank and piping as indicated on P1.0.1 is excluded. We understand that this will be done by the Owner under separate contract.
3. We have not provided sump pumps at the elevator pits.

HVAC

1. 15010 3.11 and 3.11 E calling for an Infection Control Risk Assessment (ICRA) Plan and maintaining a negative air pressure in the construction area applies to hospitals and has not been included in this GMP.
2. Test and balance.

DIVISION 16 - ELECTRICAL

Electrical

1. Permit fees.
2. Power company incoming service to the power company vault.
3. All work and equipment inside the power company vault.
4. We exclude any upgrade or repair of existing electrical equipment being reused.
5. Fuel for the main 15,000 gallon fuel tank is not included.
6. Pumps and controls for pumping fuel from the main fuel tank to the new generator.
7. Public telephones located inside the building.

SECTION 2C



Lee County Justice Center
100% CD GMP Estimate
11/18/05

Allowances

DIVISION 1 – GENERAL REQUIREMENTS

- | | |
|---|-------------|
| 1. Potential sales tax savings from Direct Owner Purchase program | (\$450,000) |
| 2. Potential Value Engineering Savings | (\$300,100) |

DIVISION 2 – SITEWORK

- | | |
|--|----------|
| 1. Tree protection (not clearly indicated on the drawings) | \$10,000 |
| 2. Tree removal (not clearly indicated on the drawings) | \$10,000 |

DIVISION 6 – WOOD & PLASTICS

- | | |
|---|----------|
| 1. Pair of door pull at courtroom entrances per addendum #3 | \$500 EA |
|---|----------|

DIVISION 11 – EQUIPMENT

- | | |
|---|-----------|
| 1. Allowance included for detention equipment and hardware not specified. | \$202,760 |
|---|-----------|

DIVISION 12 – FURNISHINGS

- | | |
|------------------------|-----------|
| 1. Owner's FF&E costs. | \$500,000 |
|------------------------|-----------|

DIVISION 14 – CONVEYING SYSTEMS

- | | |
|---|-------------|
| 1. Public Elevator Cab Finish Allowance | \$20,000/EA |
| 2. Judge Elevator Cab Finish Allowance | \$15,000/EA |
| 3. Inspections cost of temporary elevator | \$3,000 |
| 4. Flooring for Prisoner Elevator cabs | \$4,000 |

SECTION 3

SECTION 3A

CENTEX CONSTRUCTION

PROJECT: LEE COUNTY JUSTICE CENTER - COURTS ADDITION TOWER/JUDGES PARKING GARAGE

BID DATE: October 6, 2005

220,836

SECT.	ITEM	GMP TOTAL	SUB NAME
6	DIV 1 Testing Laboratory	By Owner	
7	Parking	40,000	CC Estimate
8	Surveying	In G.C.'s	
9	Document Reproduction	In G.C.'s	
10	DIV 2 Demolition	25,000	CC Allowance
11	Earthwork	673,000	Bateman
12	Tree Protection	10,000	Allowance
13	Tree Removal	10,000	Allowance
14	Asphalt Paving & Concrete Curbs	In Earthwork	
15	Concrete Paving & Sidewalks	In Earthwork	
16	Pavers	70,000	U.S. Brick
17	Landscape & Irrigation	365,800	CC Estimate
18	Ornamental Fences & Gates	32,500	White Aluminum
19	Site Furnishings	In Landscape	
20	DIV 3 Cranes	818,254	Lewis Equipment
21	Material/Personnel Hoist	298,360	Lewis Equipment
22	Soil Treatment	In Concrete	
23	Cast-in-Place Concrete	7,470,917	Southwest Constr.
24	Architectural Precast	2,716,483	Gate
25	DIV 4 Masonry	724,200	Southwest Constr.
26	DIV 5 Metals	1,248,500	Custom Welding
27	Ornamental Railings	57,000	Lvers
28	Expansion Joint Covers	68,000	Fire Stop Systems
29	DIV 6 Rough Carpentry	By Trades	
30	Temporary Stair Towers	20,000	CC Estimate
31	Wood Stair Infill	2,100	CC Estimate
32	Temporary Ladders	7,500	CC Estimate
33	Finish Carpentry	1,754,620	Adams Brothers
34	Court Room Door Pull Allowance	4,500	Allowance
35	Stone Seals in Courtrooms (Mat'l Allowance)	16,500	Owner Allowance
36	DIV 7 Waterproofing & Caulking	466,800	ABG
37	Roofing	278,500	Sutter
38	Lightweight Insulating Concrete	90,000	Sutter
39	Spray On Fireproofing	N/A	N/A
40	DIV 8 H.M. Doors, Frames & Hardware (Non-Security)	664,826	H.M.S.
41	Overhead Doors	142,900	J.B. Mathews
42	Glass & Glazing	992,500	Harmon
43	DIV 9 Drywall & Stucco	3,448,755	Lotspeich
44	Acoustical	329,200	Lotspeich
45	Tile	356,500	Gator Tile
46	Carpet & Resilient Tile	30,200	Acousti
47	Painting	388,900	CC Estimate
48	DIV 10 Visual Display Boards (3)	6,200	Multiline
49	Toilet Partitions	18,900	ABS
50	Louvers	59,500	Downtown Glass
51	Impact Resistant Wall Protection	None Shown	None Shown
52	Access Flooring	13,250	Irvine
53	Flagpoles	7,200	ABS
54	Building Clock	26,500	Canterbury
55	Installation of Clock	20,000	CC Estimate
56	Metal Lockers	4,600	ABS
57	Fire Extinguishers	5,300	Mardale
58	Signage	By Owner	By Owner
59	Aluminum Sunshades	650,800	Downtown/Peachtree
60	Toilet Accessories	43,400	ABS

CENTEX CONSTRUCTION

PROJECT: LEE COUNTY JUSTICE CENTER - COURTS ADDITION TOWER/JUDGES PARKING GARAGE

BID DATE: October 6, 2005

220,836

	SECT.	ITEM	GMP TOTAL	SUB NAME
61	DIV 11	Projection Screens	18,100	Mardale
62		Projector Lifts	40,000	CC Estimate
63		Residential Appliances	9,700	GE
64		Detention Equipment & Furnishings	212,469	H.M. Specialists
65		Detention Hardware Allowance	202,760	Allowance
66	DIV 12	Entrance Mats	2,300	Kadee
67		Window Treatment	26,000	National Stage
68		FF&E	500,000	Owner Allowance
69	DIV 13	Security Electronics	982,895	Quality
70	DIV 14	Elevators	1,405,400	Kone
71		Public Cab Finish Allowance	40,000	Allowance
72		Judges Cab Finish Allowance	15,000	Allowance
73		Prisoner Cab Floor Finish Allowance	4,000	Allowance
74		Temp Elevator Inspection Allowance	300	Allowance
75		Escalators	In Elevator	In Elevator
76		Wheelchair Lifts	In Elevator	In Elevator
77	DIV 15	Plumbing	1,098,000	B & I Mechanical
78		HVAC	3,492,500	B & I Mechanical
79		Fire Protection	534,863	Naples Fire
80	DIV 16	Electrical	3,960,000	Fortune
81		Start-up	150,000	CC Estimate
82	MISC.	Portable Wheelchair Lifts (2 each)	59,145	CC Estimate
83		Audio/Video Projection System	0	Not Included
84		Turnstiles & Bi-Directional Motorized Gates	100,000	CC Estimate
85		Direct Owner Purchase Order Allowance	(450,000)	Allowance
86		Value Engineering Allowance	(300,100)	Allowance
87				
88		Subtotals	36,580,297	
89		BUILDING PERMIT		
90		GENERAL CONDITIONS	2,870,694	
91		SUBGUARD	457,254	
92		OWNERS PROT LIAB INSURANCE	By Owner	
93		BUILDERS RISK INSURANCE	1,064,062	
94		PERFORMANCE BOND	344,856	
95		INFORMATION TECH SUPPORT	156,753	
96		CASUALTY INSURANCE	492,652	
97		CONTINGENCY	1,097,409	
98		Subtotals	43,063,977	
99		FEE	1,722,559	
100		Subtotal	44,786,536	
101		Additional Preconstruction	160,422	
102		Final GMP Amount	44,946,958	

103

104

COST/SF: \$203.53

SECTION 3B

LEE COUNTY JUSTICE CENTER

BID ALTERNATES

ALTERNATE No. 1 - Add additional Judges Elevator. Price to include fire shutters at each finished floor.

ADD: \$265,860

ALTERNATE No. 2 - Add additional Public Elevator.

ADD: \$452,531

ALTERNATE No. 3 - Delete all work associated with the "Street Scape Improvements".

ADD: (\$324,385)

**CENTEX
CONSTRUCTION**

LEE COUNTY JUSTICE CENTER

ALTERNATE No. 1 - Add additional Judges Elevator. Price to include fire shutters at each finished floor.

Trade	Price	Sub Name
Overhead Doors (5 ea)	\$22,570	
Tile Flooring	\$420	
Elevators	\$210,800	
Electrical	<u>\$2,700</u>	
Sub Total	\$236,490	
Mark-ups	<u>\$29,370</u>	
Total	\$265,860	

**CENTEX
CONSTRUCTION**

LEE COUNTY JUSTICE CENTER

ALTERNATE No. 2 - Add additional Public Elevator.

Trade	Price	Sub Name
Tile Flooring	\$840	
Elevators	\$396,700	
Electrical	<u>\$5,000</u>	
Sub Total	\$402,540	
Mark-ups	<u>\$49,991</u>	
Total	\$452,531	

**CENTEX
CONSTRUCTION**

LEE COUNTY JUSTICE CENTER

ALTERNATE No. 3 - Delete all work associated with the "Street Scape Improvements".

Trade	Price	Sub Name
Earthwork	(\$256,900)	
Pavers	(\$21,000)	
Landscaping	(\$48,650)	
Electrical	<u>\$38,000</u>	
Sub Total	(\$288,550)	
Mark-ups	<u>(\$35,835)</u>	
Total	(\$324,385)	

LEE COUNTY JUSTICE CENTER

BID ALTERNATES

ALTERNATE No. 1 - Add additional Judges Elevator. Price to include fire shutters at each finished floor.

ADD: \$265,860

ALTERNATE No. 2 - Add additional Public Elevator.

ADD: \$452,531

ALTERNATE No. 3 - Delete all work associated with the "Street Scape Improvements".

ADD: (\$324,385)

SECTION 3C

CENTEX CONSTRUCTION, LLC.
Lee County Justice Center - Proposed Courts Addition
Subcontractor Proposed Value Engineering Opportunities

CSI Division	Scope	V.E. Proposal	Value
3	Arch. Precast Conc.	1. Use plain steel rebar in lieu of galvanized 2. Prime paint connections in lieu of galvanizing.	(\$59,800) (\$15,256) Subtotal: (\$75,056)
5	Metal Fabrications	1. Reduce corner guards in parking garage to 2'-6" in lieu of 4'-0" 2. Use embed plates at stairs & elevators in lieu of wedge anchors 3. Voluntary alternate (see attached) 4. Use beams (w8x15) in lieu of 8x4 t.s.	(\$800) (\$4,200) (\$7,000) (\$8,115) Subtotal: (\$20,115)
6	Millwork	1. Change all solid hardwood specified as quarter sawn Anigre to Sapele (solid) 2. Use Marshall Company for courtroom pew benches.	(\$22,750) (\$5,000) Subtotal: (\$27,750)
8	Doors & Hardware	1. Provide doors w/ "A" grade face in lieu of "AA" and plain slice in lieu of quarter slice	(\$5,123)
9	Framing & Gyp. Bd.	1. Use Spec Seal AS 200 for floor to floor fire safing in lieu of Balco FF2H04 system.	(\$224,605)
13	Security Electronics	1. Substitute Samsung CCTV Camera Products	(\$11,170)
15	Plumbing	1. Provide PVC aboveground sanitary and storm piping in lieu of cast iron	(\$45,000)
15	HVAC	1. Delete the marine lights in AHU-1RA and 2RA 2. Provide externally insulated single wall duct in lieu of double wall duct 3. Provide Standard mill finish on louvers in lieu of kynar 4. Provide standard tape closure on duct insulation in lieu of fabric & mastic 5. Provide standard galvanized sheet metal exhaust duct in garage in lieu of 16 gauge welded steel 6. Provide P/T plugs in lieu of pressure gauges and thermometers for VAV box reheat coils (±200) 7. Delete fan cages and belt guards for AHU-1RA & 2RA (units will still meet ETL safety req'ts.) 8. Provide premium efficiency ODP fan motors for AHU-1RA, 2RA and 11 in lieu of TEFC motors 9. Provide 20 gauge inner liner in lieu of 16 gauge for air handling unit cabinets 10. Provide static fire dampers in lieu of dynamic fire dampers 11. Provide alternate style air distribution devices 12. Provide standard insulation in VAV boxes in lieu of closed cell insulation 13. Delete the lighting control system 14. Reduce the number of points monitored by the HVAC controls system. (estimate. Not quantified)	(\$1,000) (\$50,000) (\$2,000) (\$10,000) (\$15,000) (\$40,000) (\$5,000) (\$6,000) (\$2,000) (\$3,000) (\$4,500) (\$3,000) (\$50,000) (\$10,000) Subtotal: (\$201,500)
16	Electrical	1. Review fixture package for savings	(\$24,000)
		Grand total:	(\$634,319)

SECTION 4



Lee County Justice Center
100% CD GMP Estimate
11/18/05

Schedule Narrative

Schedule Narrative

1. This Guaranteed Maximum Price Proposal is predicated on a construction schedule of 23 months duration to substantial completion and 24 months duration to final completion.
2. The 23 month duration to substantial completion and 24 month duration to final completion will commence based on the actual notice to proceed date.
3. The 23 month duration to substantial completion and 24 month duration to final completion are predicated on all permitting and required approvals being in place at time of notice to proceed.

SECTION 5

Lee County Justice Center: Proposed Courts Addition
Document Log
100% C.D. Submittal: 9/06/2005

Description	Drawing No.	Drawing Date	Architect/ Engineer	Date Received	Addendum	Drawing Date	Date Received	Comments
DRAWINGS								
VOLUME 1:								
GENERAL								
Cover Sheet - Volume 1	G000	9/6/2005	BSSW	9/9/2005				
Sheet Index - Volume 1	G001	9/6/2005	BSSW	9/9/2005				
Symbols, General Notes, Accessibility	G002	9/6/2005	BSSW	9/9/2005				
Partitions & Standard Assemblies	G003	9/6/2005	BSSW	9/9/2005				
Master Material Keynote List	G004	9/6/2005	BSSW	9/9/2005				
Axonometric Views (For Information Only)	G005	9/6/2005	BSSW	9/9/2005				
Axonometric Views (For Information Only)	G006	9/6/2005	BSSW	9/9/2005				
LIFE SAFETY								
Code Analysis, UL Assemblies	LS0.0.1	9/6/2005	BSSW	9/9/2005				
Code Analysis, UL Assemblies	LS0.0.2	9/6/2005	BSSW	9/9/2005				
First Floor Lifesafety Plan (Garage)	LS1.0.1	9/6/2005	BSSW	9/9/2005				
Second Floor Lifesafety Plan (Garage)	LS1.0.2	9/6/2005	BSSW	9/9/2005				
Third Floor Lifesafety Plan (Garage)	LS1.0.3	9/6/2005	BSSW	9/9/2005				
First Floor Lifesafety Plan	LS1.1.1	9/6/2005	BSSW	9/9/2005				
Second Floor Lifesafety Plan	LS1.2.1	9/6/2005	BSSW	9/9/2005				
Third Floor Lifesafety Plan	LS1.3.1	9/6/2005	BSSW	9/9/2005				
Fourth Floor Lifesafety Plan	LS1.4.1	9/6/2005	BSSW	9/9/2005				
Fifth Floor Lifesafety Plan	LS1.5.1	9/6/2005	BSSW	9/9/2005				
Transfer Level Lifesafety Plan	LS1.5.2	9/6/2005	BSSW	9/9/2005				
Sixth Floor Lifesafety Plan	LS1.6.1	9/6/2005	BSSW	9/9/2005				
Seventh, Eighth, & Ninth Floor Lifesafety Plans	LS1.7.9	9/6/2005	BSSW	9/9/2005				
Tenth Floor Lifesafety Plan	LS1.10.1	9/6/2005	BSSW	9/9/2005				
SITE PLANS								
Overall Site Plan	AS1.0.1	9/6/2005	TKW	9/9/2005				
Plaza Site Plan	AS1.0.2	9/6/2005	TKW	9/9/2005				
Site Plan - Plaza Cont	AS1.0.3	9/6/2005	TKW	9/9/2005				
Site Details	AS1.0.4	Missing	TKW	9/9/2005				
CIVIL								
Cover Sheet & Location Map	C1	8/8/2005	TKW	9/9/2005				
Aerial Photograph	C2	8/8/2005	TKW	9/9/2005				
Site Plan	C3	8/6/2005	TKW	9/9/2005				
Paving, Grading & Drainage Plan	C4	8/8/2005	TKW	9/9/2005				
Drainage Details	C5	8/8/2005	TKW	9/9/2005				
Utility Plan	C6	8/8/2005	TKW	9/9/2005				
Utility Details Sanitary	C7	8/8/2005	TKW	9/9/2005				
Utility Details Water	C8	8/8/2005	TKW	9/9/2005				
SWP #3	C9	8/8/2005	TKW	9/9/2005				
LANDSCAPE								
Hardscape Site Plan	L-1	9/6/2005	TLC	9/9/2005				
Hardscape Site Plan	L-2	9/6/2005	TLC	9/9/2005				
Hardscape Detailed Site Plan	L-3	9/6/2005	TLC	9/9/2005				
Hardscape Details	L-4	9/6/2005	TLC	9/9/2005				
Not Used	L-5	--	TLC		3	9/27/2005	10/3/2005	
Landscape Plan	L-8	9/6/2005	TLC	9/9/2005				
Landscape Plan	L-7	9/6/2005	TLC	9/9/2005				
Detailed Plaza Landscape Plan	L-8	9/6/2005	TLC	9/9/2005				
Landscape Details	L-9	9/6/2005	TLC	9/9/2005				
Irrigation Plan	L-10	9/6/2005	TLC	9/9/2005	3	9/27/2005	10/3/2005	
Irrigation Plan	L-11	9/6/2005	TLC	9/9/2005				
Irrigation Details	L-12	9/6/2005	TLC	9/9/2005				
ARCHITECTURAL								
First Floor Plan - Parking Garage	A1.0.1	9/6/2005	BSSW	9/9/2005				
Second Floor Plan - Parking Garage	A1.0.2	9/6/2005	BSSW	9/9/2005				
Third Floor Plan - Parking Garage	A1.0.3	9/6/2005	BSSW	9/9/2005				
Judges Parking Garage - Door & Finish Schedule	A1.0.4	9/6/2005	BSSW	9/9/2005				
First Floor Plan	A1.1.1	9/6/2005	BSSW	9/9/2005	1	9/23/2005	9/23/2005	
First Floor Plan - Dimensioned	A1.1.1A	--	BSSW		1	9/23/2005	9/23/2005	
First Floor RCP	A1.1.2	9/6/2005	BSSW	9/9/2005				
First Floor Door & Finish Schedules	A1.1.3	9/6/2005	BSSW	9/9/2005				
Second Floor Plan	A1.2.1	9/6/2005	BSSW	9/9/2005				
Second Floor Plan - Dimensioned	A1.2.1A	--	BSSW		1	9/23/2005	9/23/2005	
Second Floor RCP	A1.2.2	9/6/2005	BSSW	9/9/2005				
Second Floor Door & Finish Schedules	A1.2.3	9/6/2005	BSSW	9/9/2005				
Third Floor Plan	A1.3.1	9/6/2005	BSSW	9/9/2005				
Third Floor Plan - Dimensioned	A1.3.1A	--	BSSW		1	9/23/2005	9/23/2005	
Third Floor RCP	A1.3.2	9/6/2005	BSSW	9/9/2005				
Third Floor Door & Finish Schedules	A1.3.3	9/6/2005	BSSW	9/9/2005				
Fourth Floor Plan, RCP, & Schedules	A1.4.1	9/6/2005	BSSW	9/9/2005				

Lee County Justice Center: Proposed Courts Addition
Document Log
100% C.D. Submittal: 9/06/2005

Description	Drawing No.	Drawing Date	Architect/ Engineer	Date Received	Addendum	Drawing Date	Date Received	Comments
Fifth Floor Plan	A1.5.1	9/6/2005	BSSW	9/9/2005				
Fifth Floor Plan - Dimensioned	A1.5.1A	--	BSSW		1	9/23/2005	9/23/2005	
Fifth Floor RCP	A1.5.2	9/6/2005	BSSW	9/9/2005				
Fifth Floor Door & Finish Schedules	A1.5.3	9/6/2005	BSSW	9/9/2005				
Transfer Level Floor Plan	A1.5T.1	9/6/2005	BSSW	9/9/2005				
Transfer Level RCP	A1.5T.2	9/6/2005	BSSW	9/9/2005				
Sixth Floor Plan	A1.6.1	9/6/2005	BSSW	9/9/2005				
Sixth Floor Plan - Dimensioned	A1.6.1A	--	BSSW		1	9/23/2005	9/23/2005	
Sixth Floor RCP	A1.6.2	9/6/2005	BSSW	9/9/2005				
Sixth Floor Door & Finish Schedules	A1.6.3	9/6/2005	BSSW	9/9/2005				
Seventh Floor Plan, RCP, & Schedules	A1.7.1	9/6/2005	BSSW	9/9/2005				
Eighth Floor Plan, RCP, & Schedules	A1.6.1	9/6/2005	BSSW	9/9/2005				
Ninth Floor Plan, RCP, & Schedules	A1.9.1	9/6/2005	BSSW	9/9/2005				
Tenth Floor Plan	A1.10.1	9/6/2005	BSSW	9/9/2005				
Tenth Floor Plan - Dimensioned	A1.10.1A	--	BSSW		1	9/23/2005	9/23/2005	
Tenth Floor RCP	A1.10.2	9/6/2005	BSSW	9/9/2005				
Tenth Floor Door & Finish Schedules	A1.10.3	9/6/2005	BSSW	9/9/2005				
Mechanical Penitence Plan	A1.11.1	9/6/2005	BSSW	9/9/2005				
Roof Plan	A1.12.1	9/6/2005	BSSW	9/9/2005				
West Building Elevation - Tower	A2.0.1	9/6/2005	BSSW	9/9/2005				
South Building Elevation - Tower	A2.0.2	9/6/2005	BSSW	9/9/2005				
East Building Elevation - Tower	A2.0.3	9/6/2005	BSSW	9/9/2005				
North Building Elevation - Tower	A2.0.4	9/6/2005	BSSW	9/9/2005				
Building Elevations - Misc	A2.0.5	9/6/2005	BSSW	9/9/2005				
Building Elevations - Parking Garage	A2.0.6	9/6/2005	BSSW	9/9/2005				
Architectural Concrete Panel Schedule	A2.1.1	--	BSSW		1	9/23/2005	9/23/2005	
Architectural Concrete Panel Schedule	A2.1.2	--	BSSW		1	9/23/2005	9/23/2005	
Architectural Concrete Panel Elevations	A2.2.1	9/6/2005	BSSW	9/9/2005				
Architectural Concrete Panel Elevations	A2.2.2	9/6/2005	BSSW	9/9/2005				
Building Section - East/West @ Lobby	A2.3.1	9/6/2005	BSSW	9/9/2005				
Building Section - North/South @ Holding	A2.3.2	9/6/2005	BSSW	9/9/2005				
Building Section - North/South @ West Courtrooms	A2.3.3	9/6/2005	BSSW	9/9/2005				
Building Section - Tower	A2.3.4	9/6/2005	BSSW	9/9/2005				
Building Section - Tower	A2.3.5	9/6/2005	BSSW	9/9/2005				
Building Section - Tower	A2.3.6	9/6/2005	BSSW	9/9/2005				
Building Section - Tower	A2.3.7	9/6/2005	BSSW	9/9/2005				
Building Section - Parking Garage	A2.3.8	9/6/2005	BSSW	9/9/2005				
Building Section - Parking Garage	A2.3.9	9/6/2005	BSSW	9/9/2005				
Building Section - Parking Garage	A2.3.10	9/6/2005	BSSW	9/9/2005				
Door & Window Elevations	A2.4.1	9/6/2005	BSSW	9/9/2005				
Door/Frame Elevations	A2.4.2	9/6/2005	BSSW	9/9/2005				
Wall Section @ Col. Line 4	A3.1.1	9/6/2005	BSSW	9/9/2005				
Wall Section @ Col. Line F	A3.1.2	9/6/2005	BSSW	9/9/2005				
Wall Section - Lobby West	A3.1.3	9/6/2005	BSSW	9/9/2005				
Wall Section - Entry Lobby	A3.1.4	9/6/2005	BSSW	9/9/2005				
Wall Section @ Connector to Existing JC	A3.1.5	9/6/2005	BSSW	9/9/2005				
Wall Section @ Stair No. 3	A3.1.6	9/6/2005	BSSW	9/9/2005				
Wall Section @ Col. Line A	A3.1.7	9/6/2005	BSSW	9/9/2005				
Wall Section @ Exist. Justice Center	A3.1.8	9/6/2005	BSSW	9/9/2005				
Wall Section @ Stair No. 2 and Exist. Justice Center	A3.1.9	9/6/2005	BSSW	9/9/2005				
Wall Section - Parking Garage	A3.1.10	9/6/2005	BSSW	9/9/2005				
Wall Section - Parking Garage	A3.1.11	9/6/2005	BSSW	9/9/2005				
Architectural Concrete Panel Details	A3.2.1	9/6/2005	BSSW	9/9/2005				
Architectural Concrete Panel Details	A3.2.2	9/6/2005	BSSW	9/9/2005				
Canopy Details	A3.2.3	9/6/2005	BSSW	9/9/2005				
Details @ Security Lobby Details Cont.	A3.2.4	9/6/2005	BSSW	9/9/2005				
Details - Expansion Joints	A3.2.5	9/6/2005	BSSW	9/9/2005				
Details - Exterior Walls	A3.2.6	9/6/2005	BSSW	9/9/2005	1	9/23/2005	9/23/2005	
Details - Roof	A3.3.1	9/6/2005	BSSW	9/9/2005				
Details - Roof	A3.3.2	9/6/2005	BSSW	9/9/2005				
Details - Roof	A3.3.3	9/6/2005	BSSW	9/9/2005				
Enlarged Outrigger Plan and Details	A3.3.4	9/6/2005	BSSW	9/9/2005				
Aluminum Canopy @ Aluminum Grille Details	A3.3.5	9/6/2005	BSSW	9/9/2005				
Door/Window Details	A3.4.1	9/6/2005	BSSW	9/9/2005				
Door/Window Details	A3.4.2	9/6/2005	BSSW	9/9/2005				
Stair No. 1 - Enlarged Plans & Section	A4.0.1	9/6/2005	BSSW	9/9/2005				
Stair No. 2 - Sections	A4.0.2	9/6/2005	BSSW	9/9/2005				
Stair No. 2 - Enlarged Plans	A4.0.3	9/6/2005	BSSW	9/9/2005				
Stair No. 3 - Enlarged Plans & Section	A4.0.4	9/6/2005	BSSW	9/9/2005				
Stair No. 4 - Enlarged Plans & Section	A4.0.5	9/6/2005	BSSW	9/9/2005				
Enlarged Plans @ Connector to Existing Justice Center	A4.0.6	9/6/2005	BSSW	9/9/2005				
Judge & Prisoner Elevator - Enlarged Plans & Section	A4.1.1	9/6/2005	BSSW	9/9/2005				
Public Elevator - Enlarged Plans & Section	A4.1.2	9/6/2005	BSSW	9/9/2005				
Escalator Enlarged Plans and Sections	A4.2.1	9/6/2005	BSSW	9/9/2005				
Restroom Enlarged Plans	A5.0.1	9/6/2005	BSSW	9/9/2005				
Courtroom - Enlarged Plans - Judges Benches & Jury Boxes	A5.1.1	9/6/2005	BSSW	9/9/2005				
Courtroom - Interior Elevations & Sections	A5.1.2	9/6/2005	BSSW	9/9/2005				
Courtroom - Interior Elevations & Sections	A5.1.3	9/6/2005	BSSW	9/9/2005				
Enlarged Security Lobby Plan	A5.1.4	9/6/2005	BSSW	9/9/2005				

Lee County Justice Center: Proposed Courts Addition
Document Log
100% C.D. Submittal: 9/06/2005

Description	Drawing No.	Drawing Date	Architect/ Engineer	Date Received	Addendum	Drawing Date	Date Received	Comments
Interior Elevations	A5.1.5	9/6/2005	BSSW	9/9/2005				
Interior Elevations	A5.1.6	9/6/2005	BSSW	9/9/2005				
Millwork Details	A5.4.1	9/6/2005	BSSW	9/9/2005				
Millwork Details	A5.4.2	9/6/2005	BSSW	9/9/2005				
Casework Sections & Details	A5.4.3	9/6/2005	BSSW	9/9/2005				
FFE - 1st Floor	A6.1.1	9/6/2005	BSSW	9/9/2005				
FFE - 2nd Floor	A6.1.2	9/6/2005	BSSW	9/9/2005				
FFE - 3rd Floor	A6.1.3	9/6/2005	BSSW	9/9/2005				
FFE - 4th Floor	A6.1.4	9/6/2005	BSSW	9/9/2005				
FFE - 5th Floor	A6.1.5	9/6/2005	BSSW	9/9/2005				
FFE - Transfer Level	A6.1.6	9/6/2005	BSSW	9/9/2005				
FFE - 6th & 7th Floor	A6.1.7	9/6/2005	BSSW	9/9/2005				
FFE - 6th & 9th Floor	A6.1.6	9/6/2005	BSSW	9/9/2005				
STRUCTURAL								
General Notes	S100	9/6/2005	TKW	9/9/2005				
Component and Cladding Design & Wind Pressure	S100A	9/6/2005	TKW	9/9/2005				
First Floor Foundation Plan	S101	9/6/2005	TKW	9/9/2005				
Second Floor Framing Plan	S102	9/6/2005	TKW	9/9/2005				
Third Floor Framing Plan	S103	9/6/2005	TKW	9/9/2005				
Fourth Floor Framing Plan	S104	9/6/2005	TKW	9/9/2005				
Fifth Floor Framing Plan	S105	9/6/2005	TKW	9/9/2005				
Transfer Floor Framing Plan	S105A	9/6/2005	TKW	9/9/2005				
Sixth Floor Framing Plan	S106	9/6/2005	TKW	9/9/2005				
Seventh Floor Framing Plan	S107	9/6/2005	TKW	9/9/2005				
Eighth Floor Framing Plan	S106	9/6/2005	TKW	9/9/2005				
Ninth Floor Framing Plan	S109	9/6/2005	TKW	9/9/2005				
Tenth Floor Framing Plan	S110	9/6/2005	TKW	9/9/2005				
Roof Framing Plan	S111	9/6/2005	TKW	9/9/2005				
Mechanical Penthouse Roof Framing Plan	S112	9/6/2005	TKW	9/9/2005				
Parking Garage Ground Floor Foundation Plan	S201	9/6/2005	TKW	9/9/2005				
Parking Garage Second Floor Framing Plan	S202	9/6/2005	TKW	9/9/2005				
Parking Garage Third Floor Framing Plan	S203	9/6/2005	TKW	9/9/2005				
Section And Details	S300	9/6/2005	TKW	9/9/2005				
Section And Details	S301	9/6/2005	TKW	9/9/2005				
Section And Details	S302	9/6/2005	TKW	9/9/2005				
Section And Details	S303	9/6/2005	TKW	9/9/2005				
Section And Details	S304	9/6/2005	TKW	9/9/2005				
Shear Wall Reinforcing Elevations	S400	9/6/2005	TKW	9/9/2005				
Schedules, Section And Details	S401	9/6/2005	TKW	9/9/2005				
Column And Beam Schedule	S402	9/6/2005	TKW	9/9/2005				
Pile Cap and Column Details	S403	9/6/2005	TKW	9/9/2005				
VOLUME 2								
PLUMBING								
Plumbing Legend, Notes, & Index	P0.0.0	9/6/2005	TLC	9/9/2005				
First Floor Plan - Parking Garage Plumbing Plan	P1.0.1	9/6/2005	TLC	9/9/2005				
Second Floor Plan - Parking Garage Plumbing Plan	P1.0.2	9/6/2005	TLC	9/9/2005				
Third Floor Plan - Parking Garage Plumbing Plan	P1.0.3	9/6/2005	TLC	9/9/2005				
Garage Roof Plumbing Plan	P1.0.4	9/6/2005	TLC	9/9/2005				
First Floor Plan - Plumbing	P1.1.1	9/6/2005	TLC	9/9/2005				
Second Floor Plan - Plumbing	P1.2.1	9/6/2005	TLC	9/9/2005				
Third Floor Plan - Plumbing	P1.3.1	9/6/2005	TLC	9/9/2005				
Fourth Floor Plan - Plumbing	P1.4.1	9/6/2005	TLC	9/9/2005				
Fifth Floor Plan - Plumbing	P1.5.1	9/6/2005	TLC	9/9/2005				
Transfer Level Plan - Plumbing	P1.5.5	9/6/2005	TLC	9/9/2005				
Sixth Floor Plan - Plumbing	P1.6.1	9/6/2005	TLC	9/9/2005				
Seventh Floor Plan - Plumbing	P1.7.1	9/6/2005	TLC	9/9/2005				
Eighth Floor Plan - Plumbing	P1.8.1	9/6/2005	TLC	9/9/2005				
Ninth Floor Plan - Plumbing	P1.9.1	9/6/2005	TLC	9/9/2005				
Tenth Floor Plan - Plumbing	P1.10.1	9/6/2005	TLC	9/9/2005				
Mechanical Penthouse Plan - Plumbing	P1.11.1	9/6/2005	TLC	9/9/2005				
Roof Plan - Plumbing	P1.12.1	9/6/2005	TLC	9/9/2005				
Plumbing Details	P2.0.1	9/6/2005	TLC	9/9/2005				
Plumbing Details	P2.0.2	9/6/2005	TLC	9/9/2005				
Riser Diagrams	P3.0.1	9/6/2005	TLC	9/9/2005				
Riser Diagrams	P3.0.2	9/6/2005	TLC	9/9/2005				
Enlarged Plumbing Plans	P4.0.1	9/6/2005	TLC	9/9/2005				
Plumbing Fixture Schedules	P5.0.1	9/6/2005	TLC	9/9/2005				
MECHANICAL								
HVAC Legends, Notes & Index	M0.0.0	9/6/2005	TLC	9/9/2005				
First Floor Plan - Parking Garage - HVAC	M1.0.1	9/6/2005	TLC	9/9/2005				
Second Floor Plan - Parking Garage - HVAC	M1.0.2	9/6/2005	TLC	9/9/2005				
Third Floor Plan - Parking Garage - HVAC	M1.0.3	9/6/2005	TLC	9/9/2005				
Roof Plan - Parking Garage	M1.0.4		TLC					Missing
HVAC Model	M1.0.5		TLC					Missing

Lee County Justice Center: Proposed Courts Addition
Document Log
100% C.D. Submittal: 9/06/2005

Description	Drawing No.	Drawing Date	Architect/ Engineer	Date Received	Addendum	Drawing Date	Date Received	Comments
First Floor Ductwork Plan - HVAC	M1.1.1	9/6/2005	TLC	9/9/2005				
First Floor Piping Plan - HVAC	M1.1.2	9/6/2005	TLC	9/9/2005				
Second Floor Ductwork Plan - HVAC	M1.2.1	9/6/2005	TLC	9/9/2005	2	9/26/2005	9/27/2005	
Second Floor Piping Plan - HVAC	M1.2.2	9/6/2005	TLC	9/9/2005				
Third Floor Ductwork Plan - HVAC	M1.3.1	9/6/2005	TLC	9/9/2005				
Third Floor Piping Plan - HVAC	M1.3.2	9/6/2005	TLC	9/9/2005				
Fourth Floor Ductwork Plan - HVAC	M1.4.1	9/6/2005	TLC	9/9/2005				
Fourth Floor Piping Plan - HVAC	M1.4.2	9/6/2005	TLC	9/9/2005				
Fifth Floor Ductwork Plan - HVAC	M1.5.1	9/6/2005	TLC	9/9/2005				
Fifth Floor Piping Plan - HVAC	M1.5.2	9/6/2005	TLC	9/9/2005				
Transfer Level Ductwork Plan - HVAC	M1.5.5	9/6/2005	TLC	9/9/2005				
Transfer Level Piping Plan - HVAC	M1.5.6	9/6/2005	TLC	9/9/2005				
Sixth Floor Ductwork Plan - HVAC	M1.6.1	9/6/2005	TLC	9/9/2005				
Sixth Floor Piping Plan - HVAC	M1.6.2	9/6/2005	TLC	9/9/2005				
Seventh Floor Ductwork Plan - HVAC	M1.7.1	9/6/2005	TLC	9/9/2005				
Seventh Floor Piping Plan - HVAC	M1.7.2	9/6/2005	TLC	9/9/2005				
Eighth Floor Ductwork Plan - HVAC	M1.8.1	9/6/2005	TLC	9/9/2005				
Eighth Floor Piping Plan - HVAC	M1.8.2	9/6/2005	TLC	9/9/2005				
Ninth Floor Ductwork Plan - HVAC	M1.9.1	9/6/2005	TLC	9/9/2005				
Ninth Floor Piping Plan - HVAC	M1.9.2	9/6/2005	TLC	9/9/2005				
Tenth Floor Ductwork Plan - HVAC	M1.10.1	9/6/2005	TLC	9/9/2005				
Tenth Floor Piping Plan - HVAC	M1.10.2	9/6/2005	TLC	9/9/2005				
Penthouse Plan - HVAC	M1.11.1	9/6/2005	TLC	9/9/2005				
HVAC Controls	M2.1.1	9/6/2005	TLC	9/9/2005	3	9/29/2005	10/3/2005	
HVAC Controls	M2.1.2	9/6/2005	TLC	9/9/2005				
HVAC Controls	M2.1.3	9/6/2005	TLC	9/9/2005				
HVAC Details	M3.1.1	9/6/2005	TLC	9/9/2005				
HVAC Details	M3.1.2	9/6/2005	TLC	9/9/2005				
HVAC Schedules	M4.1.1	9/6/2005	TLC	9/9/2005				
HVAC Schedules	M4.1.2	9/6/2005	TLC	9/9/2005				
HVAC Schedules	M4.1.3	9/6/2005	TLC	9/9/2005				
FIRE PROTECTION								
Fire Protection Symbols and Notes	F0.0.0	9/6/2005	TLC	9/9/2005				
Ground Floor Plan - Judges Parking - Fire Protection	F0.0.1		TLC					Missing
First Floor Plan - Judges Parking - Fire Protection	F0.0.2		TLC					Missing
Second Floor Plan - Judges Parking - Fire Protection	F0.0.3		TLC					Missing
First Floor Plan - Parking Garage - Fire Protection	F1.0.1	9/6/2005	TLC	9/9/2005				
Second Floor Plan - Parking Garage - Fire Protection	F1.0.2	9/6/2005	TLC	9/9/2005				
First Floor Plan - Fire Protection	F1.1.1	9/6/2005	TLC	9/9/2005				
Second Floor Plan - Fire Protection	F1.2.1	9/6/2005	TLC	9/9/2005				
Third Floor Plan - Fire Protection	F1.3.1	9/6/2005	TLC	9/9/2005				
Fourth Floor Plan - Fire Protection	F1.4.1	9/6/2005	TLC	9/9/2005				
Fifth Floor Plan - Fire Protection	F1.5.1	9/6/2005	TLC	9/9/2005				
Transfer Level Plan - Fire Protection	F1.5.5	9/6/2005	TLC	9/9/2005				
Sixth Floor Plan - Fire Protection	F1.6.1	9/6/2005	TLC	9/9/2005				
Seventh Floor Plan - Fire Protection	F1.7.1	9/6/2005	TLC	9/9/2005				
Eighth Floor Plan - Fire Protection	F1.8.1	9/6/2005	TLC	9/9/2005				
Ninth Floor Plan - Fire Protection	F1.9.1	9/6/2005	TLC	9/9/2005				
Tenth Floor Plan - Fire Protection	F1.10.1	9/6/2005	TLC	9/9/2005				
Roof Plan - Fire Protection	F.11.1	9/6/2005	TLC	9/9/2005				
Fire Protection Details	F2.0.0	9/6/2005	TLC	9/9/2005				
Fire Protection Riser	F2.0.0	9/6/2005	TLC	9/9/2005				Duplicated Page #
ELECTRICAL								
Electrical Symb. Legend, Light. Fixt. Sched. & Gen. Notes	E0.0.0	9/6/2005	TLC	9/9/2005				
Site Plan - Electrical	E0.0.1	9/6/2005	TLC	9/9/2005	3	9/29/2005	10/3/2005	
First Floor Plan - Parking Garage - Lighting	E1.0.1	9/6/2005	TLC	9/9/2005				
Second Floor Plan - Parking Garage - Lighting	E1.0.2	9/6/2005	TLC	9/9/2005				
Third Floor Plan - Parking Garage - Lighting	E1.0.3	9/6/2005	TLC	9/9/2005				
First Floor Plan - Lighting	E1.1.1	9/6/2005	TLC	9/9/2005				
Second Floor Plan - Lighting	E1.2.1	9/6/2005	TLC	9/9/2005				
Third Floor Plan - Lighting	E1.3.1	9/6/2005	TLC	9/9/2005				
Fourth Floor Plan - Lighting	E1.4.1	9/6/2005	TLC	9/9/2005				
Fifth Floor Plan - Lighting	E1.5.1	9/6/2005	TLC	9/9/2005				
Transfer Level Plan - Lighting	E1.5.5	9/6/2005	TLC	9/9/2005				
Sixth Floor Plan - Lighting	E1.6.1	9/6/2005	TLC	9/9/2005				
Seventh Floor Plan - Lighting	E1.7.1	9/6/2005	TLC	9/9/2005				
Eighth Floor Plan - Lighting	E1.8.1	9/6/2005	TLC	9/9/2005				
Ninth Floor Plan - Lighting	E1.9.1	9/6/2005	TLC	9/9/2005				
Tenth Floor Plan - Lighting	E1.10.1	9/6/2005	TLC	9/9/2005				
Mechanical Penthouse Plan - Lighting	E1.11.1	9/6/2005	TLC	9/9/2005				
Building Roof - Lighting	E1.12.1	9/6/2005	TLC	9/9/2005				
First Floor Plan - Parking Garage - Power & Systems	E2.0.1	9/6/2005	TLC	9/9/2005				
Second Floor Plan - Parking Garage - Power & Systems	E2.0.2	9/6/2005	TLC	9/9/2005				
Third Floor Plan - Parking Garage - Power & Systems	E2.0.3	9/6/2005	TLC	9/9/2005				

Lee County Justice Center: Proposed Courts Addition
Document Log
100% C.D. Submittal: 9/06/2005

Description	Drawing No.	Drawing Date	Architect/ Engineer	Date Received	Addendum	Drawing Date	Date Received	Comments
First Floor Plan - Power & Systems	E2.1.1	9/6/2005	TLC	9/9/2005				
Second Floor Plan - Power & Systems	E2.2.1	9/6/2005	TLC	9/9/2005				
Third Floor Plan - Power & Systems	E2.3.1	9/6/2005	TLC	9/9/2005				
Fourth Floor Plan - Power & Systems	E2.4.1	9/6/2005	TLC	9/9/2005				
Fifth Floor Plan - Power & Systems	E2.5.1	9/6/2005	TLC	9/9/2005				
Transfer Level Plan - Power & Systems	E2.5.5	9/6/2005	TLC	9/9/2005				
Sixth Floor Plan - Power & Systems	E2.6.1	9/6/2005	TLC	9/9/2005				
Seventh Floor Plan - Power & Systems	E2.7.1	9/6/2005	TLC	9/9/2005				
Eighth Floor Plan - Power & Systems	E2.6.1	9/6/2005	TLC	9/9/2005				
Ninth Floor Plan - Power & Systems	E2.9.1	9/6/2005	TLC	9/9/2005				
Tenth Floor Plan - Power & Systems	E2.10.1	9/6/2005	TLC	9/9/2005				
Judges Parking Roof Plan	E3.0.1		TLC					Missing
Roof Plan - Electrical	E3.11.1	9/6/2005	TLC	9/9/2005				
1st Floor Enlarged Electrical Plan	E4.1.1	9/6/2005	TLC	9/9/2005				
2nd Floor Enlarged Electrical Plan	E4.2.1	9/6/2005	TLC	9/9/2005				
3rd Floor Enlarged Electrical Plan	E4.3.1	9/6/2005	TLC	9/9/2005				
4th Floor Enlarged Electrical Plan	E4.4.1	9/6/2005	TLC	9/9/2005				
5th Floor Enlarged Electrical Plan	E4.5.1	9/6/2005	TLC	9/9/2005				
Transfer Level Enlarged Electrical Plan	E4.5.5		TLC					Missing
6th Floor Enlarged Electrical Plan	E4.6.1	9/6/2005	TLC	9/9/2005				
7th Floor Enlarged Electrical Plan	E4.7.1	9/6/2005	TLC	9/9/2005				
6th Floor Enlarged Electrical Plan	E4.8.1	9/6/2005	TLC	9/9/2005				
9th & 10th Floor Enlarged Electrical Plan	E4.9.1	9/6/2005	TLC	9/9/2005				
Power Riser Diagram	E5.0.1	9/6/2005	TLC	9/9/2005	3	9/29/2005	10/3/2005	
Fire Alarm Riser Diagram	E5.1.1	9/6/2005	TLC	9/9/2005				
Panelboard Schedules	E6.0.1	9/6/2005	TLC	9/9/2005	3	9/29/2005	10/3/2005	
Panelboard Schedules	E6.0.2	9/6/2005	TLC	9/9/2005	3	9/29/2005	10/3/2005	
Panelboard Schedules	E6.0.3	9/6/2005	TLC	9/9/2005	3	9/29/2005	10/3/2005	
Panelboard Schedules	E6.0.4	9/6/2005	TLC	9/9/2005	3	9/29/2005	10/3/2005	
Panelboard Schedules	E6.0.5	9/6/2005	TLC	9/9/2005	3	9/29/2005	10/3/2005	
Panelboard Schedules	E6.0.6	9/6/2005	TLC	9/9/2005	3	9/29/2005	10/3/2005	
Panelboard Schedules	E6.0.7	9/6/2005	TLC	9/9/2005	3	9/29/2005	10/3/2005	
Panelboard Schedules	E6.0.6	9/6/2005	TLC	9/9/2005	3	9/29/2005	10/3/2005	
Panelboard Schedules	E6.0.9	9/6/2005	TLC	9/9/2005	3	9/29/2005	10/3/2005	
Panelboard Schedules	E6.0.10	9/6/2005	TLC	9/9/2005				
Panelboard Schedules	E6.0.11	9/6/2005	TLC	9/9/2005	3	9/29/2005	10/3/2005	
Dimming Panels & Schedules	E6.0.12	9/6/2005	TLC	9/9/2005				
Lighting Protection Plan	E7.11.1	9/6/2005	TLC	9/9/2005				
Electrical Details	E8.0.1	9/6/2005	TLC	9/9/2005				
Electrical Details	E8.0.2	9/6/2005	TLC	9/9/2005				
Electrical Details	E8.0.3	9/6/2005	TLC	9/9/2005				
Electrical Details	E8.0.4	9/6/2005	TLC	9/9/2005				
TECHNOLOGY								
Technology Legends, Symbols, Notes	T0.0.0	9/6/2005	TLC	9/9/2005				
Site Plan - Technology	T0.0.1		TLC					Missing
Parking 1st Floor Technology Plan	T1.0.1	9/6/2005	TLC	9/9/2005				
Parking 2nd Floor Technology Plan	T1.0.2		TLC					Missing
Parking 3rd Floor Technology Plan	T1.0.3		TLC					Missing
First Floor Technology Plan	T1.1.1	9/6/2005	TLC	9/9/2005				
Second Floor Technology Plan	T1.2.1	9/6/2005	TLC	9/9/2005				
Third Floor Technology Plan	T1.3.1	9/6/2005	TLC	9/9/2005				
Fourth Floor Technology Plan	T1.4.1	9/6/2005	TLC	9/9/2005				
Fifth Floor Technology Plan	T1.5.1	9/6/2005	TLC	9/9/2005				
Transfer Level Technology Plan	T1.5.5	9/6/2005	TLC	9/9/2005				
Sixth Floor Technology Plan	T1.6.1	9/6/2005	TLC	9/9/2005				
Seventh Floor Technology Plan	T1.7.1	9/6/2005	TLC	9/9/2005				
Eighth Floor Technology Plan	T1.8.1	9/6/2005	TLC	9/9/2005				
Ninth Floor Technology Plan	T1.9.1	9/6/2005	TLC	9/9/2005				
Tenth Floor Technology Plan	T1.10.1	9/6/2005	TLC	9/9/2005				
Roof Mechanical Penthouse Technology Plan	T1.11.1		TLC					Missing
Conduit and Grounding/Bonding Riser Diagram	T2.0.1	9/6/2005	TLC	9/9/2005				
Copper Riser and Fiber Optic Riser Diagram	T3.0.1	9/6/2005	TLC	9/9/2005				
1st Floor Enlarged Technology Plan	T4.1.1	9/6/2005	TLC	9/9/2005				
2nd Floor Enlarged Technology Plan	T4.2.1	9/6/2005	TLC	9/9/2005				
3rd Floor Enlarged Technology Plan	T4.3.1	9/6/2005	TLC	9/9/2005				
4th Floor Enlarged Technology Plan	T4.4.1	9/6/2005	TLC	9/9/2005				
5th Floor Enlarged Technology Plan	T4.5.1	9/6/2005	TLC	9/9/2005				
Transfer Level Enlarged Technology Plan	T4.5.5		TLC					Missing
6th Floor Enlarged Technology Plan	T4.6.1	9/6/2005	TLC	9/9/2005				
7th Floor Enlarged Technology Plan	T4.7.1	9/6/2005	TLC	9/9/2005				
8th Floor Enlarged Technology Plan	T4.6.1	9/6/2005	TLC	9/9/2005				
9th Floor Enlarged Technology Plan	T4.9.1	9/6/2005	TLC	9/9/2005				
10th Floor Enlarged Technology Plan	T4.10.1	9/6/2005	TLC	9/9/2005				
Technology Details	T5.0.1	9/6/2005	TLC	9/9/2005				
Technology Details	T5.0.2	9/6/2005	TLC	9/9/2005				

Lee County Justice Center: Proposed Courts Addition
Document Log
100% C.D. Submittal: 9/06/2005

Description	Drawing No.	Drawing Date	Architect/ Engineer	Date Received	Addendum	Drawing Date	Date Received	Comments
Technology Details	T5.0.3	9/6/2005	TLC	9/9/2005				
Technology Details	T5.0.4	9/6/2005	TLC	9/9/2005				
Technology Details	T5.0.5	9/6/2005	TLC	9/9/2005				
Technology Details	T5.0.6	9/6/2005	TLC	9/9/2005				
Technology Details	T5.0.7	9/6/2005	TLC	9/9/2005				
Technology Details	T5.0.8	9/6/2005	TLC	9/9/2005				
Technology Details	T5.0.9	9/6/2005	TLC	9/9/2005				
Technology Details	T5.0.10	9/6/2005	TLC	9/9/2005				
Technology Details	T5.0.11	9/6/2005	TLC	9/9/2005				
Technology Details	T5.0.12	9/6/2005	TLC	9/9/2005				
SECURITY CONDUIT								
Plaza Site Security Conduit Plan	SC.CA..S.1	9/6/2005	Kroll	9/9/2005				
Plaza Site Security Conduit Plan	SC.CA..S.2	9/6/2005	Kroll	9/9/2005				
Security Conduit Legend	SC.CA.00.0	9/6/2005	Kroll	9/9/2005				
Security Conduit Details	SC.CA.00.1	9/6/2005	Kroll	9/9/2005				
Security Conduit Details	SC.CA.00.2	9/6/2005	Kroll	9/9/2005				
Security Conduit Details	SC.CA.00.3	9/6/2005	Kroll	9/9/2005				
Security Conduit Details	SC.CA.00.4	9/6/2005	Kroll	9/9/2005				
Site Plan	SC.CA..S.0		Kroll					Missing
First Floor Security Conduit Plan	SC.CA..01.0	9/6/2005	Kroll	9/9/2005				
Second Floor Security Conduit Plan	SC.CA..02.0	9/6/2005	Kroll	9/9/2005				
Third Floor Security Conduit Plan	SC.CA..03.0	9/6/2005	Kroll	9/9/2005				
Fourth Floor Security Conduit Plan	SC.CA..04.0	9/6/2005	Kroll	9/9/2005				
Fifth Floor Security Conduit Plan	SC.CA..05.0	9/6/2005	Kroll	9/9/2005				
Transfer Level Security Conduit Plan	SC.CA..TL.0	9/6/2005	Kroll	9/9/2005				
Sixth Floor Security Conduit Plan	SC.CA..06.0	9/6/2005	Kroll	9/9/2005				
Seventh Floor Security Conduit Plan	SC.CA..07.0	9/6/2005	Kroll	9/9/2005				
Eighth Floor Security Conduit Plan	SC.CA..08.0	9/6/2005	Kroll	9/9/2005				
Ninth Floor Security Conduit Plan	SC.CA..09.0	9/6/2005	Kroll	9/9/2005				
Tenth Floor Security Conduit Plan	SC.CA..10.0	9/6/2005	Kroll	9/9/2005				
Mechanical Penthouse Security Conduit Plan	SC.CA..MP.0	9/6/2005	Kroll	9/9/2005				
Parking First Floor Security Conduit Plan	SC.CA..PG1.0	9/6/2005	Kroll	9/9/2005				
Parking Second Floor Security Conduit Plan	SC.CA..PG2.0	9/6/2005	Kroll	9/9/2005				
Parking Third Floor Security Conduit Plan	SC.CA..PG3.0	9/6/2005	Kroll	9/9/2005				
SECURITY								
Plaza Site Security Plan	SD.CA..S.1	9/6/2005	Kroll	9/9/2005				
Plaza Site Security Plan	SD.CA..S.2	9/6/2005	Kroll	9/9/2005				
Security Device Legend	SD.CA.00.0	9/6/2005	Kroll	9/9/2005				
Security System Block Diagram	SD.CA.00.1	9/6/2005	Kroll	9/9/2005				
Security Door Block Diagram	SD.CA.00.2	9/6/2005	Kroll	9/9/2005				
Security Camera Details	SD.CA.00.3	9/6/2005	Kroll	9/9/2005				
Security Camera Details	SD.CA.00.4	9/6/2005	Kroll	9/9/2005				
Security Central Control Room Details	SD.CA.00.5	9/6/2005	Kroll	9/9/2005				
Security IDF Room Details	SD.CA.00.6	9/6/2005	Kroll	9/9/2005				
Site Plan	SD.CA..S.0		Kroll					Missing
First Floor Security Plan	SD.CA..01.0	9/6/2005	Kroll	9/9/2005				
Second Floor Security Plan	SD.CA..02.0	9/6/2005	Kroll	9/9/2005				
Third Floor Security Plan	SD.CA..03.0	9/6/2005	Kroll	9/9/2005				
Fourth Floor Security Plan	SD.CA..04.0	9/6/2005	Kroll	9/9/2005				
Fifth Floor Security Plan	SD.CA..05.0	9/6/2005	Kroll	9/9/2005				
Transfer Level Security Plan	SD.CA..TL.0	9/6/2005	Kroll	9/9/2005				
Sixth Floor Security Plan	SD.CA..06.0	9/6/2005	Kroll	9/9/2005				
Seventh Floor Security Plan	SD.CA..07.0	9/6/2005	Kroll	9/9/2005				
Eighth Floor Security Plan	SD.CA..08.0	9/6/2005	Kroll	9/9/2005				
Ninth Floor Security Plan	SD.CA..09.0	9/6/2005	Kroll	9/9/2005				
Tenth Floor Security Plan	SD.CA..10.0	9/6/2005	Kroll	9/9/2005				
Mechanical Panthouse Security Plan	SD.CA..MP.0	9/6/2005	Kroll	9/9/2005				
Judges Parking 1st Floor Security Plan	SD.CA..PG1.0	9/6/2005	Kroll	9/9/2005				
Judges Parking 2nd Floor Security Plan	SD.CA..PG2.0	9/6/2005	Kroll	9/9/2005				
Judges Parking 3rd Floor Security Plan	SD.CA..PG3.0	9/6/2005	Kroll	9/9/2005				

Lee County Justice Center: Proposed Courts Addition

SPEC LOG

100% CD, September 6, 2005

Description	Section #	Pages	Date Received
DIVISION 0 - BIDDING REQUIREMENTS, CONTRACT FORMS & CONDITIONS OF THE CONTRACT			
LCJC Construction Contract General Conditions		1-37	9/9/2005
DIVISION 1 - GENERAL REQUIREMENTS			
Summary of Work	01010	1	9/9/2005
Definitions and Standards	01090	1-4	9/9/2005
Allowances	01212	1-2	9/9/2005
Alternates	01230	1-2	9/9/2005
Unit Prices	01270	1-2	9/9/2005
Shop Drawings, Product Data and Samples	01340	1-2	9/9/2005
Quality Control Services (Addendum No. 1)	01400	1-4	9/23/2005
Temporary Facilities	01500	1-6	9/9/2005
Product Requirements	01600	1-8	9/9/2005
Substitution Request Form (Addendum No. 1)	01600A	1-2	9/23/2005
Project Closeout	01700	1-3	9/9/2005
DIVISION 2 - SITEWORK			
Selective Demolition	02070	1-3	9/9/2005
Tree Location	02104	1-2	9/9/2005
Tree Protection	02110	1-2	9/9/2005
Site Furnishings	02140	1-1	9/9/2005
Site Earthwork	02200	1-7	9/9/2005
Demolition	02210	1-6	9/9/2005
Utility Systems Trenching	02222	1-13	9/9/2005
Dewatering	02240	1-7	9/9/2005
Augercast Piles	02362	1-9	9/9/2005
Irrigation	02441	1-8	9/9/2005
Testing of Pressure Piping System	02505	1-5	9/9/2005
Disinfection of Potable Water Piping	02507	1-8	9/9/2005
Asphaltic Concrete Pavement	02513	1-4	9/9/2005
Sidewalks, Driveways, and Curbs	02523	1-8	9/9/2005
Precast Concrete Structures for Utilities	02591	1-15	9/9/2005
Installation of Buried Pressure Piping Systems	02669	1-19	9/9/2005
Storm Drainage Sewerage System	02720	1-3	9/9/2005
Gravity Sanitary Sewerage System	02731	1-20	9/9/2005
Pavers	02783	1-3	9/9/2005
Landscaping	02800	1-10	9/9/2005
Pavement Marking	02840	1-2	9/9/2005
Sodding	02930	1-2	9/9/2005
DIVISION 3 - CONCRETE			
Cast - in - Place Concrete	03300	1-22	9/9/2005
Structural Precast Prestressed Concrete Joists & Soffit Beams	03415	1-7	9/9/2005
Plant Precast Architectural Concrete	03450	1-15	9/9/2005
Lightweight Insulating Concrete Roof Insulation	03520	1-5	9/9/2005
DIVISION 4 - MASONRY			
Unit Masonry (Concrete Masonry)	04200	1-8	9/9/2005
DIVISION 5 - METALS			
Structural Steel	05120	1-6	9/9/2005
Steel Joists	05210	1-7	9/9/2005
Steel Deck	05310	1-3	9/9/2005
Cold-Formed Metal Framing	05400	1-13	9/9/2005
Metal Fabrications	05500	1-16	9/9/2005
Metal Stairs	05511	1-10	9/9/2005
Ornamental Railing System	05721	1-3	9/9/2005
Expansion Joint Systems	05811	1-10	9/9/2005
DIVISION 6 - WOOD & PLASTICS			
Rough Carpentry	06100	1-9	9/9/2005
Interior Architectural Woodwork	06402	1-16	9/9/2005

Lee County Justice Center: Proposed Courts Addition

SPEC LOG

100% CD, September 6, 2005

Description	Section #	Pages	Date Received
DIVISION 7 - THERMAL & MOISTURE PROTECTION			
Bituminous Dampproofing	07115	1-3	9/9/2005
Bentonite Waterproofing	07170	1-6	9/9/2005
Traffic Coatings	07180	1-7	9/9/2005
Building Insulation	07210	1-7	9/9/2005
Cementitious Fireproofing	07255	1-5	9/9/2005
SBS-Modified Bitumen Membrane Roofing	07552	1-17	9/9/2005
Sheet Metal Flashing and Trim	07620	1-10	9/9/2005
Roof Accessories	07720	1-9	9/9/2005
Joint Sealers	07900	1-5	9/9/2005
DIVISION 8 - DOORS AND WINDOWS			
Steel Doors and Frames	08110	1-6	9/9/2005
Flush Wood Doors	08211	1-5	9/9/2005
High Speed Rolling Doors	08300	1-5	9/9/2005
Security Steel Doors and Frames	08322	1-8	9/9/2005
Overhead Coiling Doors (Addendum No. 3)	08331	1-6	10/3/2005
Overhead Door/Security System Interface	08333	1-5	9/9/2005
Overhead Coiling Grilles	08334	1-7	9/9/2005
Aluminum Entrances and Storefronts	08410	1-6	9/9/2005
Automatic Entrance Doors	08461	1-7	9/9/2005
Revolving Entrance Doors	08470	1-12	9/9/2005
Finish Hardware	08710	1-22	9/9/2005
Glazing	08800	1-9	9/9/2005
Glazed Aluminum Curtain Walls	08920	1-12	9/9/2005
DIVISION 9 - FINISHES			
Portland Cement Plaster	09220	1-10	9/9/2005
Gypsum Board Assemblies	09255	1-12	9/9/2005
Security Wall Systems	09260	1-4	9/9/2005
Gypsum Board Shaft Wall Systems	09275	1-5	9/9/2005
Ceramic Tile (Addendum No. 1)	09310	1-6	9/23/2005
Acoustical Panel Ceiling	09511	1-7	9/9/2005
Resilient Tile Flooring	09651	1-5	9/9/2005
Resilient Wall Base and Accessories	09653	1-5	9/9/2005
Carpet and Carpet Tile	09680	1	9/9/2005
Acoustical Wall Systems	09841	1-4	9/9/2005
Painting	09900	1-7	9/9/2005
DIVISION 10 - SPECIALTIES			
Visual Display Surfaces	10101	1-8	9/9/2005
Toilet Compartments	10155	1-4	9/9/2005
Metal Wall Louvers and Architectural Screens (Addendum No. 3)	10200	1-6	10/3/2005
Impact Resistant Wall Protection	10265	1-7	9/9/2005
Raised Access Floor System	10270	1-3	9/9/2005
Flagpoles	10350	1-5	9/9/2005
Building Clock	10437	1-5	9/9/2005
Metal Lockers	10505	1-10	9/9/2005
Fire Protection Specialties	10520	1-6	9/9/2005
Protective Covers	10530	1-5	9/9/2005
Aluminum Sun Shade	10700	1-2	9/9/2005
Toilet and Bath Accessories	10801	1-8	9/9/2005
DIVISION 11 - EQUIPMENT			
Projection Screens	11132	1-4	9/9/2005
Turnstiles and Bi-Directional Motorized Gates	11191	1-4	9/9/2005
Residential Appliances	11452	1-3	9/9/2005
DIVISION 12 - FURNISHINGS			
Floor Grids	12485	1-2	9/9/2005
Roller Shades	12494	1-8	9/9/2005
Horizontal Louver Blinds	12511	1-4	9/9/2005
Fixed Wooden Blinds	12610	1-4	9/9/2005
Pews and Benches (Addendum No. 3)	12670	1-3	10/3/2005
DIVISION 13 - SPECIAL CONSTRUCTION - NOT USED			
Security Systems (Addendum No. 3)	13700	1-44	10/3/2005
Unit Pricing Schedules (Addendum No. 2)	13700A-F	1-8	9/26/2005

Lee County Justice Center: Proposed Courts Addition

SPEC LOG

100% CD, September 6, 2005

Description	Section #	Pages	Date Received
DIVISION 14 - CONVEYING SYSTEMS			
Electric Traction Elevators	14210	1-9	9/9/2005
Elevators / Security System Interface (Addendum No. 3)	14215	1-7	10/3/2005
Escalators	14310	1-6	9/9/2005
Accessibility Lifts (Inclined) (Addendum No. 3)	14420	1-5	10/3/2005
Accessibility Lifts (Vertical)	14421	1-6	9/9/2005
DIVISION 15 - MECHANICAL			
Basic Mechanical Requirements	15010	1-22	9/9/2005
Electrical Requirements for Mechanical Equipment	15030	1-5	9/9/2005
Variable Frequency Drives	15035	1-12	9/9/2005
Basic Mechanical Materials and Methods	15050	1-17	9/9/2005
Pipe and Fittings	15060	1-12	9/9/2005
Valves	15100	1-11	9/9/2005
Piping Specialties	15120	1-9	9/9/2005
Pumps	15160	1-5	9/9/2005
Vibratoin Isolation	15240	1-9	9/9/2005
Thermal insulation	15250	1-17	9/9/2005
Fire Protection	15300	1-10	9/9/2005
Clean Agent Fire Extinguishing System	15320	1-8	9/9/2005
Fire Pump	15380	1-6	9/9/2005
Plumbing Piping System	15410	1-6	9/9/2005
Plumbing Fixtures	15440	1-6	9/9/2005
Plumbing Equipment	15450	1-6	9/9/2005
Fuel Piping System	15483	1-3	9/9/2005
Hydronic Piping System	15510	1-6	9/9/2005
Computer Room Air Conditioning Unit	15785	1-4	9/9/2005
Air Handling Unit	15800	1-9	9/9/2005
Fans	15860	1-5	9/9/2005
Air Distribution	15880	1-5	9/9/2005
Air Filter	15885	1-5	9/9/2005
Ductwork	15890	1-11	9/9/2005
Ductwork Specialties	15910	1-12	9/9/2005
Terminal Unit	15930	1-5	9/9/2005
Building Control System (Addendum No. 3)	15950	1-37	10/3/2005
Performance Verification	15990	1-10	9/9/2005
DIVISION 16 - ELECTRICAL			
Basic Electrical Requirements	16010	1-17	9/9/2005
Test and Performance Verification	16020	1-6	9/9/2005
Electrical Identification	16030	1-6	9/9/2005
Raceways and Conduits	16110	1-12	9/9/2005
Wires and Cables (600V and Below)	16120	1-5	9/9/2005
Outlet Boxes	16130	1-3	9/9/2005
Wiring Devices	16140	1-8	9/9/2005
Distribution Switchboards	16425	1-8	9/9/2005
Grounding	16450	1-4	9/9/2005
Transformers	16460	1-2	9/9/2005
Feeder Busducts	16465	1-6	9/9/2005
Panelboards	16470	1-5	9/9/2005
Safety Switches	16476	1-3	9/9/2005
Individually Enclosed Circuit Breakers	16477	1-3	9/9/2005
Motor Controllers	16481	1-7	9/9/2005
Automatic Transfer Switch	16490	1-4	9/9/2005
Lighting	16500	1-5	9/9/2005
Architectural Lighting Dimming System	16555	1-4	9/9/2005
Uninterruptible Power System	16610	1-6	9/9/2005
Exterior Engine Generator	16655	1-12	9/9/2005
Lighting Protection Systems	16670	1-5	9/9/2005
Transient Voltage Surge Suppressors	16709	1-12	9/9/2005
Addressable Fire Alarm System	16720	1-22	9/9/2005
Fire Alarm Security Interface	16725	1-4	9/9/2005
Installation of Lighting Control Panels (Addendum No. 3)	16940	1-3	10/3/2005
DIVISION 16 - TECHNICAL			
Systems General Provisions	17010	1-14	9/9/2005
Pathways and Spaces for Structured Cabling System	17110	1-11	9/9/2005
Cable Plant - Structured Cabling System	17120	1-22	9/9/2005
Combined Low Voltage / Power Floor Boxes	17130	1-5	9/9/2005
Grounding and Bonding for Telecommunications Systems	17450	1-4	9/9/2005
ADDITIONAL INFORMATION			
Addendum No. 1			9/23/2005
Addendum No. 2			9/27/2005
Addendum No. 3			9/29/2005
END OF DOCUMENT			